

**Addenda 1**

FEDERAL PROJECT NO: 1026(104)

STATE PROJECT NO: 26-118

REPLACEMENT OF BRIDGE NO. 02695

1346

ROUTE 148 OVER GREAT BROOK

IN THE TOWN OF CHESTER

PROJECT NO(S). 0026-0118

PROJECT NO(S).

DATE OF BID OPENING NOVEMBER 02, 2011 TIME: 2:00 PM **NO BIDS WILL BE ACCEPTED AFTER 2:00 PM. "NO EXCEPTIONS"**

NOTE:--THE BIDDER SHALL FILL IN, UNDER THE COLUMN "UNIT PRICES BID", THE UNIT PRICES, WRITTEN IN WORDS AND IN NUMBERS, FOR WHICH HE PROPOSES TO PERFORM THE VARIOUS ITEMS OF WORK CALLED FOR, AND UNDER THE COLUMN HEADED "AMOUNT, THE AMOUNT OF EACH OF THE ITEMS AT THE UNIT PRICE BID. AFTER THE PROPOSAL IS OPENED AND READ THE QUANTITIES WILL BE EXTENDED AND TOTALED IN ACCORDANCE WITH THE PRICES BID AND THE BID WILL BE VERIFIED OR CORRECTED.

ITEM NUMBER	ITEMS	UNIT	APPROX. QUANTITIES	UNIT PRICES BID		AMOUNT (FIGURES)
				FIGURES	WRITING	
0201001	CLEARING AND GRUBBING	l.s.				
0202002	EARTH EXCAVATION	cu.m	770			
0202202	CHANNEL EXCAVATION-EARTH	cu.m	300			
0202529	CUT BITUMINOUS CONCRETE PAVEMENT	m	110			
0202531	REMOVAL OF BITUMINOUS CONCRETE	sq.m	135			
0202911A	CONDITION SURVEY (SITE NO. 1)	l.s.				
0203202	STRUCTURE EXCAVATION-EARTH (EXCLUDING COFFERDAM AND DEWATERING)	cu.m	1100			
0204001	COFFERDAM AND DEWATERING	m	160			
0204151A	HANDLING WATER	l.s.				
0205001	TRENCH EXCAVATION 0 - 1.2 M DEEP	cu.m	60			
0205002	ROCK IN TRENCH EXCAVATION 0 - 1.2 M DEEP	cu.m	3			
0205003	TRENCH EXCAVATION 0 - 3 M DEEP	cu.m	791			
0205005	TRENCH EXCAVATION 0 - 4.5 M DEEP	cu.m	26			
0209001	FORMATION OF SUBGRADE	sq.m	1560			
0210820	WATER POLLUTION CONTROL	est/pls		\$1500	ONE THOUSAND FIVE HUNDRED DOLLARS AND NO CENTS	\$1500
0212002	SUBBASE	cu.m	390			
0213012	GRANULAR FILL	cu.m	275			
0216002	PERVIOUS STRUCTURE BACKFILL	cu.m	345			
0219001	SEDIMENTATION CONTROL SYSTEM	m	320			
0304002	PROCESSED AGGREGATE BASE	cu.m	11			
0406170	HMA S1	t	594			
0406171	HMA S0.5	t	302			
0406236	MATERIAL FOR TACK COAT	L	850			
0406303A	SAWING AND SEALING JOINTS	m	25			
0503890A	REMOVAL OF EXISTING BRIDGE	l.s.				
0507006	TYPE "C" CATCH BASIN TOP	ea.	2			
0507026	TYPE "C" CATCH BASIN (1.2 M SUMP)	ea.	1			
0507056	TYPE "C" CATCH BASIN DOUBLE GRATE TYPE II (1.2 M SUMP)	ea.	2			
0507148	TYPE "C-L" CATCH BASIN (1.8 M SUMP)	ea.	1			
0507601	MANHOLE	ea.	2			

NOT FOR BID SUBMISSION

This bid includes addenda no(s):

Kindly insert here the total amount of your Bid \$

DATE OF BID OPENING NOVEMBER 02, 2011 TIME: **NO BIDS WILL BE ACCEPTED AFTER 2:00 PM. "NO EXCEPTIONS"**

NOTE:--THE BIDDER SHALL FILL IN, UNDER THE COLUMN "UNIT PRICES BID", THE UNIT PRICES, WRITTEN IN WORDS AND IN NUMBERS, FOR WHICH HE PROPOSES TO PERFORM THE VARIOUS ITEMS OF WORK CALLED FOR, AND UNDER THE COLUMN HEADED "AMOUNT, THE AMOUNT OF EACH OF THE ITEMS AT THE UNIT PRICE BID. AFTER THE PROPOSAL IS OPENED AND READ THE QUANTITIES WILL BE EXTENDED AND TOTALLED IN ACCORDANCE WITH THE PRICES BID AND THE BID WILL BE VERIFIED OR CORRECTED.

ITEM NUMBER	ITEMS	UNIT	APPROX. QUANTITIES	UNIT PRICES BID		AMOUNT (FIGURES)
				FIGURES	WRITING	
0513007	100 MM POLYVINYL CHLORIDE PLASTIC PIPE	m	15			
0513009	150 MM POLYVINYL CHLORIDE PIPE	m	2			
0601003	CLASS "A" CONCRETE	cu.m	124			
0601091A	SIMULATED STONE MASONRY	sq.m	165			
0601108A	CONCRETE STAIRS	l.s.				
0601126A	3600MM X 1500MM PRECAST CONCRETE BOX CULVERT	m	22			
0601138A	3600MM X 2100MM PRECAST CONCRETE BOX CULVERT	m	22			
0602002	DEFORMED STEEL BARS	kg	5600			
0602910A	DRILLING HOLES AND GROUTING DOWELS	ea.	58			
0651001	BEDDING MATERIAL	cu.m	10			
0651011	300 MM R.C. PIPE	m	15			
0651013	450 MM R.C. PIPE	m	38			
0651393	300 MM X 450 MM A.C.C.M. PIPE-ARCH	m	4			
0652009	300 MM R.C. CULVERT END	ea.	1			
0652011	450 MM R.C. CULVERT END	ea.	1			
0653001	CLEAN EXISTING CATCH BASIN	ea.	1			
0653100	CLEAN EXISTING CULVERT 300 MM TO 1050 MM DIAMETER	m	42			
0703012	MODIFIED RIPRAP	cu.m	85			
0707001A	MEMBRANE WATERPROOFING (WOVEN GLASS FABRIC)	sq.m	190			
0708001	DAMPPROOFING	sq.m	90			
0714050A	TEMPORARY EARTH RETAINING SYSTEM	sq.m	8			
0725002	BAGGED STONE	bag	48			
0811001	CONCRETE CURBING	m	63			
0815001	BITUMINOUS CONCRETE LIP CURBING	m	175			
0822001	TEMPORARY PRECAST CONCRETE BARRIER CURB	m	43			
0904049A	TWO-TUBE BRIDGE RAIL	m	23			
0909500A	TIMBER GUIDE RAIL	m	40			
0910169	METAL BEAM RAIL (TYPE R-B 350 SYSTEM 6)	m	25			
0911924	R-B END ANCHORAGE TYPE II	ea.	1			
0912503	REMOVE METAL BEAM RAIL	m	40			
0912602A	RESET METAL BEAM RAIL	m	23			

NOT FOR BID SUBMISSION

This bid includes addenda no(s):

Kindly insert here the total amount of your Bid \$

FEDERAL PROJECT NO: 1026(104)  
 REPLACEMENT OF BRIDGE NO. 02695  
 ROUTE 148 OVER GREAT BROOK

STATE PROJECT NO: 26-118

1346

IN THE TOWN OF CHESTER

PROJECT NO(S): 0026-0118

PROJECT NO(S):

DATE OF BID OPENING NOVEMBER 02, 2011 TIME: **NO BIDS WILL BE ACCEPTED AFTER 2:00 PM. "NO EXCEPTIONS"**

NOTE:--THE BIDDER SHALL FILL IN, UNDER THE COLUMN "UNIT PRICES BID", THE UNIT PRICES, WRITTEN IN WORDS AND IN NUMBERS, FOR WHICH HE PROPOSES TO PERFORM THE VARIOUS ITEMS OF WORK CALLED FOR, AND UNDER THE COLUMN HEADED "AMOUNT, THE AMOUNT OF EACH OF THE ITEMS AT THE UNIT PRICE BID. AFTER THE PROPOSAL IS OPENED AND READ THE QUANTITIES WILL BE EXTENDED AND TOTALLED IN ACCORDANCE WITH THE PRICES BID AND THE BID WILL BE VERIFIED OR CORRECTED.

ITEM NUMBER	ITEMS	UNIT	APPROX. QUANTITIES	UNIT PRICES BID		AMOUNT (FIGURES)
				FIGURES	WRITING	
0917010A	REPAIR GUIDERAIL	est.		\$1000	ONE THOUSAND DOLLARS AND NO CENTS	\$1000
0921001A	CONCRETE SIDEWALK	sq.m	220			
0922501	BITUMINOUS CONCRETE DRIVEWAY	sq.m	545			
0922503A	GRAVEL DRIVEWAY	sq.m	48			
0925101A	RELAY BRICK WALK	sq.m	3			
0939001	SWEEPING FOR DUST CONTROL	hr	160			
0943001	WATER FOR DUST CONTROL	k1	2000			
0944002	FURNISHING AND PLACING TOPSOIL	sq.m	1060			
0949000	WOOD CHIP MULCH	sq.m	145			
0949085	CLETHRA ALNIFOLIA SUMMERSWEET 460 MM - 610 MM HT. B.B.	ea.	10			
0949088	COMPTONIA PEREGRINA SWEETFERN 305 MM - 380 MM HT. B.B.	ea.	15			
0949098	CORNUS SERICEA, REDOSIER DOGWOOD 460 MM-610 MM HT. CONTAINER	ea.	13			
0949161	ILEX GLABRA "COMPACTA" COMPACT INKBERRY 460 MM-610 MM HT. B.B.	ea.	10			
0949212	ARONIA MELANOCARPA - BLACK CHOKEBERRY 460MM - 610MM HT. B.B.	ea.	7			
0949324	LINDERA BENZOIN, COMMON SPICEBUSH 460 MM - 610 MM HT. B.B.	ea.	20			
0949977	QUERCUS PALUSTRIS PIN OAK 45 MM - 50 MM CAL. B.B.	ea.	8			
0950005	TURF ESTABLISHMENT	sq.m	1060			
0952051A	CONTROL AND REMOVAL OF INVASIVE VEGETATION	sq.m	900			
0969062A	CONSTRUCTION FIELD OFFICE, MEDIUM	mo.	8			
0970006A	TRAFFICPERSON (MUNICIPAL POLICE OFFICER)	est.		\$30000	THIRTY THOUSAND DOLLARS AND NO CENTS	\$30000
0971001A	MAINTENANCE AND PROTECTION OF TRAFFIC	l.s.				
0975002	MOBILIZATION	l.s.				
0976002	BARRICADE WARNING LIGHTS HIGH INTENSITY	day	500			
0977001	TRAFFIC CONE	ea.	40			
0978002	TRAFFIC DRUM	ea.	40			
0979003A	CONSTRUCTION BARRICADE TYPE III	ea.	12			

NOT FOR BID SUBMISSION

This bid includes addenda no(s):

Kindly insert here the total amount of your Bid \$

