# 6030 BID ADDENDUM

Page 1 of 2

**ADDENDUM NO.: 1** 

DATE OF ADDENDUM: 29 April 2013

## Roof, Window, Coping & Exterior repair 410-470 Capitol Avenue Hartford, CT BI-2B-280

Original Bid Due Date / Time:

May 1, 2013

1:00 P.M.

Revised Bid Due Date / Time:

May 7, 2013

1:00 P.M.

Previous Addendums: N/A

### TO: Prospective Bid Proposers:

This Addendum forms part of the "Contract Documents" and modifies or clarifies the original "Contract Documents" for this Project dated 15 January 2013. Prospective Bid Proposers shall acknowledge receipt of the total number the Addenda issued for this Project on the space provided on Section 00 41 00 Bid Proposal Form. Failure to do may subject Bid Proposers to disqualification.

The following clarifications are applicable to drawings and specifications for the project referenced above.

#### Item 1

The bid opening will be changed from May 1, 2013, 1:00 P.M. to May 8, 2013, 1:00 P.M.

#### Item 2

In Section 07 22 00, Paragraph 2.6 - Building 450 - Roof A, D, E, F, G and H

**Clarification:** Item 4 Tapered (insulation) to be 1/8-inch per foot as indicated. Drawing D1.1 indicates existing deck to be sloped 1/8-inch per foot. Existing deck slope and new insulation slope combined results in the 1/4inch per foot pitch indicated on Drawing A1.2.

#### Item 3

In Section 07 56 00, Paragraph 2.1 – Membrane Flashing System

Clarification: Change paragraph title to "Membrane Flashing and Roofing System".

### Item 4

Drawing D1.1, Scope of Roofing Removals

Clarification: Roof A, D, E, F G and H, and Building 410 Bridge - Insulation to be removed in conjunction with the inverted roof membrane assembly to be indicated as 2-inch.

#### Item 5

Drawing A3.7, Detail 1/A3.7

Clarification: Existing aluminum wall panels require removal and reinstallation as indicated to facilitate installation of new liquid-applied roofing system.

#### **End of Addendum**



# 6030 **BID ADDENDUM**

Page 2 of 2

**ADDENDUM NO.: 1** 

DATE OF ADDENDUM: 29 April 2013

David Busanet, Bidding & Contracts Supervisor Department of Administrative Services

On Behalf of the Department of Construction Services