TOWN OF ORANGE
BOARD OF EDUCATION

Boiler/Unit Vent. Replacement
RACE BROOK SCHOOL
107 Grannis Road
STATE PROJECT
TMP-107-QGCV

CODE INFORMATION

DATE OF ORIGINAL CONSTRUCTION: 1959
DATE OF ADDITIONS: 2005

1. USE GROUP CLASSIFICATION:
   (PRIMARY): E – EDUCATION
   (INCIDENTAL) A2 – ASSEMBLY
   A4 – ASSEMBLY
2. CONSTRUCTION TYPE (601):
   MINIMUM TYPE REQUIRED: IIB
   ACTUAL TYPE PROVIDED: (EXISTING) IIB
   (NEW) IIB
3. BUILDING HEIGHT (501.0 – 503.0):
   ALLOWABLE HEIGHT (STORY/FEET): 3/ 30
   ACTUAL HEIGHT (STORY/FEET): 1 / 30
   STORIES ABOVE GRADE: 2
4. BUILDING AREA (501.0 – 503.0):
   GROSS BUILDING AREA (FIRST FLOOR):
   EXISTING CONSTRUCTION 55,984 S.F.
   NEW CONSTRUCTION 0 S.F.
   TOTAL FLOOR 55,984 S.F.
5. AREA MODIFICATIONS TO TABLE 503

OPEN PERIMETER:	NORTH	N/A
	EAST	N/A
	SOUTH	N/A
	WEST	N/A
TOTAL OPEN PERIMETER:		N/A
TOTAL PERIMETER:		N/A
% INCREASE FOR OPEN PERIMETER:		N/A
(OPEN / TOTAL – .25) X 200 =		
% OF ALLOWABLE TABULAR AREA (TABLE 503)		N/A
% REDUCTION FOR HEIGHT (506.4)		N/A
% INCREASE FOR OPEN PERIMETER (506.2)		N/A
% INCREASE FOR FULL FIRE SUPPRESSION		N/A

TOTAL PERCENTAGE FACTOR

CONVERSION FACTOR (% FACTOR/100)	N/A
A) ADJUSTED TABULAR AREA:	N/A
B) TABULAR AREA (TABLE 503)	N/A
C) ACTUAL AREA / FLOOR	N/A

6. SINGLE OCCUPANCY OR NON–SEPARATED USES(302.3.1)

a) ADJUSTED BUILDING AREA
(actual building area) + (conversion factor) = N/A sq.ft.

b) ALLOWABLE AREA per floor (Aa)
(conversion factor) × (tabular area Table 503) = N/A sq.ft.

c) ACTUAL BUILDING AREA (each floor of each building) = N/A sq.ft.

d) TOTAL FLOOR AREA (all stories) = N/A sq.ft.

e) ALLOWABLE FLOOR AREA (all stories)
allowable area per floor (Aa) × number of stories (maximum 3) = N/A sq.ft.

7. MIXED OCCUPANCY SEPARATED USES(302.3.2) (Allowable Area 506.4)

(Use Group A–2)(Use Group A–4) (Use Group E)

Σ Actual Area / Allowable Area + Actual Area / Allowable Area + Actual Area / Allowable Area = ≤ 1

Σ 2,484 / 28,500 + 3,480 / 28,500 + 50,020 / 58,000 = ≤ 1

.08 + .122 + .86 = 1.062

a) ALLOWABLE AREA per floor (Aa)
(conversion factor) × (tabular area, Table 503) = N/A sq.ft.

b) TOTAL FLOOR AREA (all stories) = 55,984 sq.ft.

c) ALLOWABLE FLOOR AREA (all stories)

Σ (Use Group_____) Actual Area / Allowable Area + (Use Group_____) Actual Area / Allowable Area + (Use Group_____) Actual Area / Allowable Area + (Use Group_____) Actual Area / Allowable Area + (Use Group_____) Actual Area / Allowable Area = ≤ 3 N/A

Σ _____ + _____ + _____ + _____ + _____ = N/A

8. FIRE RESISTANCE RATING OF STRUCTURAL ELEMENTS (602)

1)	Structural Frame: including columns, girders, trusses	0 hr
2)	Bearing Walls: (Exterior)	0 hr
	(Interior)	0 hr
3)	Nonbearing walls and partitions (Exterior)	0 hr
4)	Nonbearing walls and partitions (Interior)	0 hr
5)	Floor Const.: including supporting beams and joists	0 hr
6)	Roof Const.: including supporting beams and joists	0 hr

9. OCCUPANCY LOAD

DESIGN TOTALS:	BASEMENT FLOOR:	0
	FIRST FLOOR:	1783
	SECOND FLOOR:	0
TOTAL EXIT CAPACITY:	BASEMENT FLOOR:	0
	FIRST FLOOR:	8390
	SECOND FLOOR:	0
DESIGN TOTAL FOR BUILDING:		1783
TOTAL EXIT CAPACITY OF FACILITY:		8390

10. MODIFICATIONS

NO MODIFICATIONS REQUESTED FOR

11. ACCESSIBLE BUILDING

NON–DESIGNATED

12. MINIMUM PLUMBING FIXTURE COUNT (I.P.C. CHAPTER 4) FOR EACH TYPE OF OCCUPANCY FOR EACH SEPARATE BUILDING OR ENTIRE FACILITY.

		Required	Provided
Group A Occupancy:	W/C Male	4	4
(Design Load A–2 = 175)	W/C Female	7	7
(Design Load A–4 = 468)	Lav	5	5
	D/F	2	2

		Required	Provided
Group E Occupancy:			
(Design Load = 1015	W/C	11	15
	Lav	11	15
	D/F	1	0

13. ENTIRE BUILDING SPRINKLERED Yes [X] No [ ]
14. THRESHOLD BUILDING Yes [X] No [ ]

15. CODES TO WHICH THIS BUILDING WAS DESIGNED

CODES TO WHICH THIS SPACE WAS DESIGNED

2009 CONNECTICUT STATE BUILDING CODE (CSBC)
– INTERNATIONAL BUILDING CODE / 2003 (ICC)
– INTERNATIONAL MECHANICAL CODE / 2003 (ICC)
– INTERNATIONAL PLUMBING CODE / 2003 (ICC)
– NATIONAL ELECTRIC CODE, NFPA 70 / 2005 (NEC)
– INTERNATIONAL ENERGY CONSERVATION CODE / 2009 (IECC)
ICC / ANSI A117.1
ACCESSIBLE AND USABLE BUILDINGS AND FACILITIES (ANSI)
CONNECTICUT AMMENDMENTS / 2009 / STATE BUILDING CODE

2005 CONNECTICUT STATE FIRE CODE (CSFSC)
– INTERNATIONAL FIRE CODE / 2003 (ICC)
– NATIONAL FIRE PROTECTION ASSOCIATION 1
UNIFORM FIRE CODE / 2003 (NFPA 1)
CONNECTICUT AMMENDMENTS / 2009 / STATE FIRE SAFETY CODE

2005 CONNECTICUT STATE ELEVATOR CODE (AS REF IN IBC)
– ASME A17.1 – 2000 SAFETY CODE FOR ELEVATORS AND ESCALATORS

16. BUILDING AREA FOR GRANT CALCULATIONS (ENTIRE FACILITY)
Per State Building Code Definition "Area, Building" (to interior face of exterior walls)

Existing Construction prior to this project	54,349	sq.ft.
Existing being demolished and removed	(–)	sq.ft.
Total new construction for this project	0	sq.ft.
Total building area	54,349	sq.ft.

Open areas; floor openings and areas under projections (list separately, must reconcile with areas shown on code plan).

Building space	0	sq.ft.
Building space	0	sq.ft.

Total constructed building area (to exterior face of exterior walls, a.k.a. "contractor building area") 55,984 sq.ft.

GENERAL NOTES

1. EXISTING CONDITIONS SHALL BE VERIFIED PRIOR TO BID & CONSTRUCTION. DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT IN WRITING. THE ARCHITECT WILL CLARIFY ANY DISCREPANCIES VIA ADDENDUM OR WRITTEN RESPONSE.
2. SEAL ALL PENETRATIONS MADE IN EXISTING 1 HOUR RATED WALLS AS SHOWN ON DRAWING RB–A101, RB–A102, RB–A103.
3. WHERE EXISTING CONSTRUCTION IS REMOVED PATCH ALL AREAS WITH MATERIALS CONSISTENT WITH EXISTING INCLUDING ADJACENT SURFACES. MATCH AND BLEND PATCHED AREAS INTO EXISTING. REFER TO SPECIFICATIONS.

LIST OF DRAWINGS

ARCHITECTURAL

RB–A100	COVER SHEET
RB–EG101	EGRESS PLAN
RB–A101	PARTIAL FLOOR PLAN UNIT VENTILATORS
RB–A102	PARTIAL FLOOR PLAN UNIT VENTILATORS
RB–A103	PARTIAL FLOOR PLAN UNIT VENTILATORS

MECHANICAL

RB–M101	PARTIAL FLOOR PLAN MECHANICAL
RB–M102	PARTIAL FLOOR PLAN MECHANICAL
RB–M103	PARTIAL FLOOR PLAN MECHANICAL
RB–M104	PARTIAL FLOOR PLAN MECHANICAL
RB–M105	BOILER ROOM PLAN DEMOLITION MECHANICAL
RB–M106	BOILER ROOM PLAN MECHANICAL
RB–M107	SCHEDULES AND DETAILS MECHANICAL

ELECTRICAL

RB–EG1	GENERAL NOTES, SYMBOL LEGENDS, ABBREVIATIONS AND DRAWING LISTS
RB–E100	LUMINAIRE AND MECH EQUIPMENT WIRING SCHEDULE, DETAILS & NOTES
RB–ED101	ELECTRICAL DEMOLITION PLAN BOILER ROOM
RB–E101	PARTIAL FLOOR PLAN ELECTRICAL
RB–E102	PARTIAL FLOOR PLAN ELECTRICAL
RB–E103	PARTIAL FLOOR PLAN ELECTRICAL
RB–E104	ELECTRICAL PLAN BOILER ROOM

ROSE •TISO & Co. LLC.
ARCHITECTS • SURVEYORS • ENGINEERS
WWW.ROSETISO.COM
35 BRENTWOOD AVENUE, FAIRFIELD, CT 06825
TEL: (203)610-6262 • FAX: (203)610-6404

MUSCO ENGINEERING ASSOCIATES
375 Morgan Lane, Unit 307
West Haven, CT 06516
(203) 932–1901 FAX (203) 931–1550
www.muscoengineering.com

Facility Support Services, LLC
Environmental & Safety Consulting Engineers

ISSUED FOR BID:
11–01–13
JOB NO. : 1605



CODE REFERENCE PLAN LEGEND

- CLASSROOM / ART — ROOM NAME, ROOM USE
- 101 — ROOM NUMBER
- ★ — ASSEMBLY OCCUPANCY, TWO MEANS OF EGRESS REQUIRED
- 800 SF / 20 = 40p — ROOM OCCUPANCY LOAD; AREA IN SQUARE FEET; OCCUPANCY LOAD FACTOR
- 72 / 230 — EXIT CAPACITY; ACTUAL EGRESS OCCUPANCY OF DOOR OR STAIR; MAXIMUM ALLOWABLE EGRESS OCCUPANCY OF DOOR OR STAIR
- 84 → — DIRECTION OF TRAVEL WITH ACCUMULATED OCCUPANCY LOAD
- 84' → — MAXIMUM TRAVEL DISTANCE FROM FURTHEST POINT
- ♿ — ACCESSIBLE AREA OR EXIT
- EXISTING 1 HOUR FIRE RATED WALL – UL DESIGN # UL906 (TIGHT TO DECK ABOVE); 1 HOUR FIRE WALL WHERE NOTED

FLOOR AREA	= 55,984
NEW CONSTRUCTION	= 0
TOTAL FLOOR AREA	= 55,984
OCCUPANCY LOAD	= 1,793
EXIT CAPACITY	= 8,740

(37 DOORS @ 34" EACH x 170 EGRESS CAPACITY PER EACH DOOR) + (7 DOORS @ 60" EACH x 350 EGRESS CAPACITY PER EACH DOOR) = 8,740 TOTAL EXIT CAPACITY

ROSE •TISO & CO. LLC.
ARCHITECTS ● SURVEYORS ● ENGINEERS
WWW.ROSETISO.COM
35 BRENTWOOD AVENUE, FAIRFIELD, CT 06825
TEL: (203)610-6262 ● FAX: (203)610-6404

REVISIONS			
NO.	BY	DATE	DESCRIPTION

PROJECT TITLE

RACE BROOK SCHOOL
107 GRANNIS ROAD
ORANGE, CT
STATE PROJECT NO:
TMP-107-QGCV

BOILER AND UNIT VENT. REPLACEMENTS

ORANGE CONNECTICUT 1822 TOWN SEAL

Prepared For:

TOWN OF ORANGE, CT
637 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE

EGRESS PLAN

DESIGNED BY: TG	SCALE: AS NOTED
DRAWN BY: TG	DATE: 07-02-13
CHECKED BY: PR	PROJECT NUMBER: 1605
CAD FILE: R:/1605/ARCH	

SEAL

SHEET NUMBER

RB-EG101



KEY PLAN
SCALE: N.T.S.

UNIT VENTILATOR FLOOR PLAN
SCALE: 1/8" = 1'-0"

GENERAL NOTES:

1. THE INFORMATION SHOWN ON THIS DRAWING IS BASED UPON THE INFORMATION SHOWN ON THE BUILDING PLANS AND LIMITED FIELD INVESTIGATIONS AND MAY OR MAY NOT REFLECT ACTUAL FIELD CONDITIONS. THIS CONTRACTOR SHALL VERIFY THE INFORMATION INDICATED ON THIS DRAWING AND NOTIFY THE ENGINEER OF ANY DISCREPANCIES PRIOR TO SUBMITTING HIS BID.
2. THIS CONTRACTOR IS REQUIRED TO PERFORM THIS WORK IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, ORDINANCES, ETC., AND TO MEET THE REQUIREMENTS OF THE LOCAL AUTHORITIES HAVING JURISDICTION AND OWNER, WHETHER OR NOT SPECIFICALLY INDICATED OR SPECIFIED ON THIS DRAWING.
3. THE CONTRACTOR SHALL SEAL ALL PENETRATIONS THROUGH SMOKE AND/OR FIRE RATED PARTITIONS AND SLABS WITH A U.L. LISTED SMOKE AND/OR FIRE STOP TO MAINTAIN THE INTEGRITY OF THE FIRE AND/OR SMOKE RATING. PROVIDE SHOP DRAWINGS FOR ALL PENETRATIONS. REFER TO ELECTRICAL SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.

CODE REFERENCE LEGEND:

EXISTING 1 HOUR FIRE RATED WALL
UL DESIGN # UL906
(TIGHT TO DECK ABOVE)
1 HOUR FIRE WALL WHERE NOTED

CONSTRUCTION NOTES:

1. PROVIDE NEW M.O. TO ACCOMMODATE NEW UV4 LOUVER. INSTALL NEW BACKER-ROD, AND SEALANT. (SEE DRAWING RB-A101 FOR DETAILS)
2. NEW UV4 WILL REQUIRE EXISTING RADIATOR TUBE/FINS, AND COVER TO BE "CUT-BACK" TO ACCOMMODATE FOR THE LAGER SIZED NEW UV4
3. PROVIDE NEW M.O. FOR NEW UV2 LOUVER. INSTALL NEW LOUVER, BACKER-ROD, AND SEALANT. SEE DRAWING RB-A101 FOR DETAILS
4. NEW UV2 WILL REQUIRE EXISTING RADIATOR TUBE/FIN, AND COVER TO BE "CUT-BACK" TO ACCOMMODATE FOR LARGER SIZE NEW UV2
5. REMOVE EXISTING FINISH FLOOR AND TRENCH CONCRETE SLAB TO ALLOW NEW PIPING TO BE PLACED IN TRENCH. FILL TRENCH WITH CONCRETE, REPLACE FLOORING WITH NEW MATCHING VCT FLOORING.
6. REMOVE (4) 24" SECTIONS OF CABINET AND COUNTERTOP, STARTING FROM EGRESS DOOR. COUNTER TOP EDGE TO BE FLUSHED WITH CABINET END PANEL, WHEN FINISHED.
7. REMOVE (5) 24" SECTIONS OF CABINET AND COUNTERTOPS, START FROM EGRESS DOOR. COUNTERTOP EDGE SHALL BE FLUSH WITH CABINET END PANEL WHEN FINISHED.
8. PROVIDE NEW M.O. FOR NEW UV5 LOUVER, INSTALL NEW LOUVER, BACKER-ROD, AND SEALANT. SEE DRAWING RB-A101 FOR DETAILS.
9. PROVIDE NEW M.O. FOR NEW UV5 LOUVER, INSTALL NEW LOUVER, BACKER-ROD, AND SEALANT. SEE DRAWING RB-A101 FOR DETAILS.
10. PROVIDE NEW M.O. FOR NEW UV1 LOUVER, INSTALL NEW LOUVER, BACKER-ROD, AND SEALANT. SEE DRAWING RB-A101 FOR DETAILS.
11. NEW UV1 WILL REQUIRE EXISTING RADIATOR TUBE/FIN, AND COVER TO BE "CUT-BACK" TO ACCOMMODATE FOR THE NEW LARGER SIZED UV1.
12. ADD SIGNS AT DOORS "BOILER ROOM – FUEL BURNING EQUIPMENT AND CO DETECTION"
13. PATCH, PRIME, AND PAINT MECHANICAL ROOM WALLS, CEILINGS, DOORS, AND DOOR FRAMES.



SECTION
SCALE: 1 1/2"=1'-0"

1 / RB-A101 **TYPICAL BRICK AND BLOCK OPENING ENLARGMENT DETAILS**
ALL CONDITIONS SHALL BE VERIFIED IN FIELD.

ROSE •TISO & CO. LLC.
ARCHITECTS ● SURVEYORS ● ENGINEERS
WWW.ROSETISO.COM
35 BRENTWOOD AVENUE, FAIRFIELD, CT 06825
TEL: (203)610-6262 ● FAX: (203)610-6404

REVISIONS			
NO.	BY	DATE	DESCRIPTION

PROJECT TITLE

RACE BROOK SCHOOL
107 GRANNIS ROAD
ORANGE, CT
STATE PROJECT NO: TMP-107-QGCV

BOILER AND UNIT VENT. REPLACEMENTS

ORANGE CONNECTICUT 1822 TOWN SEAL

Prepared For:

TOWN OF ORANGE, CT
637 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE

PARTIAL FLOOR PLAN UNIT VENTILATORS

DESIGNED BY: TG	SCALE: AS NOTED
DRAWN BY: TG	DATE: 07-02-13
CHECKED BY: PR	PROJECT NUMBER: 1605
CAD FILE: R:/1605/ARCH	

SEAL

SHEET NUMBER

RB-A101

CONSTRUCTION NOTES:

1. PROVIDE NEW M.O. TO ACCOMMODATE NEW UV4 LOUVER. INSTALL NEW BACKER-ROD, AND SEALANT. (SEE DRAWING RB-A101 FOR DETAILS)
2. NEW UV4 WILL REQUIRE EXISTING RADIATOR TUBE/FINS, AND COVER TO BE "CUT-BACK" TO ACCOMMODATE FOR THE LAGER SIZED NEW UV4
3. PROVIDE NEW M.O. FOR NEW UV2 LOUVER. INSTALL NEW LOUVER, BACKER-ROD, AND SEALANT. SEE DRAWING RB-A101 FOR DETAILS
4. NEW UV2 WILL REQUIRE EXISTING RADIATOR TUBE/FIN, AND COVER TO BE "CUT-BACK" TO ACCOMMODATE FOR LARGER SIZE NEW UV2
5. REMOVE EXISTING FINISH FLOOR AND TRENCH CONCRETE SLAB TO ALLOW NEW PIPING TO BE PLACED IN TRENCH. FILL TRENCH WITH CONCRETE, REPLACE FLOORING WITH NEW MATCHING VCT FLOORING.
6. REMOVE (4) 24" SECTIONS OF CABINET AND COUNTERTOP, STARTING FROM EGRESS DOOR. COUNTER TOP EDGE TO BE FLUSHED WITH CABINET END PANEL, WHEN FINISHED.
7. REMOVE (5) 24" SECTIONS OF CABINET AND COUNTERTOPS, START FROM EGRESS DOOR. COUNTERTOP EDGE SHALL BE FLUSH WITH CABINET END PANEL WHEN FINISHED.
8. PROVIDE NEW M.O. FOR NEW UV5 LOUVER, INSTALL NEW LOUVER, BACKER-ROD, AND SEALANT. SEE DRAWING RB-A101 FOR DETAILS.
9. PROVIDE NEW M.O. FOR NEW UV5 LOUVER, INSTALL NEW LOUVER, BACKER-ROD, AND SEALANT. SEE DRAWING RB-A101 FOR DETAILS.
10. PROVIDE NEW M.O. FOR NEW UV1 LOUVER, INSTALL NEW LOUVER, BACKER-ROD, AND SEALANT. SEE DRAWING RB-A101 FOR DETAILS.
11. NEW UV1 WILL REQUIRE EXISTING RADIATOR TUBE/FIN, AND COVER TO BE "CUT-BACK" TO ACCOMMODATE FOR THE NEW LARGER SIZED UV1.
12. ADD SIGNS AT DOORS "BOILER ROOM – FUEL BURNING EQUIPMENT AND CO DETECTION"
13. PATCH, PRIME, AND PAINT MECHANICAL ROOM WALLS, CEILINGS, DOORS, AND DOOR FRAMES.

GENERAL NOTES:

1. THE INFORMATION SHOWN ON THIS DRAWING IS BASED UPON THE INFORMATION SHOWN ON THE BUILDING PLANS AND LIMITED FIELD INVESTIGATIONS AND MAY OR MAY NOT REFLECT ACTUAL FIELD CONDITIONS. THIS CONTRACTOR SHALL VERIFY THE INFORMATION INDICATED ON THIS DRAWING AND NOTIFY THE ENGINEER OF ANY DISCREPANCIES PRIOR TO SUBMITTING HIS BID.
2. THIS CONTRACTOR IS REQUIRED TO PERFORM THIS WORK IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, ORDINANCES, ETC., AND TO MEET THE REQUIREMENTS OF THE LOCAL AUTHORITIES HAVING JURISDICTION AND OWNER, WHETHER OR NOT SPECIFICALLY INDICATED OR SPECIFIED ON THIS DRAWING.
3. THE CONTRACTOR SHALL SEAL ALL PENETRATIONS THROUGH SMOKE AND/OR FIRE RATED PARTITIONS AND SLABS WITH A U.L. LISTED SMOKE AND/OR FIRE STOP TO MAINTAIN THE INTEGRITY OF THE FIRE AND/OR SMOKE RATING. PROVIDE SHOP DRAWINGS FOR ALL PENETRATIONS. REFER TO ELECTRICAL SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.

CODE REFERENCE LEGEND:

EXISTING 1 HOUR FIRE RATED WALL
UL DESIGN # UL906
(TIGHT TO DECK ABOVE)
1 HOUR FIRE WALL WHERE NOTED

KEY PLAN
SCALE: N.T.S.



UNIT VENTILATOR FLOOR PLAN
SCALE: 1/8" = 1'-0"

ROSE •TISO & CO. LLC.
ARCHITECTS ● SURVEYORS ● ENGINEERS
WWW.ROSETISO.COM
35 BRENTWOOD AVENUE, FAIRFIELD, CT 06825
TEL: (203)610-6262 ● FAX: (203)610-6404

REVISIONS			
NO.	BY	DATE	DESCRIPTION

PROJECT TITLE

RACE BROOK SCHOOL
107 GRANNIS ROAD
ORANGE, CT
STATE PROJECT NO:
TMP-107-QGCV

BOILER AND UNIT VENT. REPLACEMENTS

Prepared For:

TOWN OF ORANGE, CT
637 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE

PARTIAL FLOOR PLAN
UNIT VENTILATORS

DESIGNED BY: TG	SCALE: AS NOTED
DRAWN BY: TG	DATE: 07-02-13
CHECKED BY: PR	PROJECT NUMBER: 1605
CAD FILE: R:/1605/ARCH	

SEAL

SHEET NUMBER

RB-A102

CONSTRUCTION NOTES:

1. PROVIDE NEW M.O. TO ACCOMMODATE NEW UV4 LOUVER. INSTALL NEW BACKER-ROD, AND SEALANT. (SEE DRAWING RB-A101 FOR DETAILS)
2. NEW UV4 WILL REQUIRE EXISTING RADIATOR TUBE/FINS, AND COVER TO BE "CUT-BACK" TO ACCOMMODATE FOR THE LAGER SIZED NEW UV4
3. PROVIDE NEW M.O. FOR NEW UV2 LOUVER. INSTALL NEW LOUVER, BACKER-ROD, AND SEALANT. SEE DRAWING RB-A101 FOR DETAILS
4. NEW UV2 WILL REQUIRE EXISTING RADIATOR TUBE/FIN, AND COVER TO BE "CUT-BACK" TO ACCOMMODATE FOR LARGER SIZE NEW UV2
5. REMOVE EXISTING FINISH FLOOR AND TRENCH CONCRETE SLAB TO ALLOW NEW PIPING TO BE PLACED IN TRENCH. FILL TRENCH WITH CONCRETE, REPLACE FLOORING WITH NEW MATCHING VCT FLOORING.
6. REMOVE (4) 24" SECTIONS OF CABINET AND COUNTERTOP, STARTING FROM EGRESS DOOR. COUNTER TOP EDGE TO BE FLUSHED WITH CABINET END PANEL, WHEN FINISHED.
7. REMOVE (5) 24" SECTIONS OF CABINET AND COUNTERTOPS, START FROM EGRESS DOOR. COUNTERTOP EDGE SHALL BE FLUSH WITH CABINET END PANEL WHEN FINISHED.
8. PROVIDE NEW M.O. FOR NEW UV5 LOUVER, INSTALL NEW LOUVER, BACKER-ROD, AND SEALANT. SEE DRAWING RB-A101 FOR DETAILS.
9. PROVIDE NEW M.O. FOR NEW UV5 LOUVER, INSTALL NEW LOUVER, BACKER-ROD, AND SEALANT. SEE DRAWING RB-A101 FOR DETAILS.
10. PROVIDE NEW M.O. FOR NEW UV1 LOUVER, INSTALL NEW LOUVER, BACKER-ROD, AND SEALANT. SEE DRAWING RB-A101 FOR DETAILS.
11. NEW UV1 WILL REQUIRE EXISTING RADIATOR TUBE/FIN, AND COVER TO BE "CUT-BACK" TO ACCOMMODATE FOR THE NEW LARGER SIZED UV1.
12. ADD SIGNS AT DOORS "BOILER ROOM – FUEL BURNING EQUIPMENT AND CO DETECTION"
13. PATCH, PRIME, AND PAINT MECHANICAL ROOM WALLS, CEILINGS, DOORS, AND DOOR FRAMES.

GENERAL NOTES:

1. THE INFORMATION SHOWN ON THIS DRAWING IS BASED UPON THE INFORMATION SHOWN ON THE BUILDING PLANS AND LIMITED FIELD INVESTIGATIONS AND MAY OR MAY NOT REFLECT ACTUAL FIELD CONDITIONS. THIS CONTRACTOR SHALL VERIFY THE INFORMATION INDICATED ON THIS DRAWING AND NOTIFY THE ENGINEER OF ANY DISCREPANCIES PRIOR TO SUBMITTING HIS BID.
2. THIS CONTRACTOR IS REQUIRED TO PERFORM THIS WORK IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, ORDINANCES, ETC., AND TO MEET THE REQUIREMENTS OF THE LOCAL AUTHORITIES HAVING JURISDICTION AND OWNER, WHETHER OR NOT SPECIFICALLY INDICATED OR SPECIFIED ON THIS DRAWING.
3. THE CONTRACTOR SHALL SEAL ALL PENETRATIONS THROUGH SMOKE AND/OR FIRE RATED PARTITIONS AND SLABS WITH A U.L. LISTED SMOKE AND/OR FIRE STOP TO MAINTAIN THE INTEGRITY OF THE FIRE AND/OR SMOKE RATING. PROVIDE SHOP DRAWINGS FOR ALL PENETRATIONS. REFER TO ELECTRICAL SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.

CODE REFERENCE LEGEND:

EXISTING 1 HOUR FIRE RATED WALL
UL DESIGN # UL906
(TIGHT TO DECK ABOVE)
1 HOUR FIRE WALL WHERE NOTED

KEY PLAN
SCALE: N.T.S.



UNIT VENTILATOR FLOOR PLAN
SCALE: 1/8" = 1'-0"

ROSE •TISO & CO. LLC.
ARCHITECTS ● SURVEYORS ● ENGINEERS
WWW.ROSETISO.COM
35 BRENTWOOD AVENUE, FAIRFIELD, CT 06825
TEL: (203)610-6262 ● FAX: (203)610-6404

REVISIONS			
NO.	BY	DATE	DESCRIPTION

PROJECT TITLE

RACE BROOK SCHOOL
107 GRANNIS ROAD
ORANGE, CT
STATE PROJECT NO: TMP-107-QGCV

BOILER AND UNIT VENT. REPLACEMENTS

ORANGE CONNECTICUT 1822 TOWN SEAL

Prepared For:

TOWN OF ORANGE, CT
637 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE

PARTIAL FLOOR PLAN UNIT VENTILATORS

DESIGNED BY: TG	SCALE: AS NOTED
DRAWN BY: TG	DATE: 07-02-13
CHECKED BY: PR	PROJECT NUMBER: 1605
CAD FILE: R:/1605/ARCH	

SEAL	SHEET NUMBER
	RB-A103



CONSTRUCTION NOTES:

1. EXISTING AHU1 THRU 4 LOCATED AT MEZZANINE LEVEL TO REMAIN. REPLACE ALL EXISTING PNEUMATIC CONTROLS WITH NEW ELECTRIC CONTROLS. PROVIDE DEMAND VENTILATION CONTROLLER AND SET MINIMUM OUTSIDE AIR TO 10%. PROVIDE THE FOLLOWING INPUT/OUTPUT POINTS TO EXISTING EXPANDED EMS:
   - FAN START/STOP/STATUS
   - OUTSIDE, RETURN & MIXED AIR TEMPERATURES
   - OUTSIDE, RETURN & EXHAUST AIR MOTORIZED DAMPERS
   - DISCHARGE AIR TEMPERATURE
   - DISCHARGE AIR PRESSURE
   - HEATING COIL VALVE
   - FILTER STATUS
   - SUPPLY SMOKE DETECTOR
   - DEMAND VENTILATION CONTROLLER
2. EXISTING P7, 8 & 9 LOCATED AT MEZZANINE LEVEL TO REMAIN. REPLACE ALL EXISTING PNEUMATIC CONTROLS WITH NEW ELECTRIC CONTROLS. PROVIDE THE FOLLOWING INPUT/OUTPUT POINTS TO THE EXISTING EXPANDED EMS:
   - PUMP START/STOP/STATUS
3. EXISTING 2-WAY PNEUMATIC CONTROL VALVE TO BE REPLACED WITH AN ELECTRIC (24VAC) VALVE. PROVIDE THE FOLLOWING INPUT/OUTPUT POINTS TO EXISTING EMS:
   - HEATING COIL VALVE
4. EXISTING PNEUMATIC THERMOSTAT TO BE REPLACED WITH AN ELECTRIC (24VAC) THERMOSTAT/ TEMPERATURE SENSOR, FURNISHED WITH CLEAR LOCKABLE COVER (TYP.). PROVIDE THE FOLLOWING INPUT/OUTPUT POINTS TO EXISTING EMS:
   - SPACE TEMPERATURE
5. EXHAUST FAN ON ROOF TO REMAIN.
6. EXISTING CABINET UNIT HEATER TO REMAIN. REPLACE ALL EXISTING PNEUMATIC CONTROLS WITH ELECTRIC CONTROLS. PROVIDE THE FOLLOWING INPUT/OUTPUT POINTS TO EXISTING EMS:
   - FAN START/STOP/STATUS
   - DISCHARGE AIR TEMPERATURE
   - HEATING COIL VALVE
   - FILTER STATUS
7. NEW ELECTRIC UNIT HEATER. PROVIDE THE FOLLOWING INPUT/OUTPUT POINTS TO EMS:
   - FAN START/STOP/STATUS
   - ELECTRIC RESISTANCE COIL
   - SPACE TEMPERATURE
8. LINE OF EXISTING FAN-COIL UNIT TO BE DISCONNECTED, REMOVED, AND DISPOSED OF IN A LEGAL MANNER.
9. LINE OF EXISTING CEILING CABINET EXHAUST FAN CONTROLLED FROM LOCAL SWITCH TO REMAIN. CHECK FAN OPERATION AND PROVIDE ANY NECESSARY REPAIRS TO RENDER THIS EXHAUST FAN OPERATIONAL.
10. LINE OF NEW UNIT VENTILATOR. PROVIDE THE FOLLOWING INPUT/OUPUT POINTS TO EXISTING EMS:
    - FAN START/STOP/STATUS
    - OUTSIDE, RETURN & MIXED AIR TEMPERATURES
    - OUTSIDE AIR MOTORIZED DAMPER
    - DISCHARGE AIR TEMPERATURE
    - DISCHARGE AIR PRESSURE
    - HEATING COIL VALVE
    - FILTER STATUS
    - DEMAND VENTILATION CONTROLLER
    - SPACE TEMPERATURE VIA INTERLOCK WITH FINNED-TUBE RADIATION CONTROL VALVE
11. LINE OF EXISTING HOT WATER SUPPLY & RETURN RISERS FROM TUNNEL BELOW. ALL NEW UNIT VENTILATORS WILL REQUIRE TO BE ALIGNED WITH THE EXISTING FAN-COILS RIGHT HAND SIDE, SUCH THAT THE NEW UNITS PIPING COMPARTMENT WILL FALL AT PRESENT LOCATION. THE EXISTING FINNED-TUBE RADIATION ENCLOSURES WILL REQUIRE TO BE CUT/ADJUSTED, AS NECESSARY TO WORK WITH THE NEW UNIT VENTILATORS. ALL EXISTING BOOKCASES OR BUILT-IN CABINETRY WILL REQUIRE TO BE REMOVED AND RELOCATED AS NECESSARY TO PROVIDE THIS WORK.
12. LINE OF THE NEW UNIT VENTILATOR OUTSIDE AIR LOUVER/BOX. CAREFULLY CUT THE EXISTING WALL AS NECESSARY TO ACCOMMODATE THE NEW LOUVER/BOX. SEAL WATERTIGHT THE NEW LOUVER/BOX TO THE NEW WALL OPENING.
13. LINE OF EXISTING UNIT VENTILATOR TO BE DISCONNECTED, REMOVED AND DISPOSED OF IN A LEGAL MANNER.
14. EXISTING INDOOR UNIT PART OF THE 4-TON SPLIT COOLING SYSTEM TO BE DISCONNECTED, REMOVED AND TURNED OVER TO THE OWNER'S REPRESENTATIVE. COLLECT ALL REFRIGERANT AS REQUIRED BY ASHRAE 15. RE-CONNECT THE EXISTING REFRIGERATION PIPING TO THE DX COIL IN THE NEW UNIT VENTILATOR UVS. PROVIDE INITIAL REFRIGERATION CHARGE, CHECK FOR LEAKS, PROVIDE ANY NECESSARY REPAIRS FOR A LEAK FREE INSTALLATION AND RE-FILL AS REQUIRED.
15. EXISTING OUTDOOR UNIT PART OF THE 4-TON SPLIT COOLING SYSTEM TO BE RE-USED IN CONNECTION WITH THE NEW UNIT VENTILATOR UVS. REFER TO THE NOTE #14 ABOVE.

LEGEND & ABBREVIATIONS

	EXISTING EQUIPMENT/PIPING TO REMAIN
	EXISTING EQUIPMENT/PIPING TO BE REMOVED
	NEW EQUIPMENT/PIPING
B#	BOILER
HEX#	HEAT EXCHANGER
BFS#	BOILERS FEED SYSTEM
ST#	STORAGE TANK
P#	HEATING/RECIRCULATION PUMP
EXT#	EXPANSION TANK
CAC#	CONTROLS AIR COMPRESSOR
CP#	CONTROL PANEL
BD	BAROMETRIC DAMPER WITH THERMAL LINK SWITCHES
MD	MOTORIZED DAMPER
DWH#	DOMESTIC WATER HEATER
IWH#	INDIRECT WATER HEATER
AHU#	AIR HANDLING UNIT
RTU#	ROOFTOP UNIT
EF#	EXHAUST FAN
P#	PUMP
FC#	FAN-COIL UNIT
C	CONVECTOR
CUH	CABINET UNIT HEATER
UH	UNIT HEATER
FT	FINNED-TUBE RADIATION
EB	ELECTRIC BASEBOARD RADIATION
EUH	ELECTRIC UNIT HEATER
GIH	GRAVITY INTAKE HOOD
CW	COLD WATER PIPING
HW	HOT WATER PIPING
R	DOMESTIC RECIRCULATION HOT WATER PIPING
LPS/LPR	LOW PRESSURE STEAM/RETURN PIPING
PC	PUMPED CONDENSATE
HWS/HWR	HOT WATER SUPPLY/RETURN PIPING
G	GAS PIPING
CD	CONDENSATE DRAIN PIPING
AS#	AIR SEPARATOR
FOS/FOR	FUEL OIL SUPPLY/RETURN PIPING
CMD#	CARBON MONOXIDE DETECTOR
RD	ROOF DRAIN
PV	PLUMBING VENT
VD	VOLUME DAMPER
MD	MOTORIZED DAMPER
BFP	BACKFLOW PREVENTER
FT	FLUE TEMPERATURE INDICATOR
	GATE VALVE
	PLUG VALVE
	BALL VALVE
	2-WAY CONTROL VALVE (PNEUMATIC)
	2-WAY CONTROL VALVE (ELECTRIC/ ELECTRONIC)
	3-WAY CONTROL VALVE (ELECTRIC/ ELECTRONIC)
	CHECK VALVE
	BUTTERFLY VALVE
	PRESSURE REDUCING VALVE
	BACKFLOW PREVENTER
	FLOW CONTROL VALVE
	STRAINER
	RELIEF VALVE
	BALANCING VALVE
	FUSOMATIC OIL VALVE
OCF	OIL CARTRIDGE FILTER
T	THERMOSTAT/TEMPERATURE SENSOR
	TEMP. SENSOR/CONTROLLER WITH WELL
	PRESS. SENSOR/CONTROLLER WITH WELL
S	SERVICE SWITCH
SEM	EMERGENCY SHUTDOWN SWITCH
LWCO	LOW WATER CUT OUT CONTROLLER
VFD#	VARIABLE FREQUENCY DRIVE
PCP#	PUMPS CONTROL PANEL
T	TEMPERATURE GAUGE
TS	THERMAL SWITCH, SET AT 165 F
SD	SMOKE DETECTOR, DUCT MOUNTED
C	DEMAND VENTILATION CONTROLLER
SDRTS	SMOKE DETECTOR REMOTE TEST STATION
	EQUIPMENT STARTER
E	EXISTING TO REMAIN
ER	EXISTING TO BE RELOCATED
R	EXISTING TO BE REMOVED
	CONNECT TO EXISTING

GENERAL NOTE
REFER TO DRAWING RB-M102 FOR THE NEW HVAC EQUIPMENT SELECTION AND SPECIFICATIONS.

KEY PLAN



GENERAL NOTES

1. - THE INFORMATION SHOWN ON THIS DRAWING IS BASED UPON THE INFORMATION SHOWN ON THE BUILDING PLANS AND LIMITED FIELD INVESTIGATIONS AND MAY OR MAY NOT REFLECT ACTUAL FIELD CONDITIONS. THIS CONTRACTOR SHALL VERIFY THE INFORMATION INDICATED ON THIS DRAWING AND NOTIFY THE ENGINEER OF ANY DISCREPANCIES PRIOR TO SUBMITTING HIS BID.
2. - THIS CONTRACTOR IS REQUIRED TO PERFORM THIS WORK IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, ORDINANCES, ETC., AND TO MEET THE REQUIREMENTS OF THE LOCAL AUTHORITIES HAVING JURISDICTION AND OWNER, WHETHER OR NOT SPECIFICALLY INDICATED OR SPECIFIED ON THIS DRAWING.
3. - THE CONTRACTOR SHALL SEAL ALL PENETRATIONS THROUGH FIRE RATED WALLS AS INDICATED ON DWG. RB-EG101 WITH A U.L. LISTED FIRESTOP TO MAINTAIN THE INTEGRITY OF THE FIRE RATING. PROVIDE SHOP DRAWINGS FOR ALL PENETRATIONS. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.

PART FLOOR PLAN - MECHANICAL

SCALE: 1/8" = 1'-0"

ROSE • TISO & CO. LLC.
ARCHITECTS • SURVEYORS • ENGINEERS
WWW.ROSETISO.COM
35 BRENTWOOD AVENUE, FAIRFIELD, CT 06825
TEL: (203)610-6262 • FAX: (203)610-6404

MUSCO ENGINEERING ASSOCIATES
375 Morgan Lane, Unit 307
West Haven, CT 06516
(203) 932-1901 FAX (203) 931-1550
www.muscoengineering.com

DUMITRU T. PETRESCU, P.E., LLC
MECHANICAL ENGINEER

REVISIONS			
NO.	BY	DATE	DESCRIPTION

PROJECT TITLE

RACE BROOK SCHOOL
107 GRANNIS ROAD
ORANGE, CT
STATE PROJECT NO:
TMP-107-QGCV

BOILERS & UNIT VENT. REPLACEMENTS

ORANGE CONNECTICUT 1822 TOWN SEAL

Prepared For:

TOWN OF ORANGE, CT
637 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE

PART FLOOR PLAN MECHANICAL

DESIGNED BY: DTP	SCALE: AS NOTED
DRAWN BY: CP	DATE: 7-08-13
CHECKED BY: DTP	PROJECT NUMBER: 1605
CAD FILE: M101.DWG	

SEAL

SHEET NUMBER

RB-M101

MEP 130416-1

EXISTING HVAC EQUIPMENT

AIR HANDLING UNITS

AHU1 AIR HANDLING UNIT, FLOOR MOUNTED HORIZONTAL TYPE, "TRANE", CLIMATE CHANGER MODEL CCDB12BN0H, TOTAL AIR FLOW & MINIMUM OUTSIDE AIR FLOW N/A, HOT WATER HEATING COIL, 5 HP FAN MOTOR @ 208V/3 PH, (SERVING GYM).

AHU2 AIR HANDLING UNIT, FLOOR MOUNTED HORIZONTAL TYPE, "TRANE", CLIMATE CHANGER MODEL CCDB12BW0H, TOTAL AIR FLOW & MINIMUM OUTSIDE AIR FLOW N/A, HOT WATER HEATING COIL, 3 HP FAN MOTOR @ 208V/3 PH, (SERVING).

AHU3 AIR HANDLING UNIT, FLOOR MOUNTED HORIZONTAL TYPE, "TRANE", CLIMATE CHANGER MODEL CCDB10BN0H, TOTAL AIR FLOW & MINIMUM OUTSIDE AIR FLOW N/A, HOT WATER HEATING COIL, 3 HP FAN MOTOR @ 208V/3 PH, (SERVING CAFETERIA).

AHU4 AIR HANDLING UNIT, FLOOR MOUNTED HORIZONTAL TYPE, "TRANE", CLIMATE CHANGER MODEL CCD0B6AN0H, TOTAL AIR FLOW N/A (100% OUTSIDE AIR), HOT WATER HEATING COIL, 3 HP FAN MOTOR @ 208V/3 PH, (SERVING KITCHEN).

NOTES:
1. – THE AIR HANDLING UNITS SHALL REMAIN.

HEAT EXCHANGER

HEX2 HEAT EXCHANGER, STEAM TO HOT WATER TYPE, "B&G", MODEL, SIZE & CHARACTERISTICS N/A.

NOTES:
1. – THE HEAT EXCHANGER SHALL REMAIN.

PUMPS

P7, 8 & 9 PUMP, IN LINE HOT WATER HEATING TYPE, "B&G", MODEL, SIZE & CHARACTERISTICS N/A.

NOTES:
1. – THE HEATING PUMPS SHALL REMAIN.

AIR SEPARATOR

AS2 AIR SEPARATOR, IN–LINE TYPE, MAKE, MODEL & CHARACTERISTICS N/A.

NOTES:
1. – THE AIR SEPARATOR SHALL REMAIN.

EXPANSION TANK

EXT EXPANSION TANK, FACTORY PRESSURIZED, MAKE, MODEL & CHARACTERISTICS N/A.

NOTES:
1. – THE EXPANSION TANK SHALL REMAIN.

ROOFTOP UNITS (EXISTING TO REMAIN)

FINNED–TUBE RADIATION

FT EXISTING HOT WATER FINNED–TUBE RADIATION, MAKE, MODEL, SIZE & CHARACTERISTICS N/A, TO REMAIN.

CONVECTORS

C EXISTING HOT WATER CONVECTOR, MAKE, MODEL, SIZE & CHARACTERISTICS N/A, TO REMAIN.

EXHAUST FANS

EF EXISTING EXHAUST FAN ON ROOF TO REMAIN

CABINET UNIT HEATERS

CUH CABINET UNIT HEATER, CEILING MOUNTED OR WALL RECESSED TYPE, MAKE, MODEL, SIZE & CHARACTERISTICS N/A, TO REMAIN.

UNIT HEATERS

UH UNIT HEATERS, MAKES, MODELS, SIZES & CHARACTERISTICS N/A. REFER TO DRAWINGS FOR ADD'L INFO.

FAN–COIL UNITS

FC FAN–COIL UNITS, "TRANE", MODELS, SIZES & CHARACTERISTICS N/A, 750 MCF OR 1,000 CFM TOTAL AIR FLOW (MINIMUM OUTSIDE AIR N/A), TO BE DISCONNECTED, REMOVED AND DISPOSED OF IN A LEGAL MANNER.

THERMOSTATS

T EXISTING PNEUMATIC THERMOSTAT CONTROLLING THE HOT WATER FINNED–TUBE RADIATION, UNIT AND CABINET UNIT HEATERS, ETC., TO BE REMOVED AND REPLACED WITH ELECTRIC (24VAC) THERMOSTAT/TEMPERATURE SENSOR.

NEW HVAC EQUIPMENT

UNIT VENTILATORS

UV1 UNIT VENTILATOR, HEATING VERTICAL CABINET TYPE, EQUAL TO "MACIGAIRE", MODEL MAUVE1, RATED FOR 500 CFM TOTAL AIR SUPPLY @ HIGH SPEED (50 CFM/490 CFM MINIMUM OUTSIDE AIR), 20.2 MBH HEATING CAPACITY @ 53.7 F EAT, 2–ROWS, 4 GPM @ 160 F EWT & .9 FT WPD, 1/5 HP FAN MOTOR @ 120V/1 PH, ETL LISTED, 50"W x 16.63"DEEP x 30.5"H, 350 OPERATING WEIGHT, FURNISHED WITH FLANGED TYPE 24"W x 10–3/8"H OUTSIDE AIR LOUVER.

UV2 UNIT VENTILATOR, HEATING VERTICAL CABINET TYPE, EQUAL TO "MACIGAIRE", MODEL MAUVE2, RATED FOR 750 CFM TOTAL AIR SUPPLY @ HIGH SPEED (50 CFM/150 CFM MINIMUM OUTSIDE AIR), 36.3 MBH HEATING CAPACITY @ 52.4 F EAT, 2–ROWS, 4 GPM @ 160 F EWT & 1.2 FT WPD, 1/5 HP FAN MOTOR @ 120V/1 PH, ETL LISTED, 62"W x 16.63"DEEP x 30.5"H, 500 LBS OPERATING WEIGHT, FURNISHED WITH FLANGED TYPE 36"W x 10–3/8"H OUTSIDE AIR LOUVER.

UV3 UNIT VENTILATOR, HEATING VERTICAL CABINET TYPE, EQUAL TO "MACIGAIRE", MODEL MAUVE3, RATED FOR 1,000 CFM TOTAL AIR SUPPLY @ HIGH SPEED (85 CFM/255 CFM MINIMUM OUTSIDE AIR), 49.3 MBH HEATING CAPACITY @ 48.9 F EAT, 2–ROWS, 4 GPM @ 160 F EWT & 1.5 FT WPD, 1/5 HP FAN MOTOR @ 120V/1 PH, ETL LISTED, 74"W x 16.63"DEEP x 30.5"H, 600 LBS OPERATING WEIGHT, FURNISHED WITH FLANGED TYPE 48"W x 10–3/8"H OUTSIDE AIR LOUVER.

UV4 UNIT VENTILATOR, HEATING VERTICAL CABINET TYPE, EQUAL TO "MACIGAIRE", MODEL MAUVE4, RATED FOR 1,250 CFM TOTAL AIR SUPPLY @ HIGH SPEED (140 CFM/420 CFM MINIMUM OUTSIDE AIR), 62.6 MBH HEATING CAPACITY @ 43.8 F EAT, 2–ROWS, 4 GPM @ 160 F EWT & 1.8 FT WPD, 1/5 HP FAN MOTOR @ 120V/1 PH, ETL LISTED, 86"W x 16.63"DEEP x 30.5"H, 740 LBS OPERATING WEIGHT, FURNISHED WITH FLANGED TYPE 60"W x 10–3/8"H OUTSIDE AIR LOUVER.

UV5 UNIT VENTILATOR, HEATING VERTICAL CABINET WITH SPLIT COOLING SYSTEM, EQUAL TO "MACIGAIRE", MODEL MASO8H, RATED FOR 1,250 CFM TOTAL AIR SUPPLY (140 CFM/420 CFM MINIMUM OUTSIDE AIR), 82.6 MBH HEATING CAPACITY @ 43.8 F EAT, 2–ROWS, 4 GPM @ 160 F EWT & 1.8 FT WPD, 4–TON TOTAL COOLING CAPACITY @ AIR CONDITIONS, 1/5 HP FAN MOTOR, 53 MCA & 60 MFS @ 208V/1 PH, ETL LISTED, 112.4"W x 29.6"DEEP x 30.5"H, 1,462 LBS OPERATING WEIGHT, FURNISHED WITH FLANGED OUTSIDE AIR LOUVER.

NOTES:
1. – EACH UNIT VENTILATOR SHALL BE TESTED AND CERTIFIED IN ACCORDANCE WITH AHRI STANDARD 840, SHALL BE 16–5/8" DEEP WITH OUTSIDE AIR REAR AND 18" OR 22" HIGH CLOSED PASSAGE PIPE TUNNEL WITH BOTTOM RECIRCULATION, AND INCLUDES RATED CASING CONSTRUCTION, 1" THICK PLEATED DISPOSABLE FILTERS, PENCILPROOF BARSTOCK DISCHARGE GRILLE, DRAIN PANS, FAN MOTOR, OUTSIDE AND RETURN AIR MOTORIZED DAMPERS, HOT WATER HOT WATER COIL, DX COIL AND REFRIGERATION CONTROLS (UV5 ONLY), FRONT SERVICE PANELS, WITH FIELD–INSTALLED THREE–WAY HEATING VALVE PACKAGE TYPE 4 AND CONTROLS TO MATCH EXISTING, AND CONNECT TO THE EXISTING EXPANDED ENERGY MANAGEMENT SYSTEM (EMS.)
2. – INSTALL THE NEW UNIT VENTILATORS IN STRICT ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS, RECOMMENDATIONS AND WARRANTY. TEST AND CERTIFY THE OPERATION OF THE UNIT VENTILATORS IN STRICT ACCORDANCE WITH THE SPECIFIED SEQUENCES OF OPERATION.
3. – NOTE, THAT THE PRESENT SCIENCE (37) IS USED AS A COMPUTER LAB AND IS THE ONLY CLASSROOM IN THIS SCHOOL WHICH IS PROVIDED WITH COOLING VIA (1) 4–TON SPLIT COOLING SYSTEM, WHICH LACKS VENTILATION AIR. THE PRESENT SPLIT SYSTEM INDOOR UNIT SHALL BE DISCONNECTED, REMOVED AND TURNED OVER TO THE OWNER'S REPRESENTATIVE. THE PRESENT SPLIT SYSTEM OUTDOOR UNIT MOUNTED ON ROOF SHALL BE RE–USED IN CONNECTION WITH THE NEW UNIT VENTILATOR UV5. TEST THE OPERATION OF THE EXISTING ROOF MOUNTED OUTDOOR AIR–COOLED CONDENSING UNIT, PROVIDE ALL NECESSARY REPAIRS, EXTEND THE EXISTING REFRIGERATION PIPING TO THE DX COIL IN THE NEW UV5. FOLLOWING THE EXISTING REFRIGERATION PIPING ROUTING, PROVIDE THE INITIAL REFRIGERATION CHARGE AND TEST FOR REFRIGERATION LEAKS. PROVIDE ALL NECESSARY REPAIRS AND RENDER THE REFRIGERATION PIPING LEAK FREE. TEST THE COOLING OPERATION FOR THE NEW UV5 AND PROVIDE ALL NECESSARY ADJUSTMENTS.

CONSTRUCTION NOTES:

1. EXISTING AHU1 THRU 4 LOCATED AT MEZZANINE LEVEL TO REMAIN. REPLACE ALL EXISTING PNEUMATIC CONTROLS WITH NEW ELECTRIC CONTROLS. PROVIDE DEMAND VENTILATION CONTROLLER AND SET MINIMUM OUTSIDE AIR TO 10%. PROVIDE THE FOLLOWING INPUT/OUTPUT POINTS TO EXISTING EXPANDED EMS:
   – FAN START/STOP/STATUS
   – OUTSIDE, RETURN & MIXED AIR TEMPERATURES
   – OUTSIDE, RETURN & EXHAUST AIR MOTORIZED DAMPERS
   – DISCHARGE AIR TEMPERATURE
   – DISCHARGE AIR PRESSURE
   – HEATING COIL VALVE
   – FILTER STATUS
   – SUPPLY SMOKE DETECTOR
   – DEMAND VENTILATION CONTROLLER
2. EXISTING P7, 8 & 9 LOCATED AT MEZZANINE LEVEL TO REMAIN. REPLACE ALL EXISTING PNEUMATIC CONTROLS WITH NEW ELECTRIC CONTROLS. PROVIDE THE FOLLOWING INPUT/OUTPUT POINTS TO THE EXISTING EXPANDED EMS:
   – PUMP START/STOP/STATUS
3. EXISTING 2–WAY PNEUMATIC CONTROL VALVE TO BE REPLACED WITH AN ELECTRIC (24VAC) VALVE. PROVIDE THE FOLLOWING INPUT/OUTPUT POINTS TO EXISTING EMS:
   – HEATING COIL VALVE
4. EXISTING PNEUMATIC THERMOSTAT TO BE REPLACED WITH AN ELECTRIC (24VAC) THERMOSTAT/TEMPERATURE SENSOR, FURNISHED WITH CLEAR LOCKABLE COVER (TYP). PROVIDE THE FOLLOWING INPUT/OUTPUT POINTS TO EXISTING EMS:
   – SPACE TEMPERATURE
5. EXHAUST FAN ON ROOF TO REMAIN.
6. EXISTING CABINET UNIT HEATER TO REMAIN. REPLACE ALL EXISTING PNEUMATIC CONTROLS WITH ELECTRIC CONTROLS. PROVIDE THE FOLLOWING INPUT/OUTPUT POINTS TO EXISTING EMS:
   – FAN START/STOP/STATUS
   – DISCHARGE AIR TEMPERATURE
   – HEATING COIL VALVE
   – FILTER STATUS
7. NEW ELECTRIC UNIT HEATER. PROVIDE THE FOLLOWING INPUT/OUTPUT POINTS TO EMS:
   – FAN START/STOP/STATUS
   – ELECTRIC RESISTANCE COIL
   – SPACE TEMPERATURE
8. LINE OF EXISTING FAN–COIL UNIT TO BE DISCONNECTED, REMOVED, AND DISPOSED OF IN A LEGAL MANNER.
9. LINE OF EXISTING CEILING CABINET EXHAUST FAN CONTROLLED FROM LOCAL SWITCH TO REMAIN. CHECK FAN OPERATION AND PROVIDE ANY NECESSARY REPAIRS TO RENDER THIS EXHAUST FAN OPERATIONAL.
10. LINE OF NEW UNIT VENTILATOR. PROVIDE THE FOLLOWING INPUT/OUPUT POINTS TO EXISTING EMS:
    – FAN START/STOP/STATUS
    – OUTSIDE, RETURN & MIXED AIR TEMPERATURES
    – OUTSIDE AIR MOTORIZED DAMPER
    – DISCHARGE AIR TEMPERATURE
    – DISCHARGE AIR PRESSURE
    – HEATING COIL VALVE
    – FILTER STATUS
    – DEMAND VENTILATION CONTROLLER
    – SPACE TEMPERATURE VIA INTERLOCK WITH FINNED–TUBE RADIATION CONTROL VALVE
11. LINE OF EXISTING HOT WATER SUPPLY & RETURN RISERS FROM TUNNEL BELOW ALL NEW UNIT VENTILATORS WILL REQUIRE TO BE ALIGNED WITH THE EXISTING FAN–COILS RIGHT HAND SIDE, SUCH THAT THE NEW UNITS PIPING COMPARTMENT WILL FALL AT PRESENT LOCATION. THE EXISTING FINNED–TUBE RADIATION ENCLOSURES WILL REQUIRE TO BE CUT/ADJUSTED, AS NECESSARY TO WORK WITH THE NEW UNIT VENTILATORS. ALL EXISTING BOOKCASES OR BUILT–IN CABINETRY WILL REQUIRE TO BE REMOVED AND RELOCATED AS NECESSARY TO PROVIDE THIS WORK.
12. LINE OF THE NEW UNIT VENTILATOR OUTSIDE AIR LOUVER/BOX. CAREFULLY CUT THE EXISTING WALL AS NECESSARY TO ACCOMMODATE THE NEW LOUVER/BOX. SEAL WATERTIGHT THE NEW LOUVER/BOX TO THE NEW WALL OPENING.
13. LINE OF EXISTING UNIT VENTILATOR TO BE DISCONNECTED, REMOVED AND DISPOSED OF IN A LEGAL MANNER.
14. EXISTING INDOOR UNIT PART OF THE 4–TON SPLIT COOLING SYSTEM TO BE DISCONNECTED, REMOVED AND TURNED OVER TO THE OWNER'S REPRESENTATIVE. COLLECT ALL REFRIGERANT AS REQUIRED BY ASHRAE 15. RE–CONNECT THE EXISTING REFRIGERATION PIPING TO THE DX COIL IN THE NEW UNIT VENTILATOR UV5. PROVIDE INITIAL REFRIGERATION CHARGE. CHECK FOR LEAKS, PROVIDE ANY NECESSARY REPAIRS FOR A LEAK FREE INSTALLATION AND RE–FILL AS REQUIRED.
15. EXISTING OUTDOOR UNIT PART OF THE 4–TON SPLIT COOLING SYSTEM TO BE RE–USED IN CONNECTION WITH THE NEW UNIT VENTILATOR UV5. REFER TO THE NOTE #14 ABOVE.



PART FLOOR PLAN – MECHANICAL

SCALE: 1/8" = 1'–0"

GENERAL NOTES

1. – THE INFORMATION SHOWN ON THIS DRAWING IS BASED UPON THE INFORMATION SHOWN ON THE BUILDING PLANS AND LIMITED FIELD INVESTIGATIONS AND MAY OR MAY NOT REFLECT ACTUAL FIELD CONDITIONS. THIS CONTRACTOR SHALL VERIFY THE INFORMATION INDICATED ON THIS DRAWING AND NOTIFY THE ENGINEER OF ANY DISCREPANCIES PRIOR TO SUBMITTING HIS BID.
2. – THIS CONTRACTOR IS REQUIRED TO PERFORM THIS WORK IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, ORDINANCES, ETC., AND TO MEET THE REQUIREMENTS OF THE LOCAL AUTHORITIES HAVING JURISDICTION AND OWNER, WHETHER OR NOT SPECIFICALLY INDICATED OR SPECIFIED ON THIS DRAWING.
3. – THE CONTRACTOR SHALL SEAL ALL PENETRATIONS THROUGH FIRE RATED WALLS AS INDICATED ON DWG. RB–EG101 WITH A U.L. LISTED FIRESTOP TO MAINTAIN THE INTEGRITY OF THE FIRE RATING. PROVIDE SHOP DRAWINGS FOR ALL PENETRATIONS. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.



KEY PLAN

ROSE • TISO & CO. LLC.
ARCHITECTS • SURVEYORS • ENGINEERS
WWW.ROSETISO.COM
35 BRENTWOOD AVENUE, FAIRFIELD, CT 06825
TEL: (203)610-6262 • FAX: (203)610-6404

MUSCO ENGINEERING ASSOCIATES
375 Morgan Lane, Unit 307
West Haven, CT 06516
(203) 932-1901 FAX (203) 931-1550
www.muscoengineering.com

DUMITRU T. PETRESCU, P.E., LLC
MECHANICAL ENGINEER

REVISIONS

NO.	BY	DATE	DESCRIPTION

PROJECT TITLE

RACE BROOK SCHOOL
107 GRANNIS ROAD
ORANGE, CT
STATE PROJECT NO: TMP–107–QGCV

BOILERS & UNIT VENT. REPLACEMENTS

ORANGE CONNECTICUT 1822 TOWN SEAL

Prepared For:

TOWN OF ORANGE, CT
637 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE

PART FLOOR PLAN MECHANICAL

DESIGNED BY: DTP	SCALE: AS NOTED
DRAWN BY: CP	DATE: 7–08–13
CHECKED BY: DTP	PROJECT NUMBER: 1605
CAD FILE: M102.DWG	

SEAL	SHEET NUMBER
	RB–M102

MEP 130416–1



PART FLOOR PLAN - MECHANICAL

SCALE: 1/8" = 1'-0"

GENERAL NOTE

REFER TO DRAWING RB-M102 FOR THE NEW HVAC EQUIPMENT SELECTION AND SPECIFICATIONS.

GENERAL NOTES

1. – THE INFORMATION SHOWN ON THIS DRAWING IS BASED UPON THE INFORMATION SHOWN ON THE BUILDING PLANS AND LIMITED FIELD INVESTIGATIONS AND MAY OR MAY NOT REFLECT ACTUAL FIELD CONDITIONS. THIS CONTRACTOR SHALL VERIFY THE INFORMATION INDICATED ON THIS DRAWING AND NOTIFY THE ENGINEER OF ANY DISCREPANCIES PRIOR TO SUBMITTING HIS BID.
2. – THIS CONTRACTOR IS REQUIRED TO PERFORM THIS WORK IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, ORDINANCES, ETC., AND TO MEET THE REQUIREMENTS OF THE LOCAL AUTHORITIES HAVING JURISDICTION AND OWNER, WHETHER OR NOT SPECIFICALLY INDICATED OR SPECIFIED ON THIS DRAWING.
3. – THE CONTRACTOR SHALL SEAL ALL PENETRATIONS THROUGH FIRE RATED WALLS AS INDICATED ON DWG. RB-EG101 WITH A U.L. LISTED FIRESTOP TO MAINTAIN THE INTEGRITY OF THE FIRE RATING. PROVIDE SHOP DRAWINGS FOR ALL PENETRATIONS. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.

SCOPE OF WORK

1. – ALL POTENTIAL CONTRACTORS SHALL BECOME FAMILIAR WITH THE EXISTING CONDITIONS, PRIOR TO START ANY WORK.
2. – ALL WORK SHALL BE PERFORMED IN STRICT ACCORDANCE WITH THE 2005 CONNECTICUT STATE BUILDING AND FIRE SAFETY CODES, 2003 INTERNATIONAL MECHANICAL CODE, 2003 INTERNATIONAL PLUMBING CODE, 2003 ICC/ANSI A117.1 ACCESSIBLE AND USABLE BUILDINGS AND FACILITIES, 2009 INTERNATIONAL ENERGY CONSERVATION CODE, 2009 & 2011 CONNECTICUT AMENDMENTS TO THE STATE BUILDING AND FIRE SAFETY CODES, OTHER APPLICABLE CODES, STANDARDS, REGULATIONS, ORDINANCES, ETC., AND THE REQUIREMENTS OF THE LOCAL AUTHORITIES AND UTILITIES COMPANIES HAVING JURISDICTION. THIS CONTRACTOR SHALL BE A LICENSED MECHANICAL CONTRACTOR AND SHALL BE RESPONSIBLE TO OBTAIN A CONSTRUCTION PERMIT AND PAY FOR ALL APPLICABLE FEES, TAXES, TESTS, ETC. NO WORK SHALL BE PERFORMED UNTIL SHOP DRAWINGS FOR ALL EQUIPMENT, DEVICES AND MAJOR MATERIALS, ARE SUBMITTED AND APPROVED IN WRITING BY THE PROJECT ENGINEER.
3. – PROVIDE DEMOLITION WORK TO THE EXTENT INDICATED AND REQUIRED. ALL ITEMS REQUIRED TO REMOVED SHALL BE DISPOSED IN A LEGAL MANNER OR TURNED OVER TO THE OWNER'S REPRESENTATIVE AS INDICATED ON DRAWINGS. REFER TO WORK PHASING NOTE ON DRAWINGS FOR THE SCHEDULE OF WORK WHICH WILL IMPACT THE DEMOLITION WORK. DRAIN BOILERS WHEN DEMOLITION OF THE EXISTING BOILERS B1 - B2. DISASSEMBLE THESE BOILERS SECTIONS AND SAFELY REMOVE THEM THROUGH THE EXISTING LOUVER L/D1 OPENINGS. REMOVE THESE LOUVERS AND DISPOSE OF IN A LEGAL MANNER. CUT EXISTING RH1 IN PIECES AS NEEDED TO SAFELY REMOVE THROUGH THE EXISTING OPENING. REMOVE EXISTING BURNERS AT B1 & 2 AND TURN THEM OVER TO THE OWNER'S REPRESENTATIVE. REMOVE EXISTING BOILERS' VENTS AND BREECHINGS AND DISPOSE THEM INTO A LEGAL MANNER. REMOVE THE EXISTING PIPING, FITTINGS, VALVES, SUPPORTS, ETC., TO THE EXTENT SHOWN AND REQUIRED AND DISPOSE OF IN A LEGAL MANNER. HIRE THE SERVICES OF AN INDEPENDENT CERTIFIED CHIMNEY SWEEPER TO THOROUGHLY INSPECT AND VACUUM CLEAN EXISTING CHIMNEYS, FLUES. PROVIDE THREE (3) COPIES OF THIS CHIMNEY REPORT TO THE PROJECT ENGINEER, PRIOR TO THE COMPLETION OF THE DEMOLITION WORK. PROVIDE A DETAILED DEMOLITION SCHEDULE FOR THE REVIEW AND APPROVAL BY THE PROJECT ENGINEER, PRIOR TO STARTING THIS DEMOLITION WORK.
4. – FURNISH & INSTALL ALL EQUIPMENT, DEVICES, MATERIALS, ETC., AND PROVIDE ALL NECESSARY LABOR, RIGGINGS, ETC. AS INDICATED, SHOWN OR SPECIFIED FOR COMPLETE OPERATIONAL SYSTEMS, APPROVED IN WRITING BY THE ARCHITECT/ENGINEER & OWNER'S REPRESENTATIVE, AND LOCAL AUTHORITIES HAVING JURISDICTION.
5. – ALL MECHANICAL EQUIPMENT SHALL BE INSTALLED IN STRICT ACCORDANCE WITH THE MANUFACTURERS' INSTRUCTIONS, RECOMMENDATIONS AND WARRANTY, WITH ALL REQUIRED CLEARANCES FOR MAINTENANCE AND SERVICE.
6. – ALL PIPING ROOF PENETRATIONS (SUCH AS GAS VENTS) SHALL BE PERFORMED IN APPROVED PITCH POCKETS IN STRICT ACCORDANCE WITH THE ROOF MANUFACTURER'S INSTRUCTIONS, RECOMMENDATIONS AND WARRANTY.
7. – ALL FLOORS AND WALLS PENETRATIONS SHALL BE SEALED IN ACCORDANCE WITH 2003 IBC, SEC. 712.3.1.2., WITH APPROVED FIRE STOPPING MATERIALS.
8. – ALL MECHANICAL EQUIPMENT SHALL BE SEISMICALLY RESTRAINT TO THE BUILDING STRUCTURAL ELEMENTS, AS REQUIRED BY THE 2003 INTERNATIONAL BUILDING CODE SECTION 1621. REFER TO 1999 ASHRAE 'A PRACTICAL GUIDE TO SEISMIC RESTRAINT'. THE SEISMIC RESTRAINTS MANUFACTURERS' ARE REQUIRED TO PROVIDE CERTIFIED SHOP DRAWINGS FOR EACH MECHANICAL EQUIPMENT, STAMPED & SIGNED BY A STRUCTURAL PROFESSIONAL ENGINEER, AND FURTHER OBTAIN ALL NECESSARY APPROVALS FROM THE ARCHITECT/ENGINEER AND OWNER'S REPRESENTATIVE(S), PRIOR TO INSTALLING THESE ITEMS.
9. – ALL NEW BOILERS SHALL BE DELIVERED TO SITE KNOCKDOWN, SHALL BE FULLY ASSEMBLED AT SITE, AND PRESSURE TESTED, AS INDICATED IN SECTION 23 50 11.
10. – THE NATURAL GAS PIPING ABOVE GRADE SHALL BE STEEL, ASTM A53 OR A120, SCHEDULE 40, BLACK, WITH MALLEABLE IRON FITTINGS ASME B16.3 (UP TO AND INCLUDING 2") AND FORGED STEEL ASTM A234 (ABOVE 2") WITH THREADED JOINTS (UP TO AND INCLUDING 2") AND WELDED JOINTS (ABOVE 2"). ANSI B31.1, B31.2 & B31.9. FLANGES, UNIONS AND COUPLING 2" AND UNDER SHALL BE FERROUS PIPE, MALLEABLE IRON WITH THREADED UNIONS, RATED FOR 150 PSI. ON PIPING OVER 2" USE FORGED STEEL SLIP ON FLANGES, 1/16" THICK PRE-FORMED NEOPRENE GASKETS, PLUG VALVES UP TO AND INCLUDING 2" SHALL BE BRONZE BODY, BRONZE TAPERED PLUG, NON-LUBRICATING, TEFLON PACKING, THREADED ENDS. OVER 2" USE CAST IRON BODY AND PLUG, NON-LUBRICATED, TEFLON PACKING, FLANGED ENDS. USE DIELECTRIC UNIONS WHEN DISSIMILAR MATERIALS ARE JOINED TOGETHER. ALL SUPPORTS AND ANCHORS SHALL BE CONFORMING WITH ASME B31.9, AND MSS SP58, 69 & 89. COORDINATE A15.1 LOCATION OF THE GAS METER WITH THE GAS COMPANY. PROVIDE A MAIN GAS SHUTOFF VALVE ON GAS PIPING RISER AT METER. COVER ALL GAS PIPING WITH (1) LAYER OF PRIMER AND (2) COATS OF YELLOW WEATHER RESISTANT GLOSS TYPE PAINT AND IDENTIFY GAS PIPING WITH ANSI APPROVED TYPE PLASTIC MARKERS.
11. – THE FUEL OIL PIPING ABOVE GRADE SHALL BE COPPER TUBING ASTM B88, TYPE K HARD DRAWN, WITH CAST BRONZE FITTINGS ASME 16.18, AND BCuQ SILVER BRAZED JOINTS NFPA-30, OR STEEL PIPE ASTM A53, SCHEDULE 40, WITH ASTM B16.3 MALLEABLE IRON FITTINGS ASTM B16.3 AND NFPA-30 THREADED JOINTS.
12. – THE HEATING PIPING ABOVE GRADE SHALL BE STEEL, ASTM A53, SCHEDULE 40, BLACK, WITH MALLEABLE IRON FITTINGS ASME B16.3 (UP TO AND INCLUDING 2") AND FORGED STEEL ASTM A234 (ABOVE 2") WITH THREADED JOINTS (UP TO AND INCLUDING 2") AND WELDED JOINTS (ABOVE 2") ANSI B31.1, B31.2 & B31.9. OR MECHANICAL JOINTS. FLANGES, UNIONS AND COUPLING 2" AND UNDER SHALL BE FERROUS PIPE, MALLEABLE IRON WITH THREADED UNIONS, RATED FOR 150 PSI. ON PIPING OVER 2" USE FORGED STEEL SLIP ON FLANGES, 1/16" THICK PRE-FORMED NEOPRENE GASKETS. PLUG VALVES UP TO AND INCLUDING 2" SHALL BE BRONZE BODY, BRONZE TAPERED PLUG, NON-LUBRICATING, TEFLON PACKING, THREADED ENDS. OVER 2" USE CAST IRON BODY AND PLUG, NON-LUBRICATED, TEFLON PACKING, FLANGED ENDS. USE DIELECTRIC UNIONS WHEN DISSIMILAR MATERIALS ARE JOINED TOGETHER. ALL SUPPORTS AND ANCHORS SHALL BE CONFORMING WITH ASME B31.9, AND MSS SP58, 69 & 89. PROVIDE MECHANICAL JOINTS WITH GROOVED PIPE AND FITTINGS WHERE INDICATED ON DRAWINGS, WITH DAMPER TRANS NOT LESS THAN FORMED 13-GAUGE GALVANIZED STEEL, FURNISHED WITH 24VAC ACTUATORS. CONNECT ALL LOCAL CONTROLLERS, CONTROL PANELS, ETC. TO THE EXISTING EXPANDED ENERGY MANAGEMENT SYSTEM (EMS). REFER TO DRAWINGS FOR THE MINIMUM INPUT/OUTPUT CONTROL POINTS REQUIRED TO BE MONITORED VIA EMS.
ALL CONTROL WIRING SHALL BE COPPER, TWISTED PAIR SHIELDED TYPE, #16 AWG OR BETTER. MOUNT ALL CONTROL WIRING IN EMT CONDUITS IN DRY INTERIOR SPACES, AND MOUNT SAME IN GALVANIZED STEEL CONDUITS WITH LIQUIDTIGHT FITTINGS IN INTERIOR WET SPACES (SUCH AS BOILER ROOM) OR IF EXPOSED OUTSIDE.
13. – FURNISH & INSTALL EQUIPMENT NAMEPLATES, PIPE MARKERS, DUCTWORK STENCILS, VALVE TAGS, ETC., MARKERS, IN COMPLIANCE WITH ANSI A13.1.
14. – PROVIDE THREE (3) SETS OF "AS-BUILT" DRAWINGS TO THE PROJECT ENGINEER FOR FINAL REVIEW AND APPROVAL AT PROJECT COMPLETION.
15. – THIS PROJECT SHALL BE DEEMED COMPLETE ONLY AFTER IS THOROUGHLY INSPECTED, DEMONSTRATED TO AND APPROVED IN WRITING BY THE LOCAL AUTHORITIES HAVING JURISDICTION, OWNER'S REPRESENTATIVE AND ARCHITECT/ENGINEER. ALL WARRANTIES SHALL START AFTER RECEIVING THESE APPROVALS.

CONSTRUCTION NOTES:

1. EXISTING AHU1 THRU 4 LOCATED AT MEZZANINE LEVEL TO REMAIN. REPLACE ALL EXISTING PNEUMATIC CONTROLS WITH NEW ELECTRIC CONTROLS. PROVIDE DEMAND VENTILATION CONTROLLER AND SET MINIMUM OUTSIDE AIR TO 10%. PROVIDE THE FOLLOWING INPUT/OUTPUT POINTS TO EXISTING EXPANDED EMS:
   - FAN START/STOP/STATUS
   - OUTSIDE, RETURN & MIXED AIR TEMPERATURES
   - OUTSIDE, RETURN & EXHAUST AIR MOTORIZED DAMPERS
   - DISCHARGE AIR TEMPERATURE
   - DISCHARGE AIR PRESSURE
   - HEATING COIL VALVE
   - FILTER STATUS
   - SUPPLY SMOKE DETECTOR
   - DEMAND VENTILATION CONTROLLER
2. EXISTING P7, 8 & 9 LOCATED AT MEZZANINE LEVEL TO REMAIN. REPLACE ALL EXISTING PNEUMATIC CONTROLS WITH NEW ELECTRIC CONTROLS. PROVIDE THE FOLLOWING INPUT/OUTPUT POINTS TO THE EXISTING EXPANDED EMS:
   - PUMP START/STOP/STATUS
3. EXISTING PNEUMATIC CONTROL VALVE TO BE REPLACED WITH AN ELECTRIC (24VAC) VALVE. PROVIDE THE FOLLOWING INPUT/OUTPUT POINTS TO EXISTING EMS:
   - HEATING COIL VALVE
4. EXISTING PNEUMATIC THERMOSTAT TO BE REPLACED WITH AN ELECTRIC (24VAC) THERMOSTAT/TEMPERATURE SENSOR, FURNISHED WITH CLEAR LOCKABLE COVER (TYP). PROVIDE THE FOLLOWING INPUT/OUTPUT POINTS TO EXISTING EMS:
   - SPACE TEMPERATURE
5. EXHAUST FAN ON ROOF TO REMAIN.
6. EXISTING CABINET UNIT HEATER TO REMAIN. REPLACE ALL EXISTING PNEUMATIC CONTROLS WITH ELECTRIC CONTROLS. PROVIDE THE FOLLOWING INPUT/OUTPUT POINTS TO EXISTING EMS:
   - FAN START/STOP/STATUS
   - DISCHARGE AIR TEMPERATURE
   - HEATING COIL VALVE
   - FILTER STATUS
7. NEW ELECTRIC UNIT HEATER. PROVIDE THE FOLLOWING INPUT/OUTPUT POINTS TO EMS:
   - FAN START/STOP/STATUS
   - ELECTRIC RESISTANCE COIL
   - SPACE TEMPERATURE
8. LINE OF EXISTING FURNACE COIL UNIT TO BE DISCONNECTED, REMOVED, AND DISPOSED OF IN A LEGAL MANNER.
9. LINE OF EXISTING CEILING CABINET EXHAUST FAN CONTROLLED FROM LOCAL SWITCH TO REMAIN. CHECK FAN OPERATION AND PROVIDE ANY NECESSARY REPAIRS TO RENDER THIS EXHAUST FAN OPERATIONAL.
10. LINE OF NEW UNIT VENTILATOR. PROVIDE THE FOLLOWING INPUT/OUPUT POINTS TO EXISTING EMS:
    - FAN START/STOP/STATUS
    - OUTSIDE, RETURN & MIXED AIR TEMPERATURES
    - OUTSIDE AIR MOTORIZED DAMPER
    - DISCHARGE AIR TEMPERATURE
    - DISCHARGE AIR PRESSURE
    - HEATING COIL VALVE
    - FILTER STATUS
    - DEMAND VENTILATION CONTROLLER
    - SPACE TEMPERATURE VIA INTERLOCK WITH FINNED-TUBE RADIATION CONTROL VALVE
11. LINE OF EXISTING HOT WATER SUPPLY & RETURN RISERS FROM TUNNEL BELOW. ALL NEW UNIT VENTILATORS WILL REQUIRE TO BE ALIGNED WITH THE EXISTING FAN-COILS RIGHT HAND SIDE, SUCH THAT THE NEW UNITS PIPING COMPARTMENT WILL FALL AT PRESENT LOCATION. THE EXISTING FINNED-TUBE RADIATION ENCLOSURES WILL REQUIRE TO BE FIELD ADJUSTED, AS NECESSARY TO WORK WITH THE NEW UNIT VENTILATORS. ALL EXISTING BOOKCASES OR BUILT-IN CABINETRY WILL REQUIRE TO BE REMOVED AND RELOCATED AS NECESSARY TO PROVIDE THIS WORK.
12. LINE OF THE NEW UNIT VENTILATOR OUTSIDE AIR LOUVER/BOX. CAREFULLY CUT THE EXISTING WALL AS NECESSARY TO ACCOMODATE THE NEW LOUVER/BOX. SEAL WATERTIGHT THE NEW LOUVER/BOX TO THE NEW WALL OPENING.
13. LINE OF EXISTING UNIT VENTILATOR TO BE DISCONNECTED, REMOVED AND DISPOSED OF IN A LEGAL MANNER.
14. EXISTING INDOOR UNIT PART OF THE 4–TON SPLIT COOLING SYSTEM TO BE DISCONNECTED, REMOVED AND TURNED OVER TO THE OWNER'S REPRESENTATIVE. COLLECT ALL REFRIGERANT AS REQUIRED BY ASHRAE 15. RE-CONNECT THE EXISTING REFRIGERATION PIPING TO THE DX COIL IN THE NEW UNIT VENTILATOR UV5. PROVIDE INITIAL REFRIGERATION CHARGE, CHECK FOR LEAKS, PROVIDE ANY NECESSARY REPAIRS FOR A LEAK FREE INSTALLATION AND RE-FILL AS REQUIRED.
15. EXISTING OUTDOOR UNIT PART OF THE 4–TON SPLIT COOLING SYSTEM TO BE RE-USED IN CONNECTION WITH THE NEW UNIT VENTILATOR UV5. REFER TO THE NOTE #14 ABOVE.

SEQUENCES OF OPERATION

EXISTING AIR HANDLING UNITS AT MEZZANINE LEVEL

THE OPERATION OF THE AIR HANDLING UNITS SHALL BE CONTROLLED AND MONITORED VIA THE EXISTING EXPANDED ENERGY MANAGEMENT SYSTEM (EMS). THE AIR HANDLING UNITS FANS SHALL OPERATE CONTINUOUSLY DURING THE OCCUPIED HOURS AND CYCLE DURING THE OCCUPIED HOURS, AS SCHEDULED FROM EMS. THE OUTSIDE AIR MOTORIZED DAMPERS SHALL OPEN TO THEIR MINIMUM POSITIONS DURING THE OCCUPIED HOURS AND BE FULLY CLOSED DURING THE UNOCCUPIED HOURS, AS SCHEDULED FROM EMS. THE RELATED EXHAUST FANS SHALL OPERATE ONLY DURING THE OCCUPIED HOURS, AS SCHEDULED FROM EMS. THE NEW 3-WAY HEATING MIXING CONTROL VALVES, REPLACING THE EXISTING PNEUMATIC CONTROL VALVES SHALL MODULATE IN RESPONSE TO THE HEATING THERMOSTATS/TEMPERATURE SENSORS FURNISHED WITH CLEAR LOCKABLE COVERS, AS REQUIRED TO MAINTAIN THE SPACES TEMPERATURE SETTINGS. SET AIR HANDLING UNITS UNITS TO OPERATE AT 70 F DURING OCCUPIED & 55 F DURING UNOCCUPIED HEATING.
IF ANY UNIT DISCHARGE AIR TEMPERATURE EQUALS OR EXCEEDS 135 F OR FALLS BELOW 40 F, THE UNIT EVAPORATOR FAN SHALL SHUT DOWN, OUTSIDE AIR MOTORIZED DAMPER SHALL FULLY CLOSE, AND AN ALARM SIGNAL BE GENERATED TO EMS.
IF SMOKE IS DETECTED ON ANY UNIT SUPPLY MAIN, AS SENSED BY A DUCT MOUNTED SMOKE DETECTOR, THE UNIT EVAPORATOR FAN SHALL SHUT DOWN, THE OUTSIDE AIR MOTORIZED DAMPER SHALL FULLY CLOSE, AND AN ALARM SHALL BE GENERATED TO EMS AND BUILDING'S FIRE ALARM CONTROL PANEL.
REFER TO DRAWINGS FOR THE INPUT/OUTPUT CONTROL POINTS REQUIRED TO BE PROVIDED TO THE EXISTING EXPANDED EMS.

NEW UNIT VENTILATORS

THE OPERATION OF THE NEW UNIT VENTILATORS SHALL BE CONTROLLED AND MONITORED VIA THE EXISTING EXPANDED ENERGY MANAGEMENT SYSTEM (EMS). THE UNIT VENTILATOR FAN SHALL OPERATE CONTINUOUSLY DURING THE OCCUPIED HOURS AND CYCLE DURING THE UNOCCUPIED HOURS, USING ASHRAE CYCLE II WITH THE EXCEPTION BELOW INDICATED, AS LOCALLY CONTROLLED AND SCHEDULED FROM THE EMS. SET EACH UNIT VENTILATOR TO MAINTAIN 70 F DURING THE OCCUPIED AND 55 F DURING UNOCCUPIED HEATING, FROM ITS WALL MOUNTED THERMOSTAT/TEMPERATURE SENSOR FURNISHED WITH CLEAR LOCKABLE COVER. EACH UNIT VENTILATOR SHALL FIRST START, OPERATING IN WARM-UP MODE WITH OUTSIDE AIR DAMPER FULLY CLOSED AND WITH THE 3-WAY HEATING CONTROL VALVE FULLY OPEN UNTIL THE ROOM TEMPERATURE REACHES ITS OCCUPIED SETPOINT. AFTER THE WARM-UP PERIOD EACH UNIT VENTILATOR OUTSIDE AIR MOTORIZED DAMPER SHALL FIRST OPEN TO ITS MINIMUM POSITION VIA THE DEMAND VENTILATION CONTROLLER AND THE 3-WAY HEATING CONTROL VALVE SHALL MODULATE ACCORDINGLY AS TO MAINTAIN THE ROOM TEMPERATURE SETPOINT. THE MECHANICAL COOLING SHALL BE ACTIVATED ANY TIME THE SPACE TEMPERATURE EQUALS OR EXCEEDS THE THERMOSTAT/TEMPERATURE SENSOR SETTING. IF THE CO2 LEVEL OF ANY UNIT, MONITORED BY THE DEMAND VENTILATION CONTROLLER, EQUALS OR EXCEEDS 800 PPM (I.E. ADJUSTABLE), AS SENSED BY THE CO2 SENSOR, THE OUTSIDE AIR MOTORIZED DAMPER SHALL MODULATE TOWARDS ITS FULLY OPEN POSITION UNTIL THE CO2 LEVEL FALLS BELOW ITS SETTING. IF THE ROOM TEMPERATURE RISES ABOVE THE OCCUPIED SETPOINT, THE ECONOMIZER CONTROLLER SHALL BE ENABLED, THE OUTSIDE AIR MOTORIZED DAMPER SHALL MODULATE TOWARDS ITS FULLY OPEN POSITION WITH THE HEATING CONTROL VALVE FULLY CLOSED. A LOW-LIMIT THERMOSTAT/TEMPERATURE SENSOR MOUNTED IN EACH UNIT SHALL PREVENT THE DISCHARGE AIR TEMPERATURE TO BE TOO LOW AND CAUSE DISCOMFORT TO OCCUPANTS OR EVENTUALLY FREEZE-UP OF THE HEATING COIL. IF ROOM TEMPERATURE FALLS BELOW THE SETPOINT, THE OUTSIDE AIR DAMPER SHALL MODULATE BACK TO ITS MINIMUM POSITION DICTATED BY THE DEMAND VENTILATION CONTROLLER.

EXISTING CONVECTORS AND CABINET UNIT HEATERS

THE OPERATION OF THE NEW UNIT VENTILATORS SHALL BE CONTROLLED AND MONITORED VIA THE EXISTING EXPANDED ENERGY MANAGEMENT SYSTEM (EMS). THE UNIT VENTILATOR FANS SHALL OPERATE CONTINUOUSLY DURING THE

EXISTING & NEW EXHAUST FANS

THE OPERATION OF THE EXHAUST FANS SHALL BE CONTROLLED AND MONITORED VIA THE EXISTING EXPANDED ENERGY MANAGEMENT SYSTEM (EMS). THE EXHAUST FANS SHALL OPERATE CONTINUOUSLY DURING THE OCCUPIED HOURS, AS SCHEDULED FROM EMS, UNLESS OTHERWISE NOTED.
REFER TO DRAWINGS FOR THE INPUT/OUTPUT CONTROL POINTS REQUIRED TO BE PROVIDED TO THE EXISTING EXPANDED EMS. NOTE, THAT THE KITCHEN & DISHWASHER EXHAUST FANS SHALL BE OPERATED FROM THE CURRENT LOCAL SWITCHES, BUT THEY WOULD BE PREVENTED TO RUN DURING THE UNOCCUPIED HOURS VIA EMS, IF THE SWITCHES ARE LEFT THE "ON" POSITIONS.

KEY PLAN



ROSE • TISO & CO. LLC.
ARCHITECTS • SURVEYORS • ENGINEERS
WWW.ROSETISO.COM
35 BRENTWOOD AVENUE, FAIRFIELD, CT 06825
TEL: (203)610-6262 • FAX: (203)610-6404

MUSCO ENGINEERING ASSOCIATES
375 Morgan Lane, Unit 307
West Haven, CT 06516
(203) 932-1901 FAX (203) 931-1550
www.muscoengineering.com

DUMITRU T. PETRESCU, P.E., LLC
MECHANICAL ENGINEER

REVISIONS

NO.	BY	DATE	DESCRIPTION

PROJECT TITLE

RACE BROOK SCHOOL
107 GRANNIS ROAD
ORANGE, CT
STATE PROJECT NO:
TMP-107-QGCV

BOILERS & UNIT VENT. REPLACEMENTS

ORANGE CONNECTICUT 1822 TOWN SEAL

Prepared For:

TOWN OF ORANGE, CT
637 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE

PART FLOOR PLAN MECHANICAL

DESIGNED BY: DTP	SCALE: AS NOTED
DRAWN BY: CP	DATE: 7-08-13
CHECKED BY: DTP	PROJECT NUMBER: 1605
CAD FILE: M103.DWG	

SEAL

SHEET NUMBER

RB-M103

MEA# 130416-1



BOILER ROOM - DEMOLITION PLAN - MECHANICAL

SCALE: 1/2"=1'-0"

LEGEND & ABBREVIATIONS

———	EXISTING EQUIPMENT/PIPING TO REMAIN
//////	EXISTING EQUIPMENT/PIPING TO BE REMOVED
———	NEW EQUIPMENT/PIPING
B#	BOILER
HEX#	HEAT EXCHANGER
BFS#	BOILERS FEED SYSTEM
ST#	STORAGE TANK
P#	HEATING/RECIRCULATION PUMP
EXT#	EXPANSION TANK
CAC#	CONTROLS AIR COMPRESSOR
CP#	CONTROL PANEL
BD	BAROMETRIC DAMPER WITH THERMAL LINK SWITCHES
MD	MOTORIZED DAMPER
DWH#	DOMESTIC WATER HEATER
IWH#	INDIRECT WATER HEATER
AHU#	AIR HANDLING UNIT
RTU#	ROOFTOP UNIT
EF#	EXHAUST FAN
P#	PUMP
FC#	FAN-COIL UNIT
C	CONVECTOR
CUH	CABINET UNIT HEATER
UH	UNIT HEATER
FT	FINNED-TUBE RADIATION
EB	ELECTRIC BASEBOARD RADIATION
EUH	ELECTRIC UNIT HEATER
GIH	GRAVITY INTAKE HOOD
CW	COLD WATER PIPING
HW	HOT WATER PIPING
R	DOMESTIC RECIRCULATION HOT WATER PIPING
LPS/LPR	LOW PRESSURE STEAM/RETURN PIPING
PC	PUMPED CONDENSATE
HWS/HWR	HOT WATER SUPPLY/RETURN PIPING
G	GAS PIPING
CD	CONDENSATE DRAIN PIPING
AS#	AIR SEPARATOR
FOS/FOR	FUEL OIL SUPPLY/RETURN PIPING
CMD#	CARBON MONOXIDE DETECTOR
RD	ROOF DRAIN
PV	PLUMBING VENT
VD	VOLUME DAMPER
MD	MOTORIZED DAMPER
BFP	BACKFLOW PREVENTER
FT	FLUE TEMPERATURE INDICATOR
	GATE VALVE
	PLUG VALVE
	BALL VALVE
	2-WAY CONTROL VALVE (PNEUMATIC)
	2-WAY CONTROL VALVE (ELECTRIC/ ELECTRONIC)
	3-WAY CONTROL VALVE (ELECTRIC/ ELECTRONIC)
	CHECK VALVE
	BUTTERFLY VALVE
	PRESSURE REDUCING VALVE
	BACKFLOW PREVENTER
	FLOW CONTROL VALVE
	STRAINER
	RELIEF VALVE
	BALANCING VALVE
	FUSOMATIC OIL VALVE
OCF	OIL CARTRIDGE FILTER
T	THERMOSTAT/TEMPERATURE SENSOR
	TEMP. SENSOR/CONTROLLER WITH WELL
	WITH WELL PRESS. SENSOR/CONTROLLER WITH WELL
S	SERVICE SWITCH
S_{EM}	EMERGENCY SHUTDOWN SWITCH
LWCO	LOW WATER CUT OUT CONTROLLER
VFD#	VARIABLE FREQUENCY DRIVE
PCP#	PUMPS CONTROL PANEL
T	TEMPERATURE GAUGE
TS	THERMAL SWITCH, SET AT 165 F
S_D	SMOKE DETECTOR, DUCT MOUNTED
C	DEMAND VENTILATION CONTROLLER
SDRTS	SMOKE DETECTOR REMOTE TEST STATION
	EQUIPMENT STARTER
E	EXISTING TO REMAIN
ER	EXISTING TO BE RELOCATED
R	EXISTING TO BE REMOVED
	CONNECT TO EXISTING

EXISTING EQUIPMENT

BOILERS

B1 & 2 BOILER, CAST IRON, OIL-FIRED, LOW PRESSURE STEAM TYPE, "WEIL-McLAIN", MODEL 1194-S, RATED FOR 86.7 BOILER HP, 3,608 MBH INPUT, 2,904 MBH I=B=R GROSS OUTPUT & 9,396 SQFT EDR STEAM OR 2,225.04 MBH NET HEATING OUTPUT, USING AN OIL BURNER "POWER FLAME", MODEL C3-0-25 RATED FOR USING 25.0 GPH FUEL OIL #2, 2 HP BURNER MOTOR @ 208V/3 PH AND 120V/1 PH CONTROL CIRCUIT, UL LISTED. EACH BOILER IS FURNISHED WITH (4) TANKLESS DOMESTIC WATER HEATERS, EACH "TRIANGLE TUBE", MODEL #92K34.

HEATING EXCHANGERS

HEX1 HEAT EXCHANGER, STEAM TO HOT WATER HORIZONTAL TYPE, "B&G", MODEL N2/25, CAPACITY N/A, MOUNTED ON A STRUCTURAL SUPPORT IN BOILER ROOM.

HEX2 HEAT EXCHANGER, STEAM TO HOT WATER HORIZONTAL TYPE, "B&G", MODEL & CAPACITY N/A, MOUNTED ON A STRUCTURAL SUPPORT AT MEZZANINE LEVEL.

BOILERS FEED SYSTEM

BFS1 BOILERS FEED SYSTEM, "SHIPCO", MODEL N/A, RATED, DUPLEX TYPE EACH RATED FOR 15 GPM @ 20 PSI, 1/3 HP @ 120V/1 PH.

STORAGE TANKS

ST1 & 2 STORAGE TANK FOR DOMESTIC HOT WATER, 120 GALLONS CAPACITY, VERTICAL TYPE, USED IN CONJUNCTION WITH THE BOILERS' B1 & 2 TANKLESS WATER HEATERS.

HEATING PUMPS

P1 & 2 PUMP, END SUCTION BASE MOUNTED TYPE, "B&G", MODEL 1510, SIZE 3BB, RATED FOR 153 GPM @ 69 FT HEAD, 5 HP PUMP MOTOR @ 208V/3 PH, UL LISTED, FURNISHED WITH END SUCTION DIFFUSER AND DISCHARGE TRIPLE-DUTY VALVE.

P3 PUMP, IN-LINE TYPE, "B& G", MODEL & CAPACITY N/A.

RECIRCULATING PUMPS (DOMESTIC HOT WATER)

P4 & 5 PUMP, IN LINE TYPE FOR DOMESTIC WATER RECIRCULATION, MAKE, MODEL & SIZE N/A.

EXPANSION TANKS

EXT1 & 2 EXPANSION TANK, VERTICAL PRESSURIZED TYPE, "EXTROL", MODEL SX110V TO REMAIN.

EXT3 EXPANSION TANK, VERTICAL PRESSURIZED TYPE LOCATED AT MEZZANINE LEVEL TO REMAIN.

CONTROLS AIR COMPRESSOR

CAC1 CONTROL AIR COMPRESSOR, DUPLEX TYPE WITH HORIZONTAL RECEIVER TAN, "QUINEY", MODEL QHPRS-10, SIZE AND RATING N/A.

CONTROL PANELS

CP1 CONTROL PANEL, FORMER "JOHNSONS CONTROLS" PANEL WITH DDC CONTROLLER "EASY IO 30P" INSIDE TO REMAIN.

CP2 DDC CONTROLLER, "TOUR ANDERSON", MODEL TA290W TO REMAIN.

CP3 OIL INVENTORY DEVICE TO REMAIN.

DEMOLITION NOTES

1. EXISTING CAST-IRON, HOT WATER, OIL-FIRED BOILER TO BE DRAINED, DISCONNECTED, AND REMOVED FROM THE BOILER ROOM TO A LOCATION APPROVED BY THE OWNER'S REPRESENTATIVE, ONLY AFTER THE ASBESTOS CONTENT MATERIALS HAVE BEEN REMOVED BY OTHERS IN A LEGAL MANNER. THE OWNER'S REPRESENTATIVE WILL BE RESPONSIBLE FOR DISPOSAL OF THE BOILER' S SECTIONS AND ALL OTHER METAL PARTS.
2. FUEL OIL #2 BURNER TO BE DISCONNECTED, REMOVED AND TURNED OVER TO THE OWNER'S REPRESENTATIVE OR DISPOSED OF IN A LEGAL MANNER, IF SO DECIDED BY THE OWNER'S REPRESENTATIVE.
3. SHELL & TUBE HEAT EXCHANGER TO BE DRAINED, DISCONNECTED, REMOVED AND DISPOSED OF IN A LEGAL MANNER, INCLUDING ITS STRUCTURAL SUPPORT.
4. BOILER FEED SYSTEM SHALL BE DRAINED, DISCONNECTED, REMOVED AND DISPOSED IN A LEGAL MANNER.
5. STORAGE TANK TO BE DRAINED, DISCONNECTED AND DISPOSED OF IN A LEGAL MANNER.
6. EXISTING HEATING PUMPS P1 & 2 TO REMAIN.
7. EXISTING HEATING PUMP P3 TO REMAIN.
8. EXISTING DOMESTIC HOT WATER RECIRCULATION PUMPS P4 & 5 TO REMAIN.
9. EXISTING EXPANSION TANK TO REMAIN.
10. CONTROLS AIR COMPRESSOR TO BE DISCONNECTED, REMOVED AND TURNED OVER TO THE OWNER'S REPRESENTATIVE.
11. EXISTING CONTROL PANEL TO REMAIN.
12. EXISTING BOILERS' VENTS AND BREECHING TO BE DISCONNECTED, REMOVED AND DISPOSED IN A LEGAL MANNER. ANY ASBESTOS CONTAINING MATERIALS SHALL BE REMOVED BY OTHERS HIRED BY THE OWNER'S REPRESENTATIVE, PRIOR TO STARTING THIS WORK.
13. EXISTING MASONRY LINED CHIMNEY WITH INSPECTION AND SERVICE ACCESS DOOR, 32'-6" HIGH MEASURED FROM THE BOILER ROOM FLOOR LEVEL TO THE TOP OF MASONRY WITH FLUE FURTHER EXTENDED AT LEAST 8'-0" FROM THE TOP OF CHIMNEY, TO BE RE-USED THIS CHIMNEY SHALL BE FULLY INSPECTED, THOROUGHLY CLEANED AND CERTIFIED, PRIOR TO FINAL COMPLETION AND COMMISSIONING. SUPPORT THE FLUE EXTENDED ABOVE THE MASONRY CHIMNEY WITH STAINLESS STEEL GUY WIRES.
14. EXISTING AIR SEPARATOR LOCATED IN BOILER ROOM TO BE DISCONNECTED, REMOVED AND DISPOSED OF IN A LEGAL MANNER.
15. DRAIN, DISCONNECT AND DISPOSE OF IN A LEGAL MANNER OF ALL EXISTING LOW PRESSURE STEAM (LPS), LOW PRESSURE RETURN STEAM CONDENSATE (LPR), AND PUMPED CONDENSATE (PC) PIPING, FITTINGS, VALVES, CONTROLS, SUPPORTS, ETC. NO LONGER REQUIRED LOCATED IN EITHER BOILER ROOM AND ADJACENT MEZZANINE MECHANICAL LEVEL.
16. EXISTING HEATING HOT WATER SUPPLY & RETURN PIPING TO BE RE-USED TO THE EXTEND INDICATED.
17. EXISTING FUEL OIL SUPPLY & RETURN (FOS & R) PIPING IN CONCRETE TRENCH TO REMAIN. CAP PIPING INSIDE THE PIPING TRENCH.
18. EXISTING EQUIPMENT STARTERS TO BE REMOVED.
19. CAP EXISTING COMBUSTION AIR DUCTWORK TERMINATED AT CEILING OF THE BOILER ROOM ONLY AFTER THE NEW COMBUSTION AIR DUCTWORK IS INSTALLED AND RENDERED FUNCTIONAL.

SCOPE OF WORK - DEMOLITION

1. - DISCONNECT, REMOVE AND DISPOSE IN A LEGAL MANNER OF ALL EQUIPMENT, MATERIALS, ETC., AS INDICATED, SHOWN OR IMPLIED. DRAIN OR ISOLATE THE HEATING SYSTEM, AS MAY BE REQUIRED TO PERFORM THIS DEMOLITION WORK. NOTE, THAT THERE IS EQUIPMENT INDICATED TO BE REUSED OR TURNED OVER TO THE OWNER'S REPRESENTATIVE.
2. - THIS WORK SHALL BE PERFORMED IN STRICT ACCORDANCE WITH THE 2005 CONNECTICUT STATE BUILDING CODE, 2005 CONNECTICUT STATE FIRE SAFETY CODE, 2003 INTERNATIONAL BUILDING CODE, 2003 INTERNATIONAL MECHANICAL CODE, 2003 INTERNATIONAL PLUMBING CODE, 2005 NATIONAL ELECTRICAL CODE, 2009 & 2011 CONNECTICUT AMENDMENTS TO STATE BUILDING AND FIRE SAFETY CODES, ANY OTHER APPLICABLE CODES, STANDARDS, REGULATIONS, ORDINANCES, AND THE REQUIREMENTS OF THE LOCAL AUTHORITIES AND UTILITIES COMPANIES HAVING JURISDICTION.
3. - THIS CONTRACTOR SHALL PROVIDE A DETAILED SCHEDULE OF DEMOLITION WORK, REQUIRED FOR EACH INDIVIDUAL SYSTEM, COORDINATED WITH THE ANTICIPATED DELIVERIES OF THE NEW EQUIPMENT. THIS PROPOSED SCHEDULE OF DEMOLITION WORK SHALL BE SHALL BE APPROVED IN WRITING BY THE OWNER'S REPRESENTATIVE AND ALSO APPROVED IN WRITING BY THE PROJECT ENGINEER, PRIOR TO STARTING ANY CONSTRUCTION WORK.
4. - NOTE, THAT THE G.C. SHALL BE RESPONSIBLE FOR SAFE REMOVAL AND LEGAL DISPOSAL OF ANY ASBESTOS CONTAINING MATERIALS LOCATED IN THIS BOILER ROOM, IF ANY, PRIOR TO STARTING THIS WORK. NO MECHANICAL WORK IS PERMITTED UNTIL THE ASBESTOS REMOVAL WORK IS DEEMED COMPLETED AND FINAL AIR SAMPLES ARE PERFORMED.
5. - DRAIN, DISCONNECT AND ISOLATE THE EXISTING BOILERS B1 B2. DISASSEMBLE THESE BOILERS SECTIONS AND SAFELY REMOVE THEM THROUGH THE EXISTING DOORS' OPENINGS.
6. - DRAIN, DISCONNECT, REMOVE AND DISPOSE IN A LEGAL MANNER OF EXISTING HEAT EXCHANGERS, BOILERS FEED SYSTEM, STORAGE TANKS, THEIR BASE SUPPORTS, CONNECTED LOW PRESSURE STEAM & CONDENSATE PIPING, ETC.
7. - DRAIN, DISCONNECT AND REMOVE IN A LEGAL MANNER OF EXISTING AIR SEPARATOR, AND LIMITED HOT WATER SUPPLY & RETURN PIPING TO THE EXTENT SHOWN OR REQUIRED.
8. - DISCONNECT, REMOVE AND DISPOSE OF IN LEGAL MANNER OF EXISTING BOILERS' VENTS AND BREECHINGS. HIRE THE SERVICES OF AN INDEPENDENT CERTIFIED CHIMNEY SWEEPER TO THOROUGHLY INSPECT AND CLEAN EXISTING CHIMNEY'S FLUES, PROVIDE THREE (3) COPIES OF THIS CHIMNEY REPORT TO THE PROJECT ENGINEER AT COMPLETION OF THE DEMOLITION WORK.
9. - CAREFULLY DRAIN, DISCONNECT FUEL OIL SUPPLY & RETURN PIPING, VALVES & OIL SPECIALTIES, SUPPORTS, ETC., CONNECTED TO EXISTING BOILERS, AND CAP EXISTING PIPING IN THE CONCRETE TRENCH.
10. - DRAIN, AND DISCONNECT EXISTING COLD WATER (CW) PIPING CONNECTED TO EXISTING BOILERS AND BOILERS FEED SYSTEM.
11. - TEMPORARILY IDENTIFY ALL CAPPED PIPING CONNECTIONS WITH PLASTIC MARKERS, AS TO CLEARLY EASE THE CONSTRUCTION WORK, REQUIRED TO BE PERFORMED LATER.
12. - THIS CONTRACTOR SHALL BE A CERTIFIED CONTRACTOR IN THE STATE OF CONNECTICUT, SPECIALIZED IN THIS TYPE OF WORK. THIS CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING CONSTRUCTION PERMITS, PAY ALL REQUIRED FEES, APPLICABLE TAXES, ETC., IF ANY, AND PERFORM ALL TESTS REQUESTED BY THE LOCAL AUTHORITIES HAVING JURISDICTION.
13. - THIS DEMOLITION WORK SHALL BE DEEMED COMPLETE ONLY AFTER IS INSPECTED, AND APPROVED IN WRITING BY PROJECT ENGINEER AND OWNER'S REPRESENTATIVE.



KEY PLAN

GENERAL NOTE

REFER TO DRAWING RB-M106 FOR THE BOILER ROOM NEW EQUIPMENT SELECTION AND SPECIFICATIONS.

GENERAL NOTES

1. - THE INFORMATION SHOWN ON THIS DRAWING IS BASED UPON THE INFORMATION SHOWN ON THE BUILDING PLANS AND LIMITED FIELD INVESTIGATIONS AND MAY OR MAY NOT REFLECT ACTUAL FIELD CONDITIONS. THIS CONTRACTOR SHALL VERIFY THE INFORMATION INDICATED ON THIS DRAWING AND NOTIFY THE ENGINEER OF ANY DISCREPANCIES PRIOR TO SUBMITTING HIS BID.
2. - THIS CONTRACTOR IS REQUIRED TO PERFORM THIS WORK IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, ORDINANCES, ETC., AND TO MEET THE REQUIREMENTS OF THE LOCAL AUTHORITIES HAVING JURISDICTION AND OWNER, WHETHER OR NOT SPECIFICALLY INDICATED OR SPECIFIED ON THIS DRAWING.
3. - THE CONTRACTOR SHALL SEAL ALL PENETRATIONS THROUGH FIRE RATED WALLS AS INDICATED ON DWG. RB-EG101 WITH A U.L. LISTED FIRESTOP TO MAINTAIN THE INTEGRITY OF THE FIRE RATING. PROVIDE SHOP DRAWINGS FOR ALL PENETRATIONS. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.

ROSE •TISO & Co. LLC.
ARCHITECTS • SURVEYORS • ENGINEERS
www.rosetiso.com
35 Brentwood Avenue, Fairfield, CT 06825
tel: (203)610-6262 • fax: (203)610-6404

MUSCO ENGINEERING ASSOCIATES
375 Morgan Lane, Unit 307
West Haven, CT 06516
(203) 932-1901 FAX (203) 931-1550
www.muscoengineering.com

DUMITRU T. PETRESCU, P.E., LLC
MECHANICAL ENGINEER

REVISIONS			
NO.	BY	DATE	DESCRIPTION

PROJECT TITLE

RACE BROOK SCHOOL
107 GRANNIS ROAD
ORANGE, CT
STATE PROJECT NO:
TMP-107-QGCV

BOILERS & UNIT VENT. REPLACEMENTS

Prepared For:

TOWN OF ORANGE, CT
637 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE

BOILER ROOM PLAN DEMOLITION MECHANICAL

DESIGNED BY: DTP	SCALE: AS NOTED
DRAWN BY: CP	DATE: 7-08-13
CHECKED BY: DTP	PROJECT NUMBER: 1605
CAD FILE: M104.DWG	

SEAL

SHEET NUMBER

RB-M104

MEA# 130416-1



BOILER ROOM FLOOR PLAN - MECHANICAL
SCALE: 1/2"=1'-0"



BOILERS' PIPING SCHEMATIC DIAGRAM
NTS



DETAIL AT BOILERS' SUPPLY MANIFOLD
NTS

CONSTRUCTION NOTES:

1. NEW CAST-IRON, HOT WATER BOILER.
2. NEW DUAL-FUEL BURNER.
3. LINE OF EXISTING CONCRETE FLOOR CHANNEL TO BE RE-USED.
4. LINE OF NEW 5" THICK CONCRETE PAD.
5. NEW 72"x24" COMBUSTION AIR DUCTWORK EXTENDED UP TO THE UPPER COMBUSTION AIR PLENUM AND EXTENDED DOWN TO 12" AFF AND TERMINATED WITH GALVANIZED STEEL AIR MESH.
6. REQUIRED CLEARANCE FOR FLUE BAFFLE 88" FOR NEW BOILERS B1 & 2, AND 48" FOR B3
7. REQUIRED CLEARANCE FOR MODULAR RETURN WATER MIXING TUBE 36" FOR NEW BOILERS BOILERS B1, 2 & 3.
8. BOILER 4" SUPPLY MANIFOLD - REFER TO DETAIL FOR TAPPINGS.
9. BOILER 4" RETURN MANIFOLD - REFER TO DETAIL FOR TAPPINGS.
10. BOILERS 12"ø VENT CONNECTION FOR NEW BOILERS B1 & 2, AND 8"ø FOR B3.
11. NEW BOILER VENT WITH BAROMETRIC DAMPER WITH THERMAL SPILL SWITCH (TYP).
12. NEW BOILER'S BREECHING (TYP).
13. NEW BOILER'S BREECHING CLEANOUT (TYP).
14. NEW BOILER'S FLUE TEMPERATURE INDICATOR/ CONTROLLER FT1, 2 & 3.
15. NEW 72"x24" COMBUSTION AIR DUCTWORK EXTENDED UP TO THE UPPER COMBUSTION AIR PLENUM AND EXTENDED DOWN TO 12" BELOW AND TERMINATED WITH GALVANIZED STEEL AIR MESH.
16. NEW CARBON MONOXIDE DETECTOR WITH INTEGRATED ALARM HORN WITH BUILT-IN TROUBLE/POWER SUPERVISION RELAY. REFER TO SPECS AND SEQUENCE OF OPERATION.
17. NEW 1-1/2"G DN (2,769 CFH @ 5 PSIG) TO GAS PRESSURE REGULATOR DOWN TO 6.5" W.C. AND GE/IRI APPROVED GAS TRAIN.
18. NEW 1"G DN (1,216 CFH @ 5 PSIG) TO GAS PRESSURE REGULATOR DOWN TO 6.5" W.C. AND GE/IRI APPROVED GAS TRAIN.
19. MAKE THE FINAL NATURAL GAS, FOS & R, POWER & CONTROLS CONNECTIONS TO BURNER WITH FLEXIBLE HOSES AND FLEXIBLE CONDUITS, AS TO ALLOW THE BOILER'S DOOR OPENING FOR CLEANING.
20. MODIFY THE EXISTING FOS & R PIPING LOCATED IN THE EXISTING CONCRETE FLOOR TRENCH AS NECESSARY TO ACCEPT NEW OIL STANDPIPE - REFER TO DETAILS.
21. CAP NEW 2" GAS PIPING ABOVE THE EXISTING KITCHEN CEILING. NOTE, THAT THE PRESENT ELECTRICAL KITCHEN APPLIANCES WILL REQUIRE TO BE REPLACED WITH GAS-FIRED KITCHEN APPLIANCES.
22. NEW 2" HIGH PRESSURE (5 PSIG) NATURAL GAS PIPING THRU ROOF IN APPROVED PITCH POCKET. PROVIDE NEW 2" HIGH PRESSURE GAS PIPING ON ROOF FROM THE NEW GAS SERVICE PIPING LOCATED OUTSIDE OF SCIENCE ROOM (145). REFER TO THE ROOF DRAWINGS FOR THE NEW GAS PIPING ROUTING. REFER TO KEY PLAN ON THIS DRAWING. COVER ALL GAS PIPING AND SUPPORTS WITH (1) LAYER OF PRIMER AND (2) LAYERS OF WEATHER RESISTANT ENAMEL YELLOW PAINT.
23. LOCATION OF THE NEW GAS SERVICE PIPING. COORDINATE THE GAS METER INSTALLATION WITH THE GAS COMPANY. PROVIDE A MAIN PLUG SHUTOFF VALVE ON THE NEW GAS METER PIPING RISER.
24. NEW ELECTRIC/ELECTRONIC CONTROLS SHALL REPLACE ALL PNEUMATIC CONTROLS THROUGHOUT THIS BOILER ROOM.
25. LOCATION OF NEW OUTSIDE AIR TEMPERATURE SENSOR TO BE USED BY THE NEW BOILERS B1 & 2. THIS TEMPERATURE SENSOR SHALL BE CONNECTED TO EXISTING EMS.
26. NEW COLD WATER PIPING TO BOILER B1, 2 & 3 LOW WATER CUTOFFS. REFER TO THE DETAILS ON DRAWING RB-M106 FOR LOCATIONS AND SPECIFICATIONS OF THE BACKFLOW PREVENTERS.
27. LOCATION OF THE EXISTING AND RELOCATED BOILERS' EMERGENCY SHUTDOWN SWITCHES. WIRE EACH BOILERS' EMERGENCY SHUTDOWN SWITCH IN SERIES WITH BOILERS' SERVICE AND THERMAL SWITCHES TO BE PERFORMED BY THE ELECTRICAL CONTRACTOR.
28. BOILERS DUAL FUEL SWITCHOVER PANEL (BDFSP1) TO INCLUDE ALL NECESSARY SWITCHES, RELAYS, SAFETY CONTROLS, ETC., AS TO SAFELY ENABLE AUTOMATIC SWITCHING FROM NATURAL GAS TO FUEL OIL#2 AND VICE VERSA OF THE BOILERS DUAL FUEL
29. ALL GAS PRESSURE REGULATORS SHALL BE VENTED FULL SIZE ABOVE THE ROOF LEVEL, TERMINATE THE GAS VENTS 2'-0" ABOVE THE ROOF LEVEL WITH VENT CAPS FURNISHED WITH INSECT SCREENS. ALL ROOF PENETRATIONS SHALL BE PERFORMED IN APPROVED PITCH POCKETS. ALL VENT PIPING SHALL BE COPPER PIPING TYPE L WITH MECHANICAL JOINTS.
30. BOILERS' CONTROL PANEL (BCP1).
31. EXISTING EXPANSION TANKS TO REMAIN.
33. ALL ORIGINAL VALVES LOCATED WITHIN THE BOILER ROOM SHALL BE REPLACED WITH NEW VALVES. ALL EXISTING VALVES TO BE REPLACED AND THE NEW VALVES 2" AND UNDER SHALL BE BALL TYPE, AND ALL VALVES 2-1/2" AND LARGER SHALL BE BUTTERFLY TYPE, UNLESS OTHERWISE NOTED.
34. SINCE, THIS SCHOOL WASTE/SANITARY PIPING DISCHARGES INTO A SEPTIC SYSTEM, ALL PROPOSED CHEMICALS FOR BOILER CLEANING AND WATER TREATMENT WILL REQUIRE TO BE ENVIRONMENTALLY FRIENDLY AND APPROVED BY THE ORANGE SCHOOL DISTRICT, PRIOR TO STARTING THIS WORK. THIS CONTRACTOR SHALL CONTACT "AZURE WATER SERVICES, LLC" AT 203-932-3655 OR OTHER TOWN APPROVED MANUFACTURER AND SUPPLIER OF ENVIRONMENTALLY-RESPONSIBLE PRODUCTS, TO BE USED FOR THIS PROJECT. FILTER BAGS SHALL BE USED TO CAPTURE ANY SOLIDS, PRIOR TO DISCHARGING INTO Sseptic SYSTEM.



KEY PLAN

GENERAL NOTES

1. - THE INFORMATION SHOWN ON THIS DRAWING IS BASED UPON THE INFORMATION SHOWN ON THE BUILDING PLANS AND LIMITED FIELD INVESTIGATIONS AND MAY OR MAY NOT REFLECT ACTUAL FIELD CONDITIONS. THIS CONTRACTOR SHALL VERIFY THE INFORMATION INDICATED ON THIS DRAWING AND NOTIFY THE ENGINEER OF ANY DISCREPANCIES PRIOR TO SUBMITTING HIS BID.
2. - THIS CONTRACTOR IS REQUIRED TO PERFORM THIS WORK IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, ORDINANCES, ETC., AND TO MEET THE REQUIREMENTS OF THE LOCAL AUTHORITIES HAVING JURISDICTION AND OWNER, WHETHER OR NOT SPECIFICALLY INDICATED OR SPECIFIED ON THIS DRAWING.
3. - THE CONTRACTOR SHALL SEAL ALL PENETRATIONS THROUGH FIRE RATED WALLS AS INDICATED ON DWG. RB-EG101 WITH A U.L. LISTED FIRESTOP TO MAINTAIN THE INTEGRITY OF THE FIRE RATING. PROVIDE SHOP DRAWINGS FOR ALL PENETRATIONS. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.

ROSE TISO & CO. LLC.
ARCHITECTS • SURVEYORS • ENGINEERS
WWW.ROSETISO.COM
35 BRENTWOOD AVENUE, FAIRFIELD, CT 06825
TEL: (203)610-6262 • FAX: (203)610-6404

MEA
MUSCO ENGINEERING ASSOCIATES
375 Morgan Lane, Unit 307
West Haven, CT 06516
(203) 932-1901 FAX (203) 931-1550
www.muscoengineering.com

DUMITRU T. PETRESCU, P.E., LLC
MECHANICAL ENGINEER

REVISIONS

NO.	BY	DATE	DESCRIPTION

PROJECT TITLE

RACE BROOK SCHOOL
107 GRANNIS ROAD
ORANGE, CT
STATE PROJECT NO:
TMP-107-QGCV

BOILERS & UNIT VENT. REPLACEMENTS

ORANGE CONNECTICUT 1822 TOWN SEAL

Prepared For:

TOWN OF ORANGE, CT
637 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE

BOILER ROOM PLAN MECHANICAL

DESIGNED BY: DTP	SCALE: AS NOTED
DRAWN BY: DTP	DATE: 7-08-13
CHECKED BY: DTP	PROJECT NUMBER: 1605
CAD FILE: M105.DWG	

SEAL

SHEET NUMBER

RB-M105

MEA# 130416-1

NEW EQUIPMENT

BOILERS

B1 & 2 BOILER, HIGH EFFICIENCY CAST IRON MULTI-PASS COMMERCIAL DUAL FUEL-FIRED TYPE, EQUAL TO "BURNHAM", MODEL MPC14, RATED FOR 60.4 BOILER HP, 2,769 MBH NATURAL GAS AND 2,772 MBH FUEL OIL #2 WITH 19.8 GPH BURNER INPUT, 2,019 MBH NET I=B=R HEATING OUTPUT, 85.8% NATURAL GAS AND 88.4% FUEL OIL #2 COMBUSTION EFFICIENCY, 277.7 SOFT HEATING SURFACE, 211 GALLONS WATER CONTENT, 7,486 LBS SHIPPING WEIGHT AND 12"ø VENT DIAMETER, FURNISHED WITH SAFETY AND OPERATION CONTROLS, PROVIDED WITH DUAL FUEL-FIRED BURNER, EQUAL TO "POWER FLAME", MODEL C3-GO-30, RATED FOR 2,769 GPH FUEL OIL #2 INPUT, 19.8 GPH FUEL OIL #2 INPUT, 1.5 HP BLOWER MOTOR ● 208V/1 PH, 120V/1 PH CONTROL CIRCUIT, 2"/1.5" DUAL SIZE STANDARD GE/IRI APPROVED GAS TRAINS, 6.5" W.C. MINIMUM GAS PRESSURE, UL LISTED. REFER TO SECTION 235011 FOR ADDITIONAL INFO.

B3 BOILER, HIGH EFFICIENCY CAST IRON MULTI-PASS COMMERCIAL DUAL FUEL-FIRED TYPE, EQUAL TO "BURNHAM", MODEL MPC7, RATED FOR 30.6 BOILER HP, 1,216 MBH NATURAL GAS & 1,218 MBH FUEL OIL #2, 8.7 GPH BURNER INPUT, 890 MBH I=B=R NET HEATING OUTPUT, 86.0 NATURAL GAS & 88.1% FUEL OIL #2 COMBUSTION EFFICIENCY, 135.8 SOFT HEATING SURFACE, 108 GALLONS WATER CONTENT, 3733 LBS SHIPPING WEIGHT AND 8"ø VENT DIAMETER, FURNISHED WITH SAFETY AND OPERATION CONTROLS, PROVIDED WITH DUAL FIRED BURNER, EQUAL TO "POWER FLAME", MODEL C1-GO-12, RATED FOR 1,216 MBH NATURAL GAS & 8.7 GPH FUEL OIL #2 INPUT, 1/3 HP BLOWER MOTOR - 120V/1 PH, 120V/1 PH CONTROL CIRCUIT, 1.25"/1" DUAL SIZE STANDARD GE/IRI GAS APPROVED GAS TRAINS, 6.5" MINIMUM GAS PRESSURE, UL LISTED. REFER TO SECTION 235011 FOR ADDITIONAL INFO.

NOTES:
1. – PROVIDE NEW 5" THICK REINFORCED CONCRETE PAD AS INDICATED ON DRAWINGS.
2. – FURNISH BOILERS WITH KNOCKDOWN SECTIONS FOR FIELD INSTALLATION AND TESTING. USE THE EXISTING BOILER'S ROOM ACCESS DOORS.
3. – INSTALL BOILERS ON THE NEW COMMON CONCRETE PAD AND ATTACH BOILERS SEISMICALLY TO THIS PAD. BEFORE INSTALLATION CAN PROCEED, FURNISH STRUCTURAL SHOP DRAWINGS FOR THE BOILERS SEISMIC ATTACHMENTS TO CONCRETE PAD FOR REVIEW BY THE PROJECT ENGINEER. THESE SHOP DRAWINGS SHALL INCLUDE DETAILED CONSTRUCTION DRAWINGS, STAMPED & SIGNED BY A LICENSED STRUCTURAL ENGINEER IN THE STATE OF CONNECTICUT. THESE CALCULATIONS SHALL ACCOUNT FOR MANUFACTURER'S RECOMMENDATIONS WITH REGARDS TO BOILERS' SECTIONS EXPANSION AND CONTRACTION REQUIREMENTS.
4. – PROVIDE BURNERS MOUNTING PLATES, BOILER FITTINGS, AND OTHER PARTS, SUCH AS REQUIRED FOR A COMPLETE OPERATIONAL INSTALLATION. SEISMICALLY SUPPORT BURNERS WITH SUPPORTS ANCHORED TO THE EXISTING CONCRETE SLAB.
5. – ERECT, INSTALL AND TEST BOILERS IN STRICT ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS, RECOMMENDATIONS AND WARRANTY.
6. – CONNECT THE NEW BOILERS TO EXISTING AND NEW UTILITIES SUCH AS: HOT WATER SUPPLY AND RETURN, COLD WATER MAKE-UP, GAS AND FUEL OIL PIPING, CONTROLS, ETC., AS INDICATED AND REQUIRED FOR A COMPLETE OPERATIONAL SYSTEM.
7. – PIPE EACH BOILER RELIEF VALVE AND DRAIN FULL SIZE TO EXISTING DRAIN CHANNEL.
8. – EACH GAS TRAIN MAIN SOLENOID & VENT VALVES, AND GAS PRESSURE REGULATOR SHALL BE INDIVIDUALLY VENTED FULL SIZE OUTSIDE THE BOILER ROOM AND TERMINATED ABOVE THE ROOF VENT CAPS.
9. – PROVIDE TEN (10) YEAR MANUFACTURER'S DEFECT WARRANTY ON SECTIONS AND ONE (1) YEAR OVERALL WARRANTY FOR THIS WORK.

INDIRECT WATER HEATERS

IWH1 & 2 INDIRECT WATER HEATER, "TURBOMAX" MODEL 109, RATED FOR 119 GALLONS CAPACITY, 483 GPH RECOVERY RATE ● 140 F CONTINUOUS FLOW USING 400.0 MBH NET HEATING BOILER CAPACITY WITH 2" HWS & R CONNECTIONS, 29"ø x 72-3/4"H.

NOTES:
1. – PROVIDE NEW 5" THICK REINFORCED CONCRETE PAD AS INDICATED ON DRAWINGS.
2. – INSTALL THE INDIRECT WATER HEATERS IN STRICT ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS, RECOMMENDATIONS AND WARRANTY.
3. – SEISMICALLY ANCHOR THE INDIRECT WATER HEATERS TO THE CONCRETE PAD.
4. – PIPE THE INDIRECT WATER HEATERS AS INDICATED ON THE DETAIL ON THIS DRAWING.

AIR SEPARATORS

AS1 AIR SEPARATOR, FLANGED TYPE, EQUAL TO "B&G", MODEL R-4

AS2 AIR SEPARATOR, FLANGED TYPE, EQUAL TO "B&G", MODEL R-3.

NOTES:
1. – INSTALL AIR SEPARATORS IN STRICT ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS, RECOMMENDATIONS AND WARRANTY.
2. – SEISMICALLY SUPPORT THE AIR SEPARATORS FROM THE EXISTING BUILDING'S STRUCTURAL ELEMENTS.

EXPANSION TANK

EXT3 EXPANSION TANK, VERTICAL PRE-CHARGED DIAPHRAGM TYPE, EQUAL TO "B&G", MODEL D-60V, RATED FOR 33.6 GALLONS CAPACITY AND 11.3 GALLONS ACCEPTANCE RATE, 16-1/4"ø x 45-1/8" H, 12 PSI OPERATING PRESSURE, 100 PSI AND 240 F MAXIMUM DESIGN PRESSURE & TEMPERATURE.

NOTES:
1. – INSTALL THE EXPANSION TANK IN STRICT ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS, RECOMMENDATIONS AND WARRANTY.
2. – MOUNT THE EXPANSION TANK ON THE NEW 5" THICK CONCRETE PAD AND SEISMICALLY ANCHOR THE EXPANSION TANK TO THIS CONCRETE PAD.

HEATING PUMPS

P6 PUMP, IN-LINE TYPE, EQUAL TO "B&G", MODEL SERIES 60, MODEL #2x2x5-1/4, RATED FOR 90 GPM ● 20 FT HEAD, 67% EFFICIENCY, 4.75" IMPELLER SIZE, 3/4 HP PUMP MOTOR ● 208V/3 PH, LISTED.

NOTES:
1. – INSTALL HEATING PUMP IN STRICT ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS, RECOMMENDATIONS AND WARRANTY.
2. – SEISMICALLY SUPPORT THE HEATING PUMP FROM THE EXISTING BUILDING'S STRUCTURAL ELEMENTS.

VENTS AND BREECHINGS

THE NEW VENTS AND BREECHING SHALL BE EQUAL TO "METAL-FAB, INC.", MODEL IPIC-1 FOR VENTS AND IPIC-2 FOR BREECHING, 1400 F FACTORY BUILT-CHIMNEY, WITH 304SS INNER PIPE MATERIAL AND ALUMINIZED STEEL OUTER PIPE MATERIAL, FURNISHED WITH 1 INCH HIGH TEMPERATURE INSULATION FOR VENTS AND 2 INCHES HIGH TEMPERATURE INSULATION FOR BREECHING, CONFORMING TO NFPA-37 & -211 AND UL-103.

NOTES:
1. – INSTALL VENTS AND BREECHINGS IN STRICT ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS, RECOMMENDATIONS AND WARRANTY.
2. – PROVIDE SEISMIC TYPE SUPPORTS AND ANCHORS TO EXISTING BUILDING STRUCTURAL ELEMENTS.
3. – COVER ALL SUPPORTS AND ANCHORS WITH TWO (2) LAYERS OF PRIMER AND TWO (2) COATS OF WEATHER RESISTANT PAINT.

FLUE TEMPERATURE INDICATORS/CONTROLLERS

FTI1, 2 & 3 FLUE TEMPERATURE INDICATOR, "HEAT-TIMER", MODEL DIGI-SPAN SPC950T, 24 VAC, RATED FOR 220 F TO 950 F RANGE AND 3 TO 70 F DIFFERENTIAL, UL LISTED, FURNISHED WITH HIGH TEMPERATURE STAINLESS STEEL SENSOR, MODEL P/N 804019-00, LOW VOLTAGE TRANSFORMER, AND INTERFACE CABLE, MODEL P/N 908305.

NOTES:
1. – INSTALL FLUE TEMPERATURE INDICATORS IN STRICT ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS, RECOMMENDATIONS AND WARRANTY.
2. – CONNECT THE FLUE TEMPERATURE INDICATORS/CONTROLLERS TO THE BOILERS TO EXISTING EMS. INTERFACE WIRING TO BE MULTI-STRANDED, RIGID CONDUITS WITH LIQUIDTIGHT FITTINGS.
3. – SET SENSORS SETPOINT TO THE MAXIMUM TEMPERATURE RECOMMENDED BY THE BOILERS' MANUFACTURER.

CARBON MONOXIDE DETECTOR

CMD1 CARBON MONOXIDE DETECTOR, EQUAL TO "SYSTEM SENSOR", MODEL CO1224T, 12/24 VDC, 4-WIRE ELECTRO-CHEMICAL SENSING TECHNOLOGY SYSTEM-MONITORED TYPE, FURNISHED WITH FUNCTIONAL REAL TEST USING CANNED CO, CODE-REQUIRED TROUBLE RELAY WIRING SUPERVISION WITH EMS TERMINALS, UL 2034 AND 2075 LISTED AND COMPLIANT WITH CT PUBLIC ACT 11-248.

NOTES:
1. – INSTALL THE CARBON MONOXIDE DETECTOR IN STRICT ACCORDANCE WITH THE 2012 NFPA 720 AND MANUFACTURER'S INSTRUCTIONS, RECOMMENDATIONS AND WARRANTY.
2. – REFER TO THE SEQUENCE OF OPERATION ON DRAWINGS.
3. – REFER TO THE ELECTRICAL DRAWINGS FOR CONNECTIONS TO THE BUILDING'S FIRE ALARM SYSTEM.

BOILERS CONTROL PANEL

BCP1 BOILER CONTROL PANEL, EQUAL TO "HEAT-TIMER", MODEL HWR-Q SEQ-8, FURNISHED WITH REMOTE COMMUNICATION INTERFACE(P/N 900147-00), 120V/1 PH, UL LISTED, FURNISHED WITH IMMERSION WELL TEMPERATURE SENSORS FOR EACH BOILER HWS & R, AND COMMON OUTSIDE AIR TEMPERATURE SENSOR FOR BOILERS SEQUENCING AND HWS TEMPERATURE RESET.

NOTES:
1. – INSTALL BOILER CONTROL PANEL IN STRICT ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS, RECOMMENDATIONS AND WARRANTY. PROVIDE ALL REQUIRED PROGRAMMING FOR A COMPLETE OPERATIONAL SYSTEM.
2. – THE OWNER'S REPRESENTATIVE SHALL PROVIDE A DEDICATED TELEPHONE LINE AT THIS LOCATION.



DOMESTIC WATER SYSTEM PIPING DETAIL
NTS



HEATING BOILERS PIPING DETAIL
NTS

SEQUENCES OF OPERATION

HEATING BOILERS B1 & 2

THE OPERATION OF THE HEATING BOILERS SHALL BE CONTROLLED FROM THE THE BOILERS CONTROL PANEL BCP1, AND MONITORED VIA THE EXISTING EXPANDED ENERGY MANAGEMENT SYSTEM (EMS). EACH BOILER SHALL OPERATE ON ITS OWN OPERATING & SAFETY CONTROLS, AND SHALL ONLY BE ENERGIZED IF OUTSIDE AIR TEMPERATURE IS BELOW 65 F AND IF THERE IS A PRESENT HEATING DEMAND. THE BCP1 SHALL PROVIDE LEAD/LAG CONTROL FOR THESE BOILERS SUCH THAT THEY OPERATE ON EVEN TIME BASIS. ANY TIME ANY BURNER IS ENERGIZED, THE COMBUSTION AIR LOUVERS/DAMPERS L/D1 & 2 SHALL FULLY OPEN AND SHALL FULLY AND CLOSE IF THE RESPECTIVE BURNER IS DE-ENERGIZED. HOWEVER, THE L/D1 & 2 COULD STAY OPEN ONLY IF THE SPACE TEMPERATURE EQUALS OR EXCEEDS 85 F (I.E. ADJUSTABLE), AS CONTROLLED FROM A WALL MOUNTED LOW VOLTAGE HIGH LIMIT THERMOSTAT. THE BOILERS HWS TEMPERATURE SHALL BE RESET AS A FUNCTION OF OUTSIDE AIR TEMPERATURE, FOLLOWING THE FOLLOWING SCHEDULE: AT 10 F OUTSIDE AIR TEMPERATURE THE HWS TEMPERATURE SHALL BE 200 F, AND AT 60 F OUTSIDE AIR TEMPERATURE THE HWS TEMPERATURE SHALL BE 140 F.
IF EITHER THE HWS OR HWR TEMPERATURE FALLS BELOW A PRE-SET VALUE, SUCH AS 125 F, AS INDICATED BY THE WELL MOUNTED WATER TEMPERATURE SENSORS, THE BCP1 COMMUNICATION INTERFACE SHALL BE ENERGIZED AND WILL SEND OUT A WARNING MESSAGE TO A PRE-SET TELEPHONE NUMBER VIA ITS MODEM.
IF ANY BOILER'S FLUE TEMPERATURE, MONITORED BY A TEMPERATURE SENSOR/CONTROLLER EXCEEDS THE PRESET LEVEL, THE BOILER WILL SHUT DOWN AND AN ALARM SHALL BE SENT THE EXISTING EXPANDED EMS.
THE DUAL FUEL SWITCHOVER PANEL (DFSP1) SHALL ENABLE THE SAFELY BURNERS' OPERATION USING EITHER NATURAL GAS OR FUEL OIL#2, USING AUTOMATIC MODE IN RESPONSE TO AN OUTSIDE AIR TEMPERATURE OR MANUAL MODE IN RESPONSE TO THE GAS COMPANY TELEPHONE'S REQUEST.
IF THE CARBON MONOXIDE LEVEL EXCEEDS ITS PRE-SET LEVEL, AN ALARM SHALL SOUND INSIDE THE BOILER ROOM.
PROVIDE THE FOLLOWING INPUT/OUTPUT CONTROL POINTS TO THE EXISTING EXPANDED EMS:
- OUTSIDE AIR TEMPERATURE
- BOILER ROOM TEMPERATURE
- COMBUSTION AIR MOTORIZED DAMPERS POSITION
- BOILERS' BURNERS START/STOP/STATUS
- HEATING PUMPS P1 THRU P6 START/STOP/STATUS
- HWS TEMPERATURE
- HWR TEMPERATURE
- FLUES TEMPERATURE
- NATURAL GAS VIA DFSP1
- FUEL OIL #2 VIA DFSP1
- CARBON MONOXIDE ALARM

DOMESTIC WATER BOILER B3

THE OPERATION OF THE DOMESTIC HOT WATER BOILER SHALL BE CONTROLLED FROM THE THE BOILERS CONTROL PANEL BCP1, AND MONITORED VIA THE EXISTING EXPANDED ENERGY MANAGEMENT SYSTEM (EMS).
THIS BOILER SHALL OPERATE ON ITS OWN OPERATING & SAFETY CONTROLS, BASED UPON THE DOMESTIC HOT HOT WATER DEMAND.ANY TIME THIS BOILER IS ENERGIZED, THE COMBUSTION AIR LOUVERS/DAMPERS L/D1 & 2 SHALL FULLY OPEN AND CLOSE IF THE BURNER IS DE-ENERGIZED. HOWEVER, THE L/D1 & 2 COULD STAY OPEN ONLY IF THE SPACE TEMPERATURE EQUALS OR EXCEEDS 85 F (I.E. ADJUSTABLE), AS CONTROLLED FROM A WALL MOUNTED LOW VOLTAGE HIGH LIMIT THERMOSTAT.
DURING THE OCCUPIED HOURS THE PRESENT IN-LINE PUMPS P7 & 8 SHALL CYCLE AS REQUIRED TO MEET THE DOMESTIC HOT WATER DEMAND. DURING THE UNOCCUPIED HOURS THE PUMPS P7 & 8 SHALL BE OFF, AS SCHEDULED FROM THE EXISTING EXPANDED EMS.
IF EITHER THE HWS OR HWR TEMPERATURE FALLS BELOW A PRE-SET VALUE, SUCH AS 125 F, AS INDICATED BY THE WELL MOUNTED WATER TEMPERATURE SENSORS, THE BCP1 COMMUNICATION INTERFACE SHALL BE ENERGIZED AND WILL SEND OUT A WARNING MESSAGE TO A PRE-SET TELEPHONE NUMBER VIA ITS MODEM.
IF THE BOILER'S FLUE TEMPERATURE, MONITORED BY A TEMPERATURE SENSOR/CONTROLLER EXCEEDS THE PRESET LEVEL, THE BOILER WILL SHUT DOWN AND AN ALARM SHALL BE SENT THE EXISTING EXPANDED EMS.
THE DUAL FUEL SWITCHOVER PANEL (DFSP1) SHALL ENABLE THE SAFELY BURNERS' OPERATION USING EITHER NATURAL GAS OR FUEL OIL#2, USING AUTOMATIC MODE IN RESPONSE TO AN OUTSIDE AIR TEMPERATURE OR MANUAL MODE IN RESPONSE TO THE GAS COMPANY TELEPHONE'S REQUEST.
IF THE CARBON MONOXIDE LEVEL EXCEEDS ITS PRE-SET LEVEL, AN ALARM SHALL SOUND INSIDE THE BOILER ROOM.
PROVIDE THE FOLLOWING INPUT/OUTPUT CONTROL POINTS TO THE EXISTING EXPANDED EMS:
- OUTSIDE AIR TEMPERATURE
- BOILER ROOM TEMPERATURE
- COMBUSTION AIR MOTORIZED DAMPERS POSITION
- BOILER'S BURNER START/STOP/STATUS
- RECIRCULATING PUMP P6 START/STOP/STATUS
- HWS TEMPERATURE
- HWR TEMPERATURE
- CW TEMPERATURE
- HW TEMPERATURE
- FLUE TEMPERATURE
- NATURAL GAS VIA DFSP1
- FUEL OIL #2 VIA DFSP1
- CARBON MONOXIDE ALARM

CARBON MONOXIDE DETECTOR

THE DETECTOR SHALL PROVIDE DUAL-COLOR LED INDICATOR THAT BLINKS TO INDICATE NORMAL STANDBY, ALARM OR END-OF-LIFE.

SAFE TEST FUNCTIONAL TEST: THIS TEST FACILITATES THE USE OF CO TEST SPRAY TO VERIFY THE CORRECT OPERATION OF THE DETECTOR, WHICH IS MANDATORY PER NFPA 720. THE SAFE TEST MODE IS ACTIVATED BY PRESSING AND HOLDING THE TEST/HUSH BUTTON FOR 5-10 SECONDS. WHILE IN SAFE TEST MODE DIRECTING UL-CLASSIFIED CO TESTING SPRAY AT THE SENSOR PORT WILL RESULT IN THE ACTIVATION OF THE ALARM RELAY, AND THE SOUNDER AND RED LED IN A TEMPORAL-FOUR PATTERN. PRESSING AND HOLDING THE TEST/HUSH BUTTON WILL EXIT THE SAFE TEST MODE.

DISTINCT TEMPORAL-FOUR SOUNDER ALARMS: THE 85dB TEMPORAL-FOUR SOUNDER PROVIDES A DISTINCTIVE ALARM NOTIFICATION THAT IS EASY TO DIFFERENTIATE FROM SMOKE ALARM NOTIFICATION DEVICES. THE ALARM BEEPS FOUR TIMES, RESTS FIVE SECONDS AND THEN REPEAT THE PATTERN.

TEST/HUSH BUTTON: USE THE TEST/HUSH BUTTON TO TEST THE ALARM AND SILENCE AN ACTIVATED ALARM. PUSHING PUSHING THE TEST/HUSH BUTTON SILENCES THE INTEGRATED SOUNDER FOR FIVE MINUTES. THE RED ALARM LIGHT STAYS ON AND IF CO IS STILL PRESENT AFTER FIVE MINUTES, THE DETECTOR ONCE AGAIN SOUNDS IN THE TEMPORAL-FOUR PATTERN.

END OF SENSOR LIFE INDICATOR: THE DETECTOR USES BOTH A FLASHING GREEN LED AND INTERMITTENT SOUNDER CHIRPS TO INDICATE THE DETECTOR NEEDS REPLACING. TO SILENCE THE DETECTOR, PUSH THE TEST/HUSH BUTTON. THE DETECTOR ALSO BEGINS SIGNALING A TROUBLE WHEN THE CO SENSOR IS APPROACHING END-OF-LIFE.

COMMON TROUBLE RELAY: THE TROUBLE RELAY OPENS TO INDICATE A TROUBLE CONDITION UPON LOST POWER, CO SENSOR CELL TROUBLE, OR CELL END-OF-LIFE. WHEN CONNECTED TO THE FIRE ALARM CONTROL PANEL, THE TROUBLE RELAY WILL REPORT A TROUBLE CONDITION LOCALLY AT THE FIRE ALARM CONTROL PANEL.

SCOPE OF WORK

1. – ALL POTENTIAL CONTRACTORS SHALL BECOME FAMILIAR WITH THE EXISTING CONDITIONS, PRIOR TO START ANY WORK.
2. – ALL WORK SHALL BE PERFORMED IN STRICT ACCORDANCE WITH THE 2005 CONNECTICUT STATE BUILDING AND FIRE SAFETY CODES, 2003 INTERNATIONAL MECHANICAL CODE, 2003 INTERNATIONAL PLUMBING CODE, 2003 ICC/ANSI A117.1 ACCESSIBLE AND USABLE BUILDINGS AND FACILITIES, 2009 INTERNATIONAL ENERGY CONSERVATION CODE, 2009 & 2011 CONNECTICUT AMENDMENTS TO THE STATE BUILDING AND FIRE SAFETY CODES, OTHER APPLICABLE CODES, STANDARDS, REGULATIONS, ORDINANCES, ETC., AND THE REQUIREMENTS OF THE LOCAL AUTHORITIES AND UTILITIES COMPANIES HAVING JURISDICTION. THIS CONTRACTOR SHALL BE A LICENSED MECHANICAL CONTRACTOR AND SHALL BE RESPONSIBLE TO OBTAIN A CONSTRUCTION PERMIT AND PAY FOR ALL APPLICABLE FEES, TAXES, TESTS, ETC. NO WORK SHALL BE PERFORMED UNTIL SHOP DRAWINGS FOR ALL EQUIPMENT, DEVICES AND MAJOR MATERIALS, ARE SUBMITTED AND APPROVED IN WIRING BY THE PROJECT ENGINEER.
3. – PROVIDE DEMOLITION WORK TO THE EXTENT INDICATED AND REQUIRED. ALL ITEMS REQUIRED TO REMOVED SHALL BE DISPOSED OF IN A LEGAL MANNER OR TURNED OVER TO THE OWNER'S REPRESENTATIVE AS INDICATED ON DRAWINGS. REFER TO WORK PHASING NOTE ON DRAWINGS FOR THE SCHEDULE OF WORK WHICH WILL IMPACT THE DEMOLITION WORK AND SEQUENCE. DISCONNECT AND ISOLATE THE EXISTING BOILERS B1 & B2. DISASSEMBLE THESE BOILERS SECTIONS AND SAFELY REMOVE THEM THROUGH THE EXISTING LOUVER L/D1 OPENINGS. REMOVE THESE LOUVERS AND DISPOSE OF IN A LEGAL MANNER. CUT EXISTING IWH1 IN PIECES AS NEEDED TO SAFELY REMOVE THROUGH THE EXISTING OPENING. DISCONNECT AND ISOLATE THE BOILER AT B1 & 2 AND TURN THEM OVER TO THE OWNER'S REPRESENTATIVE. REMOVE EXISTING BOILERS' VENTS AND BREECHINGS AND DISPOSE THEM IN A LEGAL MANNER. REMOVE THE EXISTING PIPING, FITTINGS, VALVES, SUPPORTS, ETC., TO THE EXTENT SHOWN AND REQUIRED AND DISPOSE OF IN A LEGAL MANNER. HIRE THE SERVICES OF AN INDEPENDENT CERTIFIED CHIMNEY SWEEPER TO THOROUGHLY INSPECT AND VACUUM CLEAN EXISTING CHIMNEY'S FLUES. PROVIDE THREE (3) COPIES OF THIS CHIMNEY REPORT TO THE PROJECT ENGINEER, PRIOR TO THE COMPLETION OF THE DEMOLITION WORK. PROVIDE A DETAILED DEMOLITION SCHEDULE FOR THE REVIEW AND APPROVAL BY THE PROJECT ENGINEER, PRIOR TO STARTING THIS DEMOLITION WORK.
4. – FURNISH & INSTALL, TEST AND ADJUST ALL EQUIPMENT, DEVICES, MATERIALS, ETC., AND PROVIDE ALL NECESSARY LABOR, RIGGINGS, ETC. AS INDICATED, SHOWN OR SPECIFIED FOR COMPLETE OPERATIONAL SYSTEMS, APPROVED IN WRITING BY THE ARCHITECT/ENGINEER & OWNER'S REPRESENTATIVE, AND LOCAL AUTHORITIES HAVING JURISDICTION.
5. – ALL MECHANICAL EQUIPMENT SHALL BE INSTALLED IN STRICT ACCORDANCE WITH THE MANUFACTURERS' INSTRUCTIONS, RECOMMENDATIONS AND WARRANTY, WITH ALL REQUIRED CLEARANCES FOR MAINTENANCE AND SERVICE.
6. – ALL PIPING AND PENETRATIONS (SUCH AS GAS VENTS) SHALL BE PERFORMED IN APPROVED PITCH POCKETS IN STRICT ACCORDANCE WITH THE ROOF MANUFACTURER'S INSTRUCTIONS, RECOMMENDATIONS AND WARRANTY.
7. – NOT USED.
8. – FOR SEISMIC RESTRAINTS SEE SPECIFICATIONS.
9. – ALL NEW BOILERS SHALL BE DELIVERED TO SITE KNOCKDOWN, SHALL BE FULLY ASSEMBLED AT SITE, AND PRESSURE TESTED, AS INDICATED IN SECTION 23 50 11.
10. – THE NATURAL GAS PIPING ABOVE GRADE SHALL BE STEEL, ASTM A53 OR A120, SCHEDULE 40, BLACK, WITH MALLEABLE/DUCTILE IRON FITTINGS ASME B16.3 (UP TO AND INCLUDING 2") AND FORGED STEEL ASTM A234 (ABOVE 2") WITH THREADED JOINTS (UP TO AND INCLUDING 2") AND WELDED JOINTS (ABOVE 2"), ANSI B31.1, B31.2 & B31.9. FLANGES, UNIONS AND COUPLING 2" AND UNDER SHALL BE FERROUS PIPE, MALLEABLE IRON WITH THREADED UNIONS, RATED FOR 150 PSI. ON PIPING OVER 2" USE FORGED STEEL SLIP ON FLANGES, 1/16" THICK PRE-FORMED NEOPRENE GASKETS. PLUG VALVES UP TO AND INCLUDING 2" SHALL BE BRONZE BODY, BRONZE TAPERED PLUG, NON-LUBRICATING, TEFLON PACKING, THREADED ENDS. OVER 2" USE CAST IRON BODY AND PLUG, NON-LUBRICATED, TEFLON PACKING, FLANGED ENDS. USE DIELECTRIC UNIONS WHEN DISSIMILAR MATERIALS ARE JOINED TOGETHER. ALL SUPPORTS AND ANCHORS SHALL BE CONFORMING WITH ASME B31.9, AND MSS SP58, 69 & 89. COORDINATE THE LOCATION OF THE GAS METER WITH THE GAS COMPANY. PROVIDE A MAIN GAS SHUTOFF VALVE ON GAS PIPING RISER AT METER; COVER ALL GAS PIPING WITH (1) LAYER OF PRIMER AND (2) COATS OF YELLOW WEATHER RESISTANT GLOSS TYPE PAINT AND IDENTIFY GAS PIPING WITH ANSI APPROVED TYPE PLASTIC MARKERS.
11. – THE FUEL OIL PIPING ABOVE GRADE SHALL BE COPPER TUBING ASTM B88, TYPE K HARD DRAWN, WITH CAST BRONZE FITTINGS ASME 16.18, AND BRONZE BODY, BRONZE TRIM, SOLDERED JOINTS NFPA-30, OR STEEL PIPE ASTM A53, SCHEDULE 40, WITH ASTM B16.3 MALLEABLE IRON FITTINGS ASTM B16.3 AND NFPA-30 THREADED JOINTS.
12. – THE HEATING PIPING ABOVE GRADE SHALL BE STEEL, ASTM A53, SCHEDULE 40, BLACK, WITH MALLEABLE IRON FITTINGS ASME B16.3 (UP TO AND INCLUDING 2") AND FORGED STEEL ASTM A234 (ABOVE 2") WITH THREADED JOINTS (UP TO AND INCLUDING 2") AND WELDED JOINTS (ABOVE 2") ANSI B31.1, B31.2 & B31.9. OR MECHANICAL JOINTS. FLANGES, UNIONS AND COUPLING 2" AND UNDER SHALL BE FERROUS PIPE, MALLEABLE IRON WITH THREADED UNIONS, RATED FOR 150 PSI. ON PIPING OVER 2" USE FORGED STEEL SLIP ON FLANGES, 1/16" THICK PRE-FORMED NEOPRENE GASKETS. EQUIPMENT DRAINS AND OVERFLOWS SHALL BE STEEL PIPE ASTM A53, SCHEDULE 40, GALVANIZED WITH GALVANIZED CAST IRON FITTINGS OR MALLEABLE IRON FITTINGS ASTM B16.3, AND THREADED OR GROOVED MECHANICAL JOINTS. THE COLD WATER PIPING ABOVE GRADE SHALL BE COPPER TUBING, ASTM B88, TYPE K HARD DRAWN, WITH ASME B16.18, CAST BRASS OR ASME B16.22 SOLDER WROUGHT COPPER FITTINGS, AND 95/5 SOLDER (ASTM B32) LEAD FREE JOINTS. GATE VALVES UP TO AND INCLUDING 2" SHALL BE BRONZE BODY, BRONZE TRIM, UNION BONNET, NON-RISING STEM, INSIDE SCREW, SOLID WEDGE DISC, SOLDER OR THREADED EDS. ABOVE 2" USE GATE VALVES WITH IRON BODY, BRONZE TRIM, BOLTED BONNET, NON-RISING STEM, HANDWHEEL, OUTSIDE SCREW AND YOKE, SOLID WEDGE DISK WITH BRONZE SEAT RINGS, AND FLANGED OR GROOVED ENDS. BALL VALVES UP TO AND INCLUDING 2" SHALL BE BRONZE TWO PIECE BODY, STAINLESS STEEL BALL, TEFLON SEATS AND STUFFING BOX RING, LEVER HANDLE,, FLANGED. USE DIELECTRIC FITTINGS WHEN DISSIMILAR MATERIALS ARE JOINED TOGETHER. ALL SUPPORTS AND ANCHORS SHALL BE CONFORMING WITH ASME B31.9, AND MSS SP58, 69 & 89.
13. – COVER THE COLD AND HEATING HOT WATER UP TO AND INCLUDING 1" WITH FIBERGLASS RIGID MOLDED INSULATION, ASTM C547, WITH "K" VALUE OF .24 @ 75 F, FURNISHED WITH VAPOR BARRIER JACKET AND FINISHED WITH PVC JACKETS. COVER THE HEATING HOT WATER OVER 1" AND UP AND INCLUDING 4", WITH 1-1/2" THICK FIBERGLASS RIGID MOLDED INSULATION, ASTM C547 WITH "K" VALUE OF .24 @ 75 F, FURNISHED WITH VAPOR BARRIER JACKETS AND FINISHED WITH PVC JACKETS. COVER THE HEATING HOT WATER OVER 4" WITH 2" THICK INSULATION IN THE SAME MANNER. COVER THE EXISTING AND NEW AIR SEPARATORS WITH 1-1/2" THICK PRE-MOLDED AND FIBERGLASS INSULATION, FURNISHED WITH VAPOR BARRIER JACKET AND FINISHED WITH PVC JACKETS.
14. – FURNISH AND INSTALL INSTRUMENTATION AS INDICATED ON DRAWINGS AND REQUIRED. PRESSURE GAUGES SHALL BE AT LEAST 4-1/2" IN DIAMETER DRAWN STEEL CASE, PHOSPHOR BRONZE BOURDON TUBE, ROTARY BRASS MOVEMENT BRASS SOCKET WITH FRONT RECALIBRATION ADJUSTMENT, BLACK SCALE ON WHITE BACKGROUND, ON PERCENT MID-SCALE ACCURACY, ASME B40.1 & UL 393. STEM TYPE THERMOMETERS SHALL BE AT LEAST 7" SCALE, RED APPEARING MERCURY, LENS FRONT TUBE, CAST ALUMINUM CASE WITH ENAMEL FINISH AND POLYCARBONATE WINDOW, WITH 2 PERCENT ACCURACY, ASTM E1 AND ASTM B77.
15. – FURNISH AND INSTALL ELECTRIC/ELECTRONIC CONTROLS, SUCH AS CONTROL PANELS, SENSORS, MOTORIZED DAMPERS, CONTROL VALVES, ETC. WIRING/CONDUITS, AND PROVIDE ANN NECESSARY INCLUDING DEMONSTRATION AND TRAIN

GENERAL REQUIREMENTS

GENERAL

AFTER CAREFULLY STUDYING THE DRAWINGS AND SPECIFICATIONS, AND BEFORE SUBMITTING THE PROPOSAL, EACH BIDDER SHALL VISIT THE SITE TO ASCERTAIN CONDITIONS OF THE SITE, AND THE NATURE AND EXACT QUANTITY OF WORK TO BE PERFORMED. NO EXTRA WILL BE ALLOWED IF THE CONTRACTOR FAILS TO NOTIFY THE ENGINEER/OWNER IN WRITING OF ANY DISCREPANCIES THAT HE MAY HAVE NOTED BETWEEN THE EXISTING CONDITIONS AND DRAWINGS AND SPECIFICATIONS.

THE CONTRACTOR SHALL VERIFY ALL MEASUREMENTS OF HIS OWN OR OTHERS AT THE SITE, AND SHALL BE RESPONSIBLE FOR CORRECTNESS OF SAME AS RELATED TO HIS WORK.

THE CONTRACTOR SHALL BE TOTALLY RESPONSIBLE FOR COORDINATION OF ANY RELATED ITEMS REGARDING UTILITIES COMPANIES AND INCLUDE THEM TO HIS COST.

CODES, REGULATIONS AND STANDARDS

ALL WORK SHALL COMPLY WITH THE REQUIREMENTS OF THE FOLLOWING CODES:

A. 2005 NATIONAL ELECTRIC CODE, NFPA 70 (NEC)
B. INTERNATIONAL BUILDING CODE 2003 (ICC)
C. INTERNATIONAL MECHANICAL CODE 2003 (ICC)
D. INTERNATIONAL PLUMBING CODE 2003 (ICC)
E. 2011 CONNECTICUT STATE AMENDMENTS / 2005 STATE BUILDING CODE
F. 2005 CONNECTICUT STATE FIRE SAFETY CODE (CSFC)
G. LOCAL AUTHORITIES HAVING JURISDICTION (AHJ)
H. ICC/ANSI A 117.1/2003 ACCESSIBLE AND USABLE BUILDINGS AND FACILITIES
I. O.S.H.A. REGULATIONS
J. AMERICANS WITH DISABILITIES ACT, ADA REQUIREMENTS (FEDERAL LAW)
K. INTERNATIONAL EXISTING BUILDING CODE/2003 (ICC)
L. INTERNATIONAL ENERGY CONSERVATION CODE 2009 (ICC) (2011 CT AMENDMENTS ADOPT 2009 EDITION)
M. 2009 & 2011 CONNECTICUT AMENDMENTS/STATE BUILDING CODE

GENERAL CONSTRUCTION NOTES

1. THIS IS AN EXISTING OPERATING FACILITY AND WILL CONTINUE TO OPERATE DURING THE CONSTRUCTION PERIOD. ALL WORK MUST BE COORDINATED WITH THE G.C. AND THE OWNER'S PERSONNEL. SCHEDULING AND CONTAINMENT OF WORK AREAS SHALL BE DONE IN CONJUNCTION WITH THE FACILITY OPERATING PERSONNEL.
2. ALL POWER OUTAGES MUST BE SCHEDULED WITH THE MANAGEMENT PERSONNEL A MINIMUM OF 36 HOURS IN ADVANCE OF THE OUTAGE. THE ELECTRICAL CONTRACTOR MUST PLAN FOR TOOLS, MATERIALS, MANPOWER, ETC. TO MAKE THE MOST EFFICIENT USE OF AND TO MINIMIZE THE FACILITY OUTAGE. PREMIUM TIME COSTS TO BE INCLUDED IN CONTRACTOR'S BID, NO ADDITIONAL ALLOWANCE WILL BE MADE FOR PREMIUM TIME.
3. PERSONNEL SAFETY IS OF PRIME IMPORTANCE. NO HAZARDOUS CONDITIONS SHALL BE ALLOWED. EVERY CARE MUST BE TAKEN TO PROTECT CONSTRUCTION AND OTHER PERSONNEL. CLEANUP SHALL BE DONE ON A DAILY BASIS.
4. THE ELECTRICAL CONTRACTOR SHALL INSTALL ALL EQUIPMENT IN ACCORDANCE WITH MANUFACTURERS INSTRUCTION AND OR REQUIREMENTS FOR PROPER OPERATION AND MAINTENANCE.
5. THE TERM "PROVIDE" SHALL MEAN TO FURNISH AND INSTALL IN COMPLETE WORKING ORDER.
6. ALL THE WIRE SIZES ARE BASED ON COPPER THHN 75°C, ALUMINUM SHALL NOT BE USED.
7. AT NO TIME SHALL THIS BUILDING BE WITHOUT POWER, FIRE ALARM, LIFE SAFETY SYSTEMS, ETC. WHEN IT IS NECESSARY TO DISCONNECT ANY EXISTING ITEM BEFORE THE NEW DEVICE OR SYSTEM IS ACTIVE, THEN THE ELECTRICAL CONTRACTOR SHALL PROVIDE THE REQUIRED SAFETY AND GIVE WRITTEN NOTICE 48 HOURS IN ADVANCE TO THE ARCHITECT/ENGINEER/OWNER.
8. THIS JOB IS COMPOSED OF ALTERATIONS IN AN EXISTING BUILDING. BEFORE SUBMITTING THE BID, THE ELECTRICAL CONTRACTOR SHALL VISIT THE SITE AND BECOME THOROUGHLY FAMILIAR WITH ALL EXISTING CONDITIONS UNDER WHICH THE WORK AND WORK OF OTHER TRADES WILL BE INSTALLED. THIS CONTRACT INCLUDES ALL NECESSARY OFFSETS, TRANSITIONS, MODIFICATIONS AND RELOCATION OF EXISTING EQUIPMENT FOR INSTALLATION OF NEW ELECTRICAL EQUIPMENT AND NEW EQUIPMENT OF OTHER TRADES. LIGHTING FIXTURES, DEVICES, CONDUIT, WIRING, ETC.). ALL NEW AND EXISTING EQUIPMENT AND SYSTEMS SHALL BE FULLY OPERATIONAL UNDER THIS CONTRACT BEFORE THE JOB IS CONSIDERED COMPLETE. THE ELECTRICAL CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY ASSUMPTIONS MADE, ANY OMISSIONS OR ERRORS MADE AS A RESULT OF THE ELECTRICAL CONTRACTOR'S FAILURE WITH HIS INSPECTION OF EXISTING CONDITIONS AND REVIEW OF ALL OTHER TRADE DOCUMENTS.
9. LOCATIONS OF EXISTING ELECTRICAL EQUIPMENT AND WIRING METHODS HAVE BEEN TAKEN FROM ON SITE SURVEYS. DUE TO OBSTRUCTIONS ALONG WALLS NOT EVERY DEVICE LOCATION MAY HAVE BEEN ACCURATELY DETERMINED. THE CONTRACTOR SHALL FIELD VERIFY EXACT LOCATIONS OF ALL EXISTING ELECTRICAL EQUIPMENT THAT WILL REQUIRE MODIFICATION DUE TO THE RENOVATION WORK PRIOR TO PRICING AND COMMENCEMENT OF WORK.
10. ALL LIGHTING CIRCUITS SHALL BE TERMINATED IN THE CEILING IN JUNCTION BOXES OR PULLED BACK TO THE PANEL WHERE THE CIRCUIT ORIGINATES. ALL OTHER AREAS TO REMAIN "AS IS" AND ALL ELECTRICAL APPURTENANCES, DEVICES AND ACCESSORIES SHALL REMAIN OPERATIONAL.
11. THE CONTRACTOR SHALL VERIFY THAT ANY EXISTING CIRCUIT WIRING TO BE REMOVED DOES NOT DISRUPT SERVICE TO EXISTING ELECTRICAL APPURTENANCES AND DEVICES TO REMAIN. THE CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY DEVICES, EQUIPMENT AND ACCESSORIES REQUIRED TO MAINTAIN SERVICE TO ALL EXISTING ELECTRICAL DEVICES AND EQUIPMENT.
12. THE CONTRACTOR SHALL REMOVE ALL CONDUIT AND WIRING ASSOCIATED WITH DEVICES AND EQUIPMENT TO BE REMOVED BACK TO THE SOURCE OF POWER, UNLESS OTHERWISE NOTED.
13. THE CONTRACTOR SHALL PROVIDE AND INSTALL PANELBOARD LEGENDS DEPICTING REMOVED/ADDED CIRCUITS FOR ALL RENOVATION WORK IN PANELBOARDS IN THE SCOPE OF WORK AREAS.
14. ALL EMPTY CONDUIT SYSTEMS SHALL CONTAIN A PULL WIRE FOR FUTURE PULLING OF CONDUCTORS.
15. EXISTING INSTALLED CONDUIT (NOT WIRE) FOUND TO BE REUSABLE MAY BE USED. ALL OTHER MATERIAL SHALL BE REMOVED FROM THE JOB SITE UNLESS OTHERWISE NOTED.
16. ALL EXISTING WIRING NOT BEING REUSED SHALL BE REMOVED.
17. NO WIRING SHALL BE REUSED WITHOUT ENGINEERS APPROVAL.
18. ANY AND ALL ELECTRICAL CONDUIT STUB-UPS SHALL BE CUT TO FLOOR LEVEL.
19. WHERE WIRES ARE BEING REMOVED FROM A CONDUIT, CONTRACTOR SHALL PROVIDE AND INSTALL A DRAG LINE IN THE CONDUIT. TAG.
20. ALL EXISTING CONDUITS TO REMAIN SHALL BE TAGGED WITH SEATON TAGS OR EQUAL AS NECESSARY.
21. CONTRACTOR SHALL INSTALL TEMPORARY LIGHTING IN SCOPE AREAS AS NECESSARY.
22. DEMOLITION AND REMOVALS ARE A PART OF THE SCOPE OF WORK. ALL UNUSED ELECTRICAL ITEMS SHALL BE REMOVED AS MUCH AS POSSIBLE. THE ELECTRICAL PLANS DO NOT SHOW ALL OF THE ELECTRICAL REMOVAL WORK. CONTRACTOR SHALL REVIEW ALL TRADE DRAWINGS ARCHITECTURAL, PLUMBING, AND MECHANICAL FOR ANY ADDITIONAL ELECTRICAL ITEMS TO BE REMOVED.
23. ASBESTOS OR UNKNOWN MATERIAL ENCOUNTERED DURING THE CONSTRUCTION SUSPECTED TO BE ASBESTOS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT/ENGINEER FOR RESOLUTION. STOP ALL WORK IN VICINITY OF SUSPECTED MATERIALS IMMEDIATELY IN THIS EVENT.
24. THE CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS WITHIN THE DEMOLITION WORK DEPICTED ON THE DRAWING AND SHALL ASCERTAIN THE EXTENT OF WORK REQUIRED WITHIN THE DEMOLITION AREA PRIOR TO PRICING AND COMMENCEMENT OF WORK.
25. THE CONTRACTOR SHALL ENSURE THAT ALL CIRCUITS REQUIRED TO BE REMOVED OR RELOCATED, ARE DE-ENERGIZED AND REMAIN DE-ENERGIZED FOR THE DURATION OF THE DEMOLITION ACTIVITY. THE CONTRACTOR SHALL FIELD VERIFY THE CIRCUITS AND IDENTIFY ANY ADDITIONAL CIRCUITS THAT MAY INTERFERE WITH DEMOLITION BOUNDARY, SUCH THAT PERSONAL SAFETY IS ENSURED, AND EQUIPMENT REQUIRED TO REMAIN OPERABLE IS MAINTAINED.
26. ALL DEMOLITION ACTIVITIES MUST BE COORDINATED WITH THE ARCHITECT/ ENGINEER AND GENERAL CONTRACTOR TO MINIMIZE INTERRUPTION OF REQUIRED SERVICES OR TO ALLOW FOR COMPENSATORY MEASURES TO BE TAKEN.

GENERAL NOTES

NOTE: CONTRACTOR SHALL MEAN ELECTRICAL CONTRACTOR

1. ALL DIMENSIONS AND EXACT EQUIPMENT LOCATIONS ARE TO BE VERIFIED WITH MECHANICAL AND ELECTRICAL DRAWINGS AND CONDITIONS IN THE FIELD.
2. THE CONTRACTOR SHALL COORDINATE WITH OTHER TRADES AND CONSULT WITH MECHANICAL DRAWINGS FOR POWER REQUIREMENTS OF THOSE TRADES. ALL EXISTING PANELBOARDS SHALL BE PROVIDED WITH A TYPED SCHEDULE.
3. A COPY OF ALL SCHEDULES SHALL BE SUBMITTED TO THE ENGINEER.
4. THE WORK SHALL BE COORDINATED WITH ALL OTHER TRADES AND PROVIDE OTHERS WITH NECESSARY INFORMATION TO COMPLETE THIS INSTALLATION. DRAWINGS ARE TO BE USED IN CONJUNCTION WITH SPECIFICATIONS ISSUED FOR THIS INSTALLATION.
5. ANY WORK INSTALLED CONTRARY TO, OR WITHOUT APPROVAL BY THE ENGINEER SHALL BE SUBJECT TO CHANGE AS DIRECTED BY THE ENGINEER AND NO EXTRA COMPENSATION WILL BE ALLOWED THE CONTRACTOR FOR MAKING THESE CHANGES.
6. CONDUIT & CABLE RUNS ARE SHOWN DIAGRAMMATICALLY ONLY AND SHALL BE INSTALLED IN A MANNER TO PREVENT CONFLICTS WITH EQUIPMENT AND STRUCTURAL CONDITIONS.
7. THE WIRING DIAGRAMS, QUANTITY AND SIZE OF WIRES AND CONDUIT REPRESENTS A SUGGESTED ARRANGEMENT BASED UPON SELECTED STANDARD COMPONENTS OF ELECTRICAL EQUIPMENT. MODIFICATIONS APPROVED BY THE ENGINEER MAY BE MADE BY THE CONTRACTOR TO ACCOMMODATE EQUIPMENT ACTUALLY PURCHASED. THE BASIC SEQUENCE AND METHOD OF CONTROL SHALL BE MAINTAINED AS INDICATED ON THE DRAWINGS.
8. THE ELECTRICAL CONTRACTOR SHALL PROVIDE ACCESS TO ANY CONCEALED EQUIPMENT. LABEL ALL CONCEALED JUNCTION BOXES.
9. THE CONTRACTOR SHALL SEAL ALL PENETRATIONS THROUGH FIRE RATED WALLS AS INDICATED ON DRAWING TH-EG101 WITH A UL LISTED FIRE STOP TO MAINTAIN THE INTEGRITY OF THE FIRE RATING.
10. VERIFY THAT LIGHTING FIXTURES AND ARRANGEMENTS ARE TO BE COMPATIBLE WITH TYPE OF CEILING WHICH FIXTURE IS TO BE MOUNTED.
11. ALL EXISTING WIRING THAT IS NOT IN USE SHALL BE REMOVED. SURFACE MOUNTED PANEL BOARD AND OTHER SUCH EQUIPMENT SHALL BE MOUNTED WITH A 1/4" AIR SPACE BETWEEN THE ENCLOSURE AND WALL. THE DISTANCE FROM TOP CIRCUIT BREAKER HANDLE TO FLOOR SHALL NOT EXCEED 6'-6" AFF. UNLESS NOTED OTHERWISE. A 1/2" UNISTRUT MAY BE USED.
12. CONTROL STATIONS SHALL HAVE PLASTIC ENGRAVED NAMEPLATES DENOTING EQUIPMENT CONTROLLED. (USE WHITE LETTERS ON BLACK BACKGROUND)
13. ALL PULLBOXES, JUNCTION BOXES, AND SWITCH BOXES INSIDE AREA SHALL BE NEMA 1.
14. ALL JUNCTION BOXES INDICATED AND/OR REQUIRED SHALL BE SIZED TO ACCOMMODATE INCOMING AND OUTGOING FEEDERS.
15. MC CABLE SHALL BE USED IN FURRED OUT WALLS AND HUNG CEILING AREA'S FOR LIGHTING AND GENERAL RECEPTACLES.
16. SWITCHES SHALL BE MOUNTED 4'-0" AND RECEPTACLES 1'-6" ABOVE FINISHED FLOOR UNLESS NOTED OTHERWISE.
17. ALL BRANCH CIRCUIT WIRES & ALL FEEDERS SHALL BE PERMANENTLY TAGGED AT THE PANEL CONNECTIONS WITH "BRADY" MARKERS.
18. ELECTRICAL CONTRACTOR SHALL REVISE ALL EXISTING CIRCUITING & CONDUIT AS NOTED. CONTRACTOR SHALL VERIFY CONDITION OF EXISTING WIRING TO BE REUSED & REPLACE AS REQUIRED.
19. IN ALL AREAS WHERE EXISTING ELECTRICAL WORK IS TO REMAIN, RESTORE ALL CIRCUITS INTERRUPTED BY NEW WORK.
20. MAINTAIN AND RESTORE, IF INTERRUPTED, ALL CONDUITS AND FEEDERS PASSING THROUGH RENOVATED AREAS AND SERVICING UNDISTURBED AREAS.
21. PARTIAL BRANCH CIRCUIT WIRING DENOTING EXISTING CONTROL OR SWITCHING ON THE DRAWINGS IS SHOWN FOR REFERENCE/CLARIFICATION ONLY, AND IS NOT TO BE CONSTRUED TO IMPLY COMPLETE CIRCUIT WIRING. THE LOCATION OF THE INTERCONNECTION OF CONTROL DEVICE, AND EQUIPMENT CONTROLLED IS DIAGRAMMATIC ONLY.
22. THE ELECTRICAL CONTRACTOR SHALL SEISMICALLY BRACE ALL ELECTRICAL ITEMS AS REQUIRED BY STATE OF CT. BUILDING CODE. PROVIDE ALL SEISMIC ANCHORS AND SUPPORTS. PROVIDE DETAILS ACCEPTABLE TO REVIEW AGENCIES FOR SUPPORTS AND ANCHORS OF ACTUAL EQUIPMENT SUPPLIED. REFER TO "GUIDELINES AND DETAILS FOR SEISMIC RESTRAINTS".
23. EACH CIRCUIT SHALL HAVE ITS OWN NEUTRAL. NEUTRALS ARE NOT ALLOWED TO BE SHARED, ESPECIALLY ON LIGHTING CIRCUITS.
24. ALL EMERGENCY LIGHTS SHALL OPERATE FOR A MINIMUM OF 90 MINUTES AND SHALL BE TESTED AS PER NFPA 72 STANDARDS.
25. ALL RECEPTACLES LOCATED WITHIN SIX FEET OF ANY SINK, TOILET OR ANY WATER SOURCE, INCLUDING EXTERIOR RECEPTACLES SHALL BE GFCI TYPE.
26. PROVIDE JUNCTION BOX AND RUN 1" CONDUIT TO ABOVE CEILING FOR EACH TIME CLOCK AND THERMOSTAT LOCATIONS AS SHOWN ON MECHANICAL PLANS.

ELECTRICAL ABBREVATIONS

SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
A	AMPS	JB	JUNCTION BOX
AC	ABOVE COUNTER	KCMIL	THOUSAND CIRCULAR MILLS
AFF	ABOVE FINISHED FLOOR	KVA	KILOVOLT-AMPERE
AFG	ABOVE FINISHED GRADE	KW	KILOWATT
AL	ALUMINUM	LP	LIGHTING PANEL
AM	AMMETER	MCB	MAIN CIRCUIT BREAKER
ATC	AUTOMATIC TEMPERATURE CONTROL	MCC	MOTOR CONTROL CENTER
ATS	AUTOMATIC TRANSFER SWITCH	MLO	MAIN LUGS ONLY
AWG	AMERICAN WIRE GAUGE	MTD	MOUNTED
C	CONDUIT	NIC	NOT IN CONTRACT
CAT.	CATALOG	NTS	NOT TO SCALE
CB	CIRCUIT BREAKER	NC	NORMALLY CLOSED
CATV	CABLE TELEVISION	NL	NEW LOCATION OF EXISTING
CCTV	CLOSED CIRCUIT TELEVISION	NO	NORMALLY OPEN
CKT	CIRCUIT	NR	NEW TO REPLACE EXISTING
CLG	CEILING	P	POLE
CU	COPPER	PNL	PANEL
DP	DISTRIBUTION PANEL	PH, ø	PHASE
DISC. SW.	DISCONNECT SWITCH	PP	POWER PANEL
CONTR.	CONTRACTOR	RE	REMOVE EXISTING
EF	EXHAUST FAN	RL	RELOCATE EXISTING
EM	EMERGENCY	RR	REMOVE AND REPLACE
EWC	ELECTRIC WATER COOLER	RGS	RIGID GALVANIZED STEEL
EX	EXISTING	TEL	TELEPHONE
EXT	EXTERIOR	TYP	TYPICAL
GFCI	GROUND FAULT CIRCUIT INTERRUPTER	U.G.	UNDERGROUND
GND	GROUND	V	VOLTS
HOA	HAND-OFF-AUTOMATIC	VIF	VERIFY IN FIELD
HP	HORSE POWER	W	WATTS
HZ	HERTZ	WP	WEATHER PROOF
IG	ISOLATED GROUND	XFMR	TRANSFORMER

ELECTRICAL SCOPE OF WORK

THE WORK INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:

1. ELECTRICAL SYSTEM MODIFICATIONS. (BOILER FEEDS & CONTROLS)
2. EMERGENCY LIGHTING SYSTEM MODIFICATIONS AS INDICATED.
3. LIFE SAFETY (EXIT SIGNS) AS INDICATED.
4. GROUNDING SYSTEM PROVIDED AS REQUIRED BY ALL LOCAL CODES.
5. FIRESTOPPING REQUIREMENTS PER DIVISION 7 AND THE CONTRACT DOCUMENTS.
6. SEISMIC BRACING OF ELECTRICAL EQUIPMENT WHERE REQUIRED BY THE SPECIFICATIONS AND STATE OF CONNECTICUT.
7. SHOP DRAWINGS AND OPERATION MANUALS AS REQUIRED BY THE SPECIFICATIONS.

FIRE ALARM DEVICES

SYMBOL	DESCRIPTION
	FIRE ALARM HORN/A.D.A. STROBE
H	AUTOMATIC FIRE ALARM HEAT DETECTOR
F	FIRE ALARM PULL STATION
MM	FIRE ALARM MONITOR MODULE
CM	FIRE ALARM CARBON MONOXIDE DETECTOR

DEVICE MOUNTING HEIGHTS

SYMBOL	DESCRIPTION
	DUPLEX RECEPTACLE AT 18" TO CENTER A.F.F., UNLESS OTHERWISE NOTED
S_S	SINGLE OR THREE-WAY POLE TOGGLE SWITCH AT 48" TO TOP OF PLATE A.F.F., UNLESS OTHERWISE NOTED

POWER & BRANCH CIRCUITING

SYMBOL	DESCRIPTION
	EXISTING DUPLEX RECEPTACLE
	EXISTING MOTOR STARTER
	EXISTING PANEL BOARD
	NEW JUNCTION BOX
	NEW DUPLEX RECEPTACLE

LIGHTING DEVICES

SYMBOL	DESCRIPTION
	EXISTING 6" X 4' FLUORESCENT STRIP LUMINAIRE
	NEW 6" X 4' FLUORESCENT STRIP LUMINAIRE
S_3	THREE-WAY TOGGLE SWITCH
	EXISTING INCANDESCENT SOCKET LUMINAIRE
	NEW EMERGENCY WALL PACK
EXIT	NEW COMBINATION EXIT SIGN/EMERGENCY LIGHT
	EXISTING EMERGENCY WALL PACK

SYMBOLS SHOWN FOR REFERENCE ONLY AND DO NOT CONSTITUTE A CHECK LIST OF DEVICES REQUIRED BY THE CONTRACTOR

THE EXIT SIGNS SHALL BE VISIBLE AT A MINIMUM OF 100 FEET. AT NO POINT SHALL EXIT SIGNS EXCEED 100 FEET FROM ONE TO THE OTHER IN ACCESS CORRIDOR. CHEVRONS SHALL BE IDENTIFIABLE AT A MINIMUM DISTANCE OF 40 FEET.

MECHANICAL DRAWING LIST

DWG. NO.	REV.	DRAWING TITLE
RB-M101	-	PARTIAL FLOOR PLAN MECHANICAL
RB-M102	-	PARTIAL FLOOR PLAN MECHANICAL
RB-M103	-	PARTIAL FLOOR PLAN MECHANICAL
RB-M104	-	PARTIAL FLOOR PLAN MECHANICAL
RB-M105	-	BOILER ROOM PLAN DEMOLITION MECHANICAL
RB-M106	-	BOILER ROOM PLAN MECHANICAL
RB-M107	-	SCHEDULES AND DETAILS MECHANICAL

ELECTRICAL DRAWING LIST

DWG. NO.	REV.	DRAWING TITLE
RB-EG1	-	GENERAL NOTES, SYMBOL LEGENDS, ABBREVIATIONS AND DRAWING LISTS
RB-E100	-	LUMINAIRE & MECHANICAL EQUIPMENT WIRING SCHEDULES, DETAILS & NOTES
RB-ED101	-	ELECTRICAL DEMOLITION PLAN BOILER ROOM
RB-E101	-	PARTIAL FLOOR PLAN ELECTRICAL
RB-E102	-	PARTIAL FLOOR PLAN ELECTRICAL
RB-E103	-	PARTIAL FLOOR PLAN ELECTRICAL
RB-E104	-	ELECTRICAL FLOOR PLAN BOILER ROOM

ROSE • TISO & CO. LLC.
ARCHITECTS • SURVEYORS • ENGINEERS
WWW.ROSETISO.COM
35 BRENTWOOD AVENUE, FAIRFIELD, CT 06825
TEL: (203)610-6262 • FAX: (203)610-6404

MUSCO ENGINEERING ASSOCIATES
375 Morgan Lane, Unit 307
West Haven, CT 06516
(203) 932-1901 FAX (203) 931-1550
www.muscoengineering.com

REVISIONS

NO.	BY	DATE	DESCRIPTION

PROJECT TITLE

RACE BROOK SCHOOL
107 GRANNIS ROAD
ORANGE, CT
STATE PROJECT NO: TMP-107-QGCV

BOILERS & UNIT VENT. REPLACEMENTS

ORANGE CONNECTICUT 1822 TOWN SEAL

Prepared For:

TOWN OF ORANGE, CT
637 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE

GENERAL NOTES, SYMBOL LEGENDS, ABBREVIATIONS AND DRAWING LISTS

DESIGNED BY: TJB	SCALE: AS NOTED
DRAWN BY: TJB	DATE: 7-08-13
CHECKED BY: MVM	PROJECT NUMBER: 1605
CAD FILE: EG1.DWG	

SEAL	SHEET NUMBER
	RB-EG1

MEA# 130416-1



FIRST FLOOR

FIRE ALARM SYSTEM NOTES:

1. CONTRACTOR SHALL PROVIDE ALL CONNECTIONS TO THE EXISTING FIRE ALARM SYSTEM AS REQUIRED. COORDINATE ALL WIRING REQUIREMENTS AND METHODS WITH THE MANUFACTURER, SIMPLEX–GRINNELL AS NECESSARY.
2. CARBON MONIOXIDE (CO) DETECTION SHALL ACTIVATE A SUPERVISORY SIGNAL IN THE EXISTING SIMPLEX/GRINNELL FIRE ALARM CONTROL PANEL AND ALL REMOTE ANNUNCIATORS, AS PER CT. GENERAL STATUTE #29–292.
3. CARBON MONIOXIDE (CO) DETECTION SHALL NOT CAUSE AN EVACUATION OF THE BUILDING, AS PER CT. GENERAL STATUTE #29–292.
4. FIRE ALARM DEVICES AND WIRING INSTALLATION SHALL BE AS PER MANUFACTURER'S INSTRUCTIONS LOCATE CO DETECTOR AS FAR AS POSSIBLE FROM HEATING APPLIANCE AND AS PER MANUFACTURERS INSTRUCTIONS AND NFPA 72.
5. FIRE ALARM SYSTEM SHALL BE TESTED AND MAINTAINED AS PER MANUFACTURER'S INSTRUCTIONS AND AS PER NFPA 72.

TYPICAL FIRE ALARM RISER
NOT TO SCALE

GENERAL NOTES:

1. INSTALLATIONS SHALL COMPLY TO FEDERAL, STATE, AND LOCAL BUILDING CODES.
2. ALL WIRING SHALL COMPLY WITH APPLICABLE SECTIONS OF THE NATIONAL ELECTRICAL CODE 2005.
3. WIRING REQUIREMENTS ARE AS FOLLOWS:
   USE OF STRANDED CONDUCTORS WITH MAXIMUM 7 STRANDS FOR #16 AND MAX. 19 STRANDS FOR SIZES #14 OR LARGER IS PERMITTED.
   USE ONLY APPROVED FIRE ALARM CABLES OR WIRES WITHIN METAL CONDUITS, TERMINATE ALL WIRING WITH U.L. LISTED DEVICES.
4. NO SMOKE DETECTOR SHALL BE LOCATED WITHIN 3 FEET OF A SUPPLY AIR OUTLET REFER TO NFPA 72 FOR MORE GUIDELINES.
5. ALL INITIATION AND SIGNALING CIRCUITS SHALL BE CLASS B.
6. ALL LOW VOLTAGE WIRING MAY RUN IN A COMMON CONDUIT.
7. RUN AC POWER IN SEPARATE CONDUIT, DO NOT RUN WITHIN ANY OTHER CONDUIT CARRYING FIRE ALARM SYSTEM WIRING.
8. NO PARALLEL BRANCHING OR "T" SPLICES ARE PERMITTED ON SIGNALING CIRCUITS.
9. DETECTOR AND SIGNALING POLARITY SHALL BE OBSERVED.
10. ALL WIRING SHALL BE CHECKED FOR OPENS, SHORTS, AND GROUNDS.
11. ALL ENCLOSURES AND CONDUITS SHALL BE PROPERLY GROUNDED IN ACCORDANCE WITH THE 2005 EDITION OF THE NATIONAL ELECTRICAL CODE.
12. INTERLOCKS SHALL NOT EXCEED RATED CURRENT OF CONTACTS.
13. INSTALLATION TO BE COMPLETED IN A PROFESSIONAL, WORKMANLIKE MANNER.

SYSTEM INITIATION:

1. THE FOLLOWING DEVICES WILL CAUSE A LOCAL ALARM WHICH INCLUDES ACTIVATION OF ALL NOTIFICATION DEVICES (SPEAKER/STROBES) & EVACUATION OF BUILDING AS PER THE LOCAL FIRE MARSHAL (AHU)
   A. SMOKE DETECTORS
   B. PULL STATIONS
14. THE FOLLOWING DEVICES WILL SEND TROUBLE SIGNAL TO THE MAIN FIRE ALARM PANEL AND WILL ALSO SEND A SIGNAL TO THE LOCAL FIRE DEPARTMENT. THIS TROUBLE ALARM WILL NOT ACTIVATE THE SPEAKERS OR STROBES AND WILL NOT CAUSE AN EVACUATION OF BUILDING.
   A. TAMPER SWITCHES
   B. CARBON MONOXIDE DETECTORS
15. THE DEVICES SHOWN ON THE RISER DO NOT REPRESENT THE ACTUAL COUNT. ELECTRICAL CONTRACTOR SHALL REFER TO FIRE ALARM FLOOR PLANS FOR EXACT COUNTS OF DEVICES, AND BE RESPONSIBLE FOR ALL REQUIRED UNITS.
16. DO NOT LOAD EACH CIRCUIT ZONE WITH MORE THAN 60% OF CAPACITY.
17. IN EXPOSED AND/OR FINISHED AREAS, NEW FIRE ALARM WIRING SHALL BE RUN IN SURFACE METAL RACEWAY (WIREMOLD OR EQUAL).
18. ALL FIRE ALARM CABLE SHALL BE RUN IN AC CABLE AND/OR CONDUIT AND CONCEALED IN WALLS AND CEILINGS.

MECHANICAL EQUIPMENT WIRING SCHEDULE

DESCRIPTION	LOAD AMPS	VOLTAGE	CONDUCTORS NO.	SIZE	GND.	TYPE	CONDUIT SIZE	CIRCUIT BREAKER	CIRCUIT	REMARKS
BOILER #1	11	208/1ø	3	14	14	THWN	–	15A–2P	BOILER PANEL	–
BOILER #2	11	208/1ø	3	14	14	THWN	–	15A–2P	BOILER PANEL	–
BOILER #3	9.8	120/1ø	3	14	14	THWN	–	15A–1P	BOILER PANEL	–
BOILER #1–CONTROLS	0.12	120/1ø	3	12	12	THWN	–	20A–1P	BOILER PANEL	–
BOILER #2–CONTROLS	0.12	120/1ø	3	12	12	THWN	–	20A–1P	BOILER PANEL	–
BOILER #3–CONTROLS	0.12	120/1ø	3	12	12	THWN	–	20A–1P	BOILER PANEL	–
BOILER CONTROL PANEL	30.0	120/1ø	3	10	10	THWN	–	40A–1P	BOILER PANEL	–
NEW CIRC. PUMP (P6)	3.5	208/3ø	4	12	12	THWN	–	20A–1P	BOILER PANEL	–
EUH1	13.9	208/3ø	4	12	12	THWN	–	20A–1P	BOILER PANEL	ADD ALTERNATE #1
CARBON MONOXIDE DET.	0.09	120/1ø	3	12	12	THWN	–	20A–1P	BOILER PANEL	PLUG–IN

MECHNICAL EQUIPMENT NOTES:
1. CONTRACTOR SHALL VERIFY ALL OUTLET CONFIGURATIONS AND LOCATIONS WITH EQUIPMENT SUPPLIER PRIOR TO ROUGH–IN.
2. CONTRACTOR TO INSTALL ELECTRICAL CIRCUITS AND ASSOCIATED J–BOXES FOR ALL EQUIPMENT PROVIDED BY OTHERS.
3. MECHANICAL EQUIPMENT SHOWN ON THE DRAWINGS WERE OBTAINED AT TIME OF DESIGN AND MAY HAVE CHANGED. VERIFY WIRE/CONDUIT, BREAKER SIZE CONNECTION TO EQUIPMENT PRIOR TO ROUGH–IN.
4. REFER TO SPECIFICATIONS AND MECHANICAL DRAWINGS FOR ADDITIONAL ELECTRICAL REQUIREMENTS.

LUMINAIRE SCHEDULE

TYPE	MANUFACTURER	EST. WATTS	CATALOG NUMBER	LAMP QTY.	LAMP TYPE	VOLTS	BALLAST QTY.	BALLAST TYPE	MOUNTING	REMARKS	LOCATION
A	DAY–BRITE	57.6	IS232–120–1/2–EB–FKR–173–FL–123	2	32W T8 3500° K 75 CRI	120	1	ELECTRONIC INSTANT START	STRUCT. ABOVE	4' X 48" FLUORESCENT STRIP LUMINAIRE WITH WIRE GUARD, CHAINS & 'S' HOOKS	SEE PLANS
EM	CHLORIDE	24	CAX6L24W12	2	MR16 6W,6V	120	–	–	WALL	SELF–CONTAINED EMERGENCY BATTERY PACK LEAD CALCIUM BATTERY & SELF–DIAGNOSTICS	SEE PLANS
EX	CHLORIDE	2.64	VXL3RW	–	LED	120	–	–	UNIVERSAL	COMM. EXIT SIGNS, THERMOPLASTIC, WHITE HOUSING WITH RED LETTERING, LED	SEE PLANS
EX1	CHLORIDE	5.88	VCAL3RW	2	MR16 6W,6V	120	–	–	WALL	COMBINATION EMERG./LED EXIT SIGN–WHITE THERMO–PLASTIC WHITE HOUSING WITH LEAD CALCIUM BATTERY CHARGER & SELF–DIAGNOSTICS	SEE PLANS

NOTES:
1. ALL FLUORESCENT BALLASTS: THD MAX. = 10%, PROGRAMMED RAPID START.
2. ALL FLUORESCENT LAMPS TO HAVE MIN. CRI 85 AND COLOR TEMPERATURE OF 4100, 2850 INITIAL LUMENS MINIMUM, 24,000 HR. LIFE EXCEPT "U" OR COMPACT LAMPS.



SUSPENDED FIXTURE DETAIL
N.T.S.



DEVICE MOUNTING DETAIL
N.T.S.



TYPICAL DETAIL FOR EMERGENCY LIGHTING CONNECTION
N.T.S.

ROSE •TISO & CO. LLC.
ARCHITECTS • SURVEYORS • ENGINEERS
WWW.ROSETISO.COM
35 BRENTWOOD AVENUE, FAIRFIELD, CT 06825
TEL: (203)610-6262 • FAX: (203)610-6404

MUSCO ENGINEERING ASSOCIATES
375 Morgan Lane, Unit 307
West Haven, CT 06516
(203) 932-1901 FAX (203) 931-1550
www.muscoengineering.com

REVISIONS			
NO.	BY	DATE	DESCRIPTION

PROJECT TITLE

RACE BROOK SCHOOL
107 GRANNIS ROAD
ORANGE, CT
STATE PROJECT NO: TMP–107–QGCV

BOILERS & UNIT VENT. REPLACEMENTS

Prepared For:

TOWN OF ORANGE, CT
637 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE
LUMINAIRE & MECHANICAL EQUIP. WIRING SCHEDULES, DETAILS & NOTES

DESIGNED BY: TJB	SCALE: AS NOTED
DRAWN BY: TJB	DATE: 4–12–13
CHECKED BY: MVM	PROJECT NUMBER: 1605
CAD FILE: E101.DWG	

SEAL

SHEET NUMBER
RB–E100

MEA# 130416–1



ELECTRICAL DEMOLITION PLAN - ELECTRICAL

SCALE: 1/2"=1'-0"

DEMOLITION NOTES

1. LOCATION OF ALL EXISTING ELECTRICAL WORK SHOWN ON FLOOR PLANS ARE BASED ON BEST AVAILABLE INFORMATION. CONTRACTOR SHALL VERIFY ALL LOCATIONS OF EXISTING ELECTRICAL WORK IN THE FIELD.
2. DEMOLITION INSIDE THE BUILDING SHALL CONSIST OF THE REMOVAL AND/OR REPLACEMENT OF ELECTRICAL, COMMUNICATION AND/OR FIRE ALARM DEVICES AS SHOWN ON THE PLANS. CONTRACTOR SHALL GIVE ATTENTION TO SALVAGEABLE/RELOCATED FIXTURES AND HAND THEM OVER TO THE OWNER. ALL NONSALVAGEABLE MATERIAL SHALL BE DISPOSED OF PROPERLY ACCORDING WITH THE CODE AND REGULATIONS.
3. IT IS NOT THE INTENT OF THESE DRAWINGS TO SHOW ENTIRE EXISTING EQUIPMENT LAYOUT AND ELECTRICAL WORK. THE CONTRACTOR SHALL REMOVE ALL ELECTRICAL WORK AS SHOWN OR NOTED ON DRAWING AND ALSO ALL EQUIPMENT AND ELECTRICAL WORK NOT BEING USED. THE CONTRACTOR SHALL REMOVE ALL ELECTRICAL WORK ASSOCIATED WITH EQUIPMENT BEING REMOVED. FULL EXTENT OF DEMOLITION/RELOCATIONS SHALL BE DETERMINED BY THE CONTRACTOR DURING HIS SITE VISIT AND SHALL INCLUDE, BUT NOT BE LIMITED TO: LIGHTING FIXTURES, RECEPTACLES, SWITCHES, FIRE ALARM, TELEPHONE, JUNCTION BOXES, CONDUIT, WIRING AND PANELS.
4. ALL OTHER EXISTING ELECTRICAL WORK SHALL REMAIN UNLESS OTHERWISE NOTED.
5. ALL HANGERS AND SUPPORTS SHALL BE REMOVED ALONG WITH CONDUIT BEING REMOVED AS A PART OF THIS CONTRACT. ALL EQUIPMENT SUPPORTS SHALL BE REMOVED ALONG WITH EQUIPMENT BEING REMOVED AS PART OF THIS CONTRACT.
6. ANY CONDUIT AND WIRING FOUND IN WALLS OR CEILINGS DURING DEMOLITION WALL BECOME PART OF THIS CONTRACT. ENGINEER SHALL BE NOTIFIED PRIOR TO REMOVAL. IF CONDUIT AND WIRING IS FEEDING EQUIPMENT TO REMAIN IN SERVICE, CONTRACTOR SHALL RELOCATE CONDUIT AND WIRING AND REFEED AFFECTED EQUIPMENT IN FULL OPERATING ORDER.
7. REFER TO DRAWINGS TH-EG1 FOR GENERAL NOTES, SYMBOL LEGENDS, ABBREVIATIONS AND DRAWING LISTS.
8. THE CONTRACTOR SHALL SEAL ALL PENETRATIONS THROUGH SMOKE & FIRE RATED PARTITIONS AND FLOORS WITH A UL LISTED SMOKE AND/OR FIRE STOP TO MAINTAIN THE INTEGRITY OF THE SMOKE/FIRE RATING. REFER TO ARCHITECTURAL DRAWINGS FOR FIRE/SMOKE RATINGS. PROVIDE SHOP DRAWINGS FOR ALL PENETRATIONS. REFER TO DIVISION 7 FOR ADDITIONAL REQUIREMENTS. ALL FLOOR/WALL PENETRATIONS SHALL BE SEALED AS PER ASTM E814.
9. REMOVE ALL JUNCTION BOXES, BACKBOXES, COVER PLATES, WIRING AND CONDUIT IN ITS ENTIRETY BACK TO SOURCE, FOR ALL ELECTRICAL DEVICES INDICATED ON THE FLOOR PLANS, UNLESS SPECIFICALLY NOTED OTHERWISE ON THE DRAWINGS.
10. THE OWNER IS RESPONSIBLE FOR THE REMOVAL OR ABATEMENT OF ANY AND ALL ASBESTOS RELATED MATERIALS PRIOR TO THE CONTRACTOR COMMENCING WITH HIS WORK. HOWEVER, OF THE CONTRACTOR SHOULD ENCOUNTER ANY MATERIALS WHICH HE SUSPECTS TO BE LADEN WITH ASBESTOS, HE SHALL CEASE WORK AT ONCE AND REPORT HIS FINDING TO THE OWNERS REPRESENTATIVE.
11. ANY ELECTRICAL SHUTDOWNS REQUIRED TO COMPLETE THE DEMOLITION WORK SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. SHUTDOWNS SHALL BE COORDINATED 48 HOURS IN ADVANCE WITH THE OWNERS REPRESENTATIVE.
12. ALL AREAS NOT UNDER CONSTRUCTION SHALL BE KEPT OPERATIONAL DURING CONSTRUCTION. TO ACCOMPLISH THIS, PROVIDE THE NECESSARY TEMPORARY ELECTRICAL SERVICES. REMOVE TEMPORARY DEVICES UPON COMPLETION OF THE PROJECT.
13. RELOCATE OR REMOVE ALL ELECTRICAL DEVICES IN ACCORDANCE WITH THE 2005 NEC. WHEN RELOCATION OR REMOVAL OF AN ELECTRICAL DEVICE INTERRUPTS THE CONTINUITY OF A CIRCUIT, REROUTE THESE CIRCUITS AS REQUIRED TO MAINTAIN CIRCUIT CONTINUITY.
14. WHERE REMOVAL OR RELOCATION OF EXISTING CONDUIT(S) PASSES THROUGH EXISTING WALLS, THE OPENINGS SHALL BE SEALED AND PAINTED TO MATCH THE EXISTING WALLS/AREAS.
15. EXISTING LUMINAIRES SHALL BE REMOVED AND REPLACED WITH NEW FIXTURES AS INDICATED ON DWG. RB-E104 AND LUMINAIRE SCHEDULE ON DWG. RB-E100.
16. EXISTING BOILER ROOM PANELS SHALL BE REMOVED AND REPLACED WITH NEW PANELS. AS INDICATED ON DWG. RB-E104.



KEY PLAN

NOTES:

1. REFER TO PROJECT MANUAL FOR ELECTRICAL SPECIFICATIONS.
2. REFER TO DRAWING RB-M103 FOR MECHANICAL SEQUENCE OF OPERATIONS, AND SCOPE OF WORK. REFER TO DRAWING RB-M102 FOR EQUIPMENT SELECTION.
3. THE CONTRACTOR SHALL SEAL ALL PENETRATIONS THROUGH FIRE RATED WALLS AS INDICATED ON DRAWING TH-EG101 WITH A U.L. LISTED FIRESTOP TO MAINTAIN THE INTEGRITY OF THE FIRE RATING. PROVIDE SHOP DRAWINGS FOR ALL PENETRATIONS. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
4. REFER TO DRAWING TH-EG1 FOR GENERAL NOTES, SYMBOL LEGENDS, ABBREVIATIONS AND DRAWING LISTS.
5. REFER TO PROJECT MANUAL FOR ELECTRICAL SPECIFICATIONS.
6. REFER TO DRAWING TH-E100 FOR LUMINAIRE SCHEDULE, EQUIP. WIRING SCHEDULE, DETAILS AND NOTES.

ROSE •TISO & CO. LLC.
ARCHITECTS • SURVEYORS • ENGINEERS
WWW.ROSETISO.COM
35 BRENTWOOD AVENUE, FAIRFIELD, CT 06825
TEL: (203)610-6262 • FAX: (203)610-6404

MUSCO ENGINEERING ASSOCIATES
375 Morgan Lane, Unit 307
West Haven, CT 06516
(203) 932-1901 FAX (203) 931-1550
www.muscoengineering.com

REVISIONS			
NO.	BY	DATE	DESCRIPTION

PROJECT TITLE

RACE BROOK SCHOOL
107 GRANNIS ROAD
ORANGE, CT
STATE PROJECT NO: TMP-107-QGCV

BOILER & UNIT VENT. REPLACEMENTS

ORANGE CONNECTICUT 1822 TOWN SEAL

Prepared For:

TOWN OF ORANGE, CT
637 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE

ELECTRICAL DEMOLITION PLAN BOILER ROOM

DESIGNED BY: TJB	SCALE: AS NOTED
DRAWN BY: TJB	DATE: 7-08-13
CHECKED BY: MVM	PROJECT NUMBER: 1605
CAD FILE: ED101.DWG	

SEAL

SHEET NUMBER

RB-ED101

MEA #130416-1



ELECTRICAL FLOOR PLAN
SCALE: 1/8" = 1'-0"



KEY PLAN

NOTES:

1. REFER TO PROJECT MANUAL FOR SPECIFICATIONS.
2. REFER TO DRAWING RB-M103 FOR MECHANICAL SEQUENCE OF OPERATIONS, AND SCOPE OF WORK. REFER TO DRAWING RB-M102 FOR EQUIPMENT SELECTION.
3. THE CONTRACTOR SHALL SEAL ALL PENETRATIONS THROUGH FIRE RATED WALLS AS INDICATED ON DRAWING TH-EG101 WITH A U.L. LISTED FIRESTOP TO MAINTAIN THE INTEGRITY OF THE FIRE RATING. PROVIDE SHOP DRAWINGS FOR ALL PENETRATIONS. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
4. CONTRACTOR SHALL VERIFY TYPE AND QUANTITY OF EXISTING CIRCUIT BREAKERS TO BE REPLACED IN EXISTING PANELS.

ROSE •TISO & CO. LLC.
ARCHITECTS ● SURVEYORS ● ENGINEERS
WWW.ROSETISO.COM
35 BRENTWOOD AVENUE, FAIRFIELD, CT 06825
TEL: (203)610-6262 ● FAX: (203)610-6404

MUSCO ENGINEERING ASSOCIATES
375 Morgan Lane, Unit 307
West Haven, CT 06516
(203) 932-1901 FAX (203) 931-1550
www.muscoengineering.com

REVISIONS			
NO.	BY	DATE	DESCRIPTION

PROJECT TITLE

RACE BROOK SCHOOL
107 GRANNIS ROAD
ORANGE, CT
STATE PROJECT NO:
TMP-107-QGCV

BOILER & UNIT VENT. REPLACEMENTS

ORANGE CONNECTICUT 1822 TOWN SEAL

Prepared For:

TOWN OF ORANGE, CT
637 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE

PARTIAL ELECTRICAL FLOOR PLAN

DESIGNED BY: TJB	SCALE: AS NOTED
DRAWN BY: TJB	DATE: 7-08-13
CHECKED BY: MVM	PROJECT NUMBER: 1605
CAD FILE: E101.DWG	

SEAL	SHEET NUMBER
	RB-E101

MEA #130416-1



ELECTRICAL FLOOR PLAN

SCALE: 1/8" = 1'-0"



KEY PLAN

NOTES:

1. REFER TO PROJECT MANUAL FOR SPECIFICATIONS.
2. REFER TO DRAWING RB-M103 FOR MECHANICAL SEQUENCE OF OPERATIONS, AND SCOPE OF WORK. REFER TO DRAWING RB-M102 FOR EQUIPMENT SELECTION.
3. THE CONTRACTOR SHALL SEAL ALL PENETRATIONS THROUGH FIRE RATED WALLS AS INDICATED ON DRAWING TH-EG101 WITH A U.L. LISTED FIRESTOP TO MAINTAIN THE INTEGRITY OF THE FIRE RATING. PROVIDE SHOP DRAWINGS FOR ALL PENETRATIONS. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
4. CONTRACTOR SHALL VERIFY TYPE AND QUANTITY OF EXISTING CIRCUIT BREAKERS TO BE REPLACED IN EXISTING PANELS.

ROSE •TISO & Co. LLC.
ARCHITECTS • SURVEYORS • ENGINEERS
WWW.ROSETISO.COM
35 BRENTWOOD AVENUE, FAIRFIELD, CT 06825
TEL: (203)610-6262 • FAX: (203)610-6404

MUSCO ENGINEERING ASSOCIATES
375 Morgan Lane, Unit 307
West Haven, CT 06516
(203) 932-1901 FAX (203) 931-1550
www.muscoengineering.com

REVISIONS			
NO.	BY	DATE	DESCRIPTION

PROJECT TITLE

RACE BROOK SCHOOL
107 GRANNIS ROAD
ORANGE, CT
STATE PROJECT NO:
TMP-107-QGCV

BOILER & UNIT VENT. REPLACEMENTS

ORANGE CONNECTICUT 1822 TOWN SEAL

Prepared For:

TOWN OF ORANGE, CT
637 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE

PARTIAL ELECTRICAL FLOOR PLAN

DESIGNED BY: TJB	SCALE: AS NOTED
DRAWN BY: TJB	DATE: 7-08-13
CHECKED BY: MVM	PROJECT NUMBER: 1605
CAD FILE: E102.DWG	

SEAL	SHEET NUMBER
	RB-E102

MEA #130416-1



ELECTRICAL FLOOR PLAN
SCALE: 1/8" = 1'-0"



KEY PLAN

NOTES:

1. REFER TO PROJECT MANUAL FOR SPECIFICATIONS.
2. REFER TO DRAWING RB-M103 FOR MECHANICAL SEQUENCE OF OPERATIONS, AND SCOPE OF WORK. REFER TO DRAWING RB-M102 FOR EQUIPMENT SELECTION.
3. THE CONTRACTOR SHALL SEAL ALL PENETRATIONS THROUGH FIRE RATED WALLS AS INDICATED ON DRAWING TH-EG101 WITH A U.L. LISTED FIRESTOP TO MAINTAIN THE INTEGRITY OF THE FIRE RATING. PROVIDE SHOP DRAWINGS FOR ALL PENETRATIONS. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
4. CONTRACTOR SHALL VERIFY TYPE AND QUANTITY OF EXISTING CIRCUIT BREAKERS TO BE REPLACED IN EXISTING PANELS.

ROSE •TISO & CO. LLC.
ARCHITECTS • SURVEYORS • ENGINEERS
WWW.ROSETISO.COM
35 BRENTWOOD AVENUE, FAIRFIELD, CT 06825
TEL: (203)610-6262 • FAX: (203)610-6404

MUSCO ENGINEERING ASSOCIATES
375 Morgan Lane, Unit 307
West Haven, CT 06516
(203) 932-1901 FAX (203) 931-1550
www.muscoengineering.com

REVISIONS

NO.	BY	DATE	DESCRIPTION

PROJECT TITLE

RACE BROOK SCHOOL
107 GRANNIS ROAD
ORANGE, CT
STATE PROJECT NO: TMP-107-QGCV

BOILER & UNIT VENT. REPLACEMENTS

ORANGE CONNECTICUT 1822 TOWN SEAL

Prepared For:

TOWN OF ORANGE, CT
637 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE

PARTIAL ELECTRICAL FLOOR PLAN

DESIGNED BY: TJB	SCALE: AS NOTED
DRAWN BY: TJB	DATE: 7-08-13
CHECKED BY: MVM	PROJECT NUMBER: 1605
CAD FILE: E103.DWG	

SEAL

SHEET NUMBER

RB-E103

MEA #130416-1



BOILER ROOM FLOOR PLAN – ELECTRICAL

SCALE: 1/2"=1'–0"



PART. MEZZANINE PLAN – ELECTRICAL

SCALE: 1/2"=1'–0"



KEY PLAN

BOILER PANEL: 225AMP, 208/120V, 3ø, 4W MLO SURFACE MOUNTED WITH BRANCH BREAKERS AS FOLLOWS:

9, 20A–1P C/B'S
1, 20A–3P C/B
2, 30A–2P C/B'S
2, 30A–3P C/B'S

PANEL LP–Y: 225AMP, 208/120V, 3ø, 4W MLO DOUBLE SURFACE MOUNTED WITH BRANCH BREAKERS AS FOLLOWS:

LEFT SIDE	RIGHT SIDE
21, 20A–1P C/B'S	3, 20A–1P C/B'S
1, 60A–3P C/B	1, 20A–3P C/B
	2, 25A–3P C/B'S
	3, 40A–3P C/B'S
	1, 60A–3P C/B

NOTES:

1. REFER TO PROJECT MANUAL FOR SPECIFICATIONS.
2. REFER TO DRAWING RB–M103 FOR MECHANICAL SEQUENCE OF OPERATIONS, AND SCOPE OF WORK. REFER TO DRAWING RB–M102 FOR EQUIPMENT SELECTION.
3. THE CONTRACTOR SHALL SEAL ALL PENETRATIONS THROUGH FIRE RATED WALLS AS INDICATED ON DRAWING TH–EG101 WITH A U.L. LISTED FIRESTOP TO MAINTAIN THE INTEGRITY OF THE FIRE RATING. PROVIDE SHOP DRAWINGS FOR ALL PENETRATIONS. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
4. THE CONTRACTOR SHALL COORDINATE THE EXACT LOCATION OF NEW LUMINAIRES WITH THE EXISTING PLUMBING AND MECHANICAL EQUIPMENT AND DEVICES AT THE CEILING LEVEL AS NECESSARY.
5. REFER TO DRAWING TH–E100 FOR FIRE ALARM RISER DIAGRAM AND NOTES.

ROSE •TISO & CO. LLC.
ARCHITECTS • SURVEYORS • ENGINEERS
WWW.ROSETISO.COM
35 BRENTWOOD AVENUE, FAIRFIELD, CT 06825
TEL: (203)610-6262 • FAX: (203)610-6404

MUSCO ENGINEERING ASSOCIATES
375 Morgan Lane, Unit 307
West Haven, CT 06516
(203) 932-1901 FAX (203) 931-1550
www.muscoengineering.com

REVISIONS			
NO.	BY	DATE	DESCRIPTION

PROJECT TITLE

RACE BROOK SCHOOL
107 GRANNIS ROAD
ORANGE, CT
STATE PROJECT NO:
TMP-107-QGCV

BOILER & UNIT VENT. REPLACEMENTS

ORANGE CONNECTICUT 1822 TOWN SEAL

Prepared For:

TOWN OF ORANGE, CT
637 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE

ENLARGED BOILER ROOM ELECTRICAL PLAN

DESIGNED BY: TJB	SCALE: AS NOTED
DRAWN BY: TJB	DATE: 7–08–13
CHECKED BY: MVM	PROJECT NUMBER: 1605
CAD FILE: E104.DWG	

SEAL

SHEET NUMBER

RB-E104

MEA #130416–1