

BHS Hydronic Heat Pumps

ADDENDUM #1

Issued November 16, 2016

CLARIFICATIONS TO SPECIFICATIONS

1. The project consists of replacement of two 25HP Taco hydronic pumps.
2. The existing balancing valves and strainers are to remain and will not be part of the bid requirement.
3. Replacement of the flex connectors on the discharge side of the pumps are to be replaced as part of the project.
4. The existing pipe flanges, elbows and reducing fittings can be reused provided they are in good condition and alignment.
5. The pumps are heating only and the system does not contain glycol.
6. A performance bond is not required on this project.
7. Provisions for a Testing and Balancing agent are not required. If it is determined that rebalancing is needed the district will contract for those services.