ITEM #0000756A – DRAINAGE STRUCTURE REPAIR

Description: Work under this item shall consist of replacing an existing steel drainage scupper pipe.

Materials: Match the existing size and material type, and meet the requirements of Article M.08.01.

Construction Methods: Remove and dispose of the existing scupper pipe back to the nearest joints beyond the limits of deterioration, as delineated by the Engineer.

Attach new pipe sections to the existing system using approved methodologies.

Method of Measurement: This work, being paid for on a Lump Sum basis, shall not be measured for payment.

Basis of Payment: This work will be paid for at the contract Lump Sum price for "Drainage Structure Repair", which price shall include the work defined herein, including conduit, straps, digging as required to access existing conduit ends and all materials, equipment, tools, labor and work incidental thereto.

Pay Item	Pay Unit
Drainage Structure Repair	l.s.