ITEM #0814002A – RESET GRANITE STONE CURBING

Description: Work under this item shall consist of removing, storing and reinstalling existing granite stone curbing as necessary for the reconstruction of the concrete sidewalk sections, to the limits and details shown on the plans or as ordered by the Engineer.

Materials: Existing granite stone curbing and anchoring bars which is acceptable shall be used. The reset stone curbing shall be in length of not less than 4 feet, except where necessary for closures, where no piece shall be less than 3 feet in length. Mortar for this work shall conform to Article M.11.04. Joint seal shall conform to Article M.03.08.

Construction Methods: The construction methods for this work shall conform to the requirements of Article 8.13.03 for stone curbing, as supplemented by the following requirements:

The curbing to be reset shall be removed with care to avoid damage to the curbs and the anchor bars. Any damaged curbs or anchor bars shall be replaced at the Contractor's expense.

Method of Measurement: This work will be measured for payment by the actual number of linear feet of curbing, reset and accepted. Measurement shall be made along the top arris line of face of curb.

Basis of Payment: This work will be paid for at the contract unit price per linear foot for "Reset Granite Stone Curbing", complete in place, which price shall include removing, storing and reinstalling granite stone curbing, all materials, equipment, tools and labor incidental thereto.

Pay Item	Pay Unit
Reset Granite Stone Curbing	L.F.