ITEM #0511204A – EXTEND EXISTING WEEPHOLES

Description:

Work under this item shall consist of installing PVC pipe with flexible hose below the bridge deck, in order to extend the existing broken deck weepholes outward and away from the bridge.

Materials:

PVC plastic pipe shall conform to the requirements of Subarticle M.08.01-20, of Form 816.

Construction Methods:

The new length of PVC pipe with appropriate coupling shall be attached to the existing weepholes to remain. The length of pipe shall be such that the bottom end stops 6 inches horizontally from all bridge components and shall extend three (3) inches below the bottom flange of the girders.

In cases where the protruding stub is not sufficiently long enough to allow installation of a typical PVC coupling, a short length of PVC pipe shall be inserted into the existing pipe in order to extend it.

The joint between the new and old pipes shall be thoroughly cleaned and solvent welded.

Method of Measurement:

This work will be measured for payment by the actual number of weephole pipes extensions installed and accepted.

Basis of Payment:

This work shall be paid for at the contract unit price, per each, for "Extend Existing Weepholes", which price shall include all materials, equipment, tools and labor incidental thereto.

Pay Item	Pay Unit
Extend Existing Weepholes	EA.