ITEM #0921001A – CONCRETE SIDEWALK

Work under this item shall conform to the requirements of Section 9.21, amended as follows:

9.21.01-Description: Add the following:

Concrete sidewalks shall be removed and disposed of in accordance with these specifications, where shown on the contract plans or as ordered by the Engineer.

Existing granite curbing along sidewalk sections shall be removed, preserved and reset. Membrane waterproofing and asphalt overlay adjacent to the curb shall be replaced as per contract plans.

9.21.02-Materials: Add the following:

Replacement membrane waterproofing shall be compatible with the existing system, and shall meet the requirements of Item #0707009A, "Membrane Waterproofing (Cold Liquid Elastomeric)". Membrane Waterproofing shall not be measured for separate payment when provided at concrete sidewalk repairs and shall be incidental to "Concrete Sidewalk".

Replacement asphalt overlay shall be compatible with the existing pavement, and shall meet the requirements of Item #0406171, "HMA S0.50" and Item #0406173, "HMA S0.25". Asphalt overlays shall not be measured for separate payment when provided at concrete sidewalk repairs and shall be incidental to "Concrete Sidewalk".

9.21.03-Construction Methods: Add the following:

Wherever portions of concrete sidewalks are to be removed, such removals shall be made to neat lines. Partial removals shall generally be to existing joints except when a location other than a joint is set as the limit by the Engineer due to construction staging limits. At removal limits where a joint is not present, the Contractor shall sawcut the concrete full depth to create a neat line.

Lap waterproofing membrane so that the upstream section laps over the downstream section.

9.21.04-Method of Measurement: Add the following:

The work of removing concrete sidewalk shall be measured in place before removal for payment by the number of square feet of concrete sidewalk removed and shall not include the area of the curbing or pavement to be removed.

9.21.05-Basis of Payment: Add the following:

The removal of concrete sidewalk will be paid for at the contract unit price per square foot for

"Concrete Sidewalk" which price shall include all materials, equipment, tools and labor incidental thereto including membrane waterproofing, asphalt overlay, cutting concrete at neat lines and all disposal costs.

The removal and resetting of granite curb will be measured and paid under the item Reset Granite Stone Curbing.

Pay Item	Pay Unit
Concrete Sidewalk	s.f.