NOTICE TO CONTRACTOR – RAILROAD REQUIREMENTS

The Contractor is hereby notified that in addition to the railroad specifications contained elsewhere in the Contract, the following additional requirements provided by the railroad shall be made a part of this Contract, and the Contractor shall be bound to comply with them.

- Any proposed construction and/or utility work to be performed within or above the Railroad Right-of-Way (ROW) and/or impacting Railroad Operations must be approved by Pan Am Railroad's Engineering Department and conducted under the supervision of a Railroad Flagman/Inspector. All work shall be coordinated accordingly with train movements. No persons will be allowed onto Railroad property for any reason without prior approval and with the presence of a flagman/inspector if needed.

- Track shielding provisions may be required at the discretion of the Railroad Flagman/Inspector in order to protect the track structure and ballast from any damage and/or contamination by falling dust and other debris during the performance of this project. The Contractor will be responsible for any repair or replacement charges if the Railroad track or other structures are damaged during construction.

- The existing clearance is listed as 18' - 8". Pan Am requires that any proposed change in elevation not decrease the clearance.

- All final drawings of this project shall be stamped by a Professional Engineer Registered in the State of Connecticut.

- Any temporary structures used in a repair that may impact Pan Am operations will need to be submitted to Pan Am Railroad for review.

- The Contractor shall submit work plans to Pan Am Railroad detailing the materials, construction procedures with respect to bridge repair and during the portion of this project affecting Railroad Property and/or Operations for review and approval prior to scheduling work.

- The Contractor will be required to execute a Standard Railroad Service Contract and provide an acceptable Railroad-protective insurance policy to Pan Am Railroad's Real Estate Department prior to commencing work on the project. The Contractor shall contact Mr. Mike Twidle at (978) 663-6937 for coordination of all Real Estate requirements.