06 - LANDSCAPE

INDEX OF DRAWINGS

DRAWING NUMBER	DRAWING TITLE	DRAWING NUMBER	DRAWING TITLE
LDS-01	**LANDSCAPE INDEX OF DRAWINGS**		
LDS-02	**LANDSCAPE DESIGN SHEET**		

THE DESIGN APPEARS TO CONFORM TO APPLICABLE CRITERIA. APPROVAL IS NOT TO BE CONSTRUED TO MEAN THAT ALL ASPECTS OF THE DESIGN HAVE BEEN PERSONALLY CHECKED BY THE UNDERSIGNED.

Scott Bushee, P.E.
I have reviewed this document
2017.07.17 09:56:42-04'00'

TRANSPORTATION PRINCIPAL ENGINEER

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/10/2017

DESIGNER/DRAFTER: M. VERRY
CHECKED BY: D. BARNES
SCALE IN FEET 0 20 40
SCALE 1"=20'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\HW_MSH_0102-0356_LDS-01.dgn

SIGNATURE/ BLOCK:
OFFICE OF ENGINEERING
APPROVED BY:

PROJECT TITLE:
REHABILITATION OF BRIDGE NO. 00722 WEST ROCKS RD. OVER ROUTE 15

TOWN: **NORWALK**

DRAWING TITLE: **LANDSCAPE INDEX OF DRAWINGS**

PROJECT NO. **102-356**
DRAWING NO. **LDS-01**
SHEET NO. **06.01**



PLANT LIST

KEY	BOTANICAL NAME	COMMON NAME	SIZE	QTY.	SPACING	COMMENTS
Am.c.	Amelanchier canadensis	Shadblow Serviceberry	4'-5' Ht. B.B.	6	6' On Center	
*A.r.	Acer rubrum	Red Maple	2"-2 1/2" Cal B.B.	5	Field Locate	Spring Dig Only
A.r.	Acer rubrum	Red Maple	3'-4' Ht. Whips B.R.	50	5' On Center	
Cr.c.	Crataegus crusgalli	Cockspur Hawthorn	8'-10' Ht. B.B.	3	Field Locate	Spring Dig Only
K.l.	Kalmia latifolia	Mountain Laurel	3' - 3 1/2' Ht. B.B.	5	Field Locate	
Pic.a.	Picea abies	Norway Spruce	6'-8' Ht. B.B.	6	Field Locate	
*Q.p.	Quercus palustris	Pin Oak	2"-2 1/2" Cal B.B.	4	Field Locate	Spring Dig Only
Q.p.	Quercus palustris	Pin Oak	24" - 36" Ht. No.3 Container	50	5' On Center	
Q.r.	Quercus rubra	Northern Red Oak	24" - 36" Ht. No.3 Container	50	5' On Center	
Rh.a.	Rhus aromatica	Fragrant Sumac	18" - 24" Ht. B.B.	65	5' On Center	
Rho.m.	Rhododendron maximum	Rosebay Rhododendron	3'-4' Ht. B.B.	6	Field Locate	
Control & Removal of Invasive Vegetation				500 S.Y.		See Note 5
Wood Chip Mulch				625 S.Y.		

NOTES

1. ALL AREAS DISTURBED BY CONSTRUCTION SHALL BE SEEDED WITH TURF ESTABLISHMENT - LAWN

2. ALL TREES AND SHRUBS MUST CONFORM TO THE AMERICAN STANDARD FOR NURSERY STOCK FOR DECIDUOUS SHRUBS, SECTION 3, AND MEET THE MINIMUM CONTAINER SIZE AND ROOT MASS AND NUMBER OF CANES FOR TYPE AND HEIGHT SPECIFIED.

3. "*" DENOTES PLANTS WITH TWO SIZES

4. "SPRING DIG ONLY" DENOTES SPECIES THAT MUST BE DUG AND SECURED IN THE SPRING ONLY

5. PERFORM CONTROL AND REMOVAL OF INVASIVE VEGETATION AS NEEDED AS SPECIFIED IN THE FIELD BY THE LANDSCAPE DESIGNER.

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/10/2017

DESIGNER/DRAFTER: M. VERRY
CHECKED BY: D. BARNES
SCALE IN FEET 0 20 40
SCALE 1"=20'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\HW_MSH_0102-0356_LDS-02.dgn

SIGNATURE/BLOCK: OFFICE OF ENGINEERING
APPROVED BY:

PROJECT TITLE: REHABILITATION OF BRIDGE NO. 00722 WEST ROCKS RD. OVER ROUTE 15

TOWN: NORWALK

DRAWING TITLE: LANDSCAPE DESIGN SHEET

PROJECT NO. 102-356
DRAWING NO. LDS-02
SHEET NO. 06.02