



ADDENDUM NO.: 3

DATE OF ADDENDUM: March 26, 2012

**Oil Tank Installation  
Connecticut Valley Hospital, Middletown, CT  
BI – MH – 923**

Original Proposal Due Date / Time:	March 20, 2012	1:00 pm
Revised Proposal Due Date / Time:	April 3, 2012	1:00 pm

---

PREVIOUS ADDENDUMS: 1, 2

---

**TO: Prospective Bid Proposers:**

This Addendum forms part of the "Contract Documents" and modifies or clarifies the original "Contract Documents" for this Project dated 9/28/11. Prospective Bid Proposers shall acknowledge receipt of the total number the Addenda issued for this Project on the space provided on Section 00 41 00 Bid Proposal Form. Failure to do may subject Bid Proposers to disqualification.

The following clarifications are applicable to drawings and specifications for the project referenced above.

**Item 1**

Delete Section 23 07 00 HVAC Insulation, in its entirety. No piping insulation is required because the tanks will not be used for #4 fuel oil.

**Item 2**

It has been brought to our attention that double poppet foot valves may not be readily available in the 3" size. For the 3" size foot valves, a single poppet foot valve equal to Preferred Utilities Model 60 Single Poppet Foot Valve is acceptable. Provide extractor as called for in drawings and specifications.

**Item 3**

**QUESTION:** Drawing M1 indicates no valves on return line. If first tank is returning oil, how does it know not to return oil to the second tank causing an overflow?

**ANSWER:** The mechanical code does not allow valves on return piping to oil tanks. The design in the bid documents relies on increased pressure in the tank with a higher fuel level to mitigate unequal return rates.

**Item 8**

**QUESTION:** How does cathodic protection work when tank does not come in contact with the ground?

**ANSWER:** Refer to industry publications. One example available online is at:  
<http://www.epa.gov/oem/docs/oil/fss/fss02/larypresent.pdf>

All questions must be in writing (not phone or e-mail) and must be forwarded to the consulting Architect/Engineer: Julia Weatherby @ Lindgren & Sharples, P.C. @ Fax Number 413 731 0786 with copies sent to the CT DCS Project Manager Wayne E. Thorpe @ 860 713 7261.

End of Addendum 3

Gail Blythe, Associate Fiscal Administrative Officer  
Department of Administrative Services  
On Behalf of the Department of Construction Services