

ADDENDUM NO.: 3

DATE OF ADDENDUM: 3/5/2014

**Sherwood Island State Park Main Pavilion Centennial Improvements
Sherwood Island State Park, Westport, CT
BI – T – 602**

Original Bid Due Date / Time:	2/26/2014	1:00 PM
Revised Bid Due Date / Time:	3/12/2014	1:00 PM

Previous Addendums: #1 2-11-2014; #2 2-19-2014

TO: Prospective Bid Proposers:

This Addendum forms part of the "Contract Documents" and modifies or clarifies the original "Contract Documents" for this Project dated 10/22/2013. Prospective Bid Proposers shall acknowledge receipt of the total number the Addenda issued for this Project on the space provided on Section 00 41 00 Bid Proposal Form. Failure to do may subject Bid Proposers to disqualification.

The following clarifications are applicable to drawings and specifications for the project referenced above.

Item 1

Specification Section 08 54 13: Delete Paragraph 2.2.E Windborne Debris Resistance in its entirety.

Item 2

1. On drawing E.001 (Light Fixture Schedule), revise lighting fixture type 'G' to be Gardco Model #121-EP2-3-50LA-2-3253-NW-120-NP-PCB
2. On drawing E.001 (Light Fixture Schedule), remove central 500W battery inverter noted for emergency fixture types 'A' and replaced with four smaller inverters. These inverters are wall mountable and shall be located near the lighting control panel in State Storage room 120. The lighting control relay panel shall provide an input to the inverters' line side switched input. See manufacturer's standard wiring diagrams for additional information. Inverters shall be provided as follows:
 - a. QTY (1) Evenlite 125VA unit to feed (1) Type AEM on Circuit 25,P1 (50W)
 - b. QTY (1) Evenlite 125VA unit to feed (2) Type AEM on Circuit 25,P1 (100W)
 - c. QTY (1) Evenlite 225VA unit to feed (3) Type AEM on Circuit 25,P1 (150W)
 - d. QTY (1) Evenlite 125VA unit to feed (2) Type AEM on Circuit 23,P1 (100W).

Item 3

1. Clarification: At Detail 1, Sheet A503, all horizontal mullions are per Detail 3B Sheet A503.
2. Clarification: Detail 1 Sheet A504, all vertical mullions are per Detail 2C on Sheet A503.
3. Clarification: Detail 2 Sheet A504, all vertical mullions are per Detail 2C on Sheet A503.

Item 4

1. Clarification: Removal/Storage/Reinstallation of the metal sculpture is by the State of Connecticut.

Item 5

1. Clarification: Picnic tables under the roof of the Pavilion shall be removed.
2. Specification Section 12 93 00: Remove Paragraph 2.6. in its entirety, and replace with the following:

ADDENDUM NO.: 3

DATE OF ADDENDUM: 3/5/2014

2.6 PICNIC TABLES

- A. Shall be Pilot Rock "Square Pedestal Tables" PQT Series, Model #PQT/P/B-3UP (2 seats), surface mount (Qty. 16) with galvanized frame and thermo-plastic coated top, as manufactured by R.J. Thomas Mfg. Co., Inc., Cherokee, IA. Color: Provide selections from manufacturer's full range of standard colors to Landscape Architect for color selection. Note: Tables shall be bolted in place with galvanized hardware after verification of arrangement by Owners Rep. and Landscape Architect
- B. Shall be Pilot Rock "Caterpillar" Series, Model #T602-6, surface mount (Qty. 30) with galvanized frame and thermo-plastic coated top, as manufactured by R.J. Thomas Mfg. Co., Inc., Cherokee, IA. Color: Provide selections from manufacturer's full range of standard colors to Landscape Architect for color selection. Note: Tables shall be bolted in place with galvanized hardware after verification of arrangement by Owners Rep. and Landscape Architect
- C. Shall be Pilot Rock "Caterpillar" Series, Model #T602-8, surface mount (Qty. 24) with galvanized frame and thermo-plastic coated top, as manufactured by R.J. Thomas Mfg. Co., Inc., Cherokee, IA. Color: Provide selections from manufacturer's full range of standard colors to Landscape Architect for color selection. Note: Tables shall be bolted in place with galvanized hardware after verification of arrangement by Owners Rep. and Landscape Architect
- D. Or Approved Equal, from DCS State Vendor Contract Award #11PSX0116 (Playground, Recreations and Park Equipment.)

3. Clarification: Tables and seats to have perforated steel H-Type tops.

Item 6

1. Clarification: Detail for concrete repair at removal of mounting hardware called out on Sheet L-110 is shown on Sheet S-301.

Item 7

1. Clarification: Reinforcement at new door openings shall be as described in Reinforced Masonry Notes on Sheet S-002.

All questions must be in writing (not phone or e-mail) and must be forwarded to the consulting Architect/Engineer (Ames & Whitaker Architects, 860-621-0957) with copies sent to the CT DCS Project Manager (Lee A. Rowley, 860-713-7270)

End of Addendum 3



Mellanee Walton, Associate Fiscal Administrative Officer
Department of Administrative Services
On Behalf of the Division of Construction Services