

ADDENDUM NO.: 2

DATE OF ADDENDUM: 06/24/2014

DESPP State Police
Troop L and Troop L Garage Re-Roofing
452A Bantam Road
Litchfield, CT
BI-N-334

Original Bid Due Date / Time:

July 2, 2014

1:00 PM

Previous Addendums:

Addendum No 1 dated June 20, 2014

TO: Prospective Bid Proposers:

This Addendum forms part of the "Contract Documents" and modifies or clarifies the original "Contract Documents" for this Project dated February 19, 2014. Prospective Bid Proposers shall acknowledge receipt of the total number the Addenda issued for this Project on the space provided on Section 00 41 00 Bid Proposal Form. Failure to do may subject Bid Proposers to disqualification.

The following clarifications are applicable to drawings and specifications for the project referenced above.

Item 1

CLARIFICATION: Existing roof construction (also noted in Specifications - Section 01 11 00):

Barracks (low slope roof):	EPDM roofing membrane ½-inch fiberboard 2.5-inch polyiso. insulation 3-inch metal deck.
Barracks (steep slope roof):	asphalt shingles felt underlayment plywood 9/16-inch metal form decking
Garage (low slope roof):	ballasted EPDM roofing membrane ½-inch fiberboard plywood prefabricated wood trusses
Garage (steep slope roof):	asphalt shingles felt underlayment plywood prefabricated wood trusses

Carport (steep slope): asphalt shingles
felt underlayment
plywood
wood trusses

Item 2

CLARIFICATION: Barracks - Contractor to assume all penetrations through the large roof hatch are to remain and to provide proper water-tight flashing as part of the reroofing project. Agency may choose to have abandoned items removed by the contractor. Resulting openings are to be made water-tight and properly flashed.

Item 3


CLARIFICATION: All DESPP wiring - DESPP and GC will coordinate. GC will be responsible for disconnecting, reconnecting, and coordinating with the DESPP representative.

Item 4

CLARIFICATION: As noted in Specification section 07 22 00, paragraph 1.1B:
Prior to start of mechanically fastening rigid insulation the Contractor to review the underside of the deck for any conduit, etc. which may be attached. Contractor shall not fasten through any conduit, etc. attached to the underside of the deck.

END OF ADDENDUM No. 2

All questions must be in writing (not phone or e-mail) and must be forwarded to the consulting Architect (Martin A. Benassi AIA Architect, Marguerite Petersen AIA, fax number 203.605.6072) with copies sent to the CT DCS Project Manager (Ward Ponticelli, RA, fax number 860.713.7261) and Construction Manager (NA).



Mellahee Walton, Associate Fiscal Administrative Officer
Department of Administrative Services
On Behalf of the Division of Construction Services