

ADDENDUM NO.: 7

DATE OF ADDENDUM: September 15, 2016

**Replacement of the Tile Roof on Galley Building
Cheshire Correctional Institution
900 Highland Avenue
Cheshire, CT
BI – JA – 471**

Original Bid Due Date / Time: September 14, 2016 1:00 PM

Revised Bid Due Date / Time: September 21, 2016 1:00 PM

Previous Addendums: Addendum #6 dated 9/12/2016, Addendum #5 dated 9/7/2016, Addendum #4 dated 8/22/2016, Addendum #3 dated 8/15/2016, Addendum #2 dated 8/12/2016, Addendum #1 dated 8/12/2016

TO: Prospective Bid Proposers:

This Addendum forms part of the "Contract Documents" and modifies or clarifies the original "Contract Documents" for this Project dated 3/21/2016. Prospective Bid Proposers shall acknowledge receipt of the total number the Addenda issued for this Project on the space provided on Section 00 41 00 Bid Proposal Form. Failure to do may subject Bid Proposers to disqualification.

The following clarifications are applicable to drawings and specifications for the project referenced above.

Item 1


Further Clarifications to Addendum #6 item #6.

1. Q: Please clarify the scope of work required by Section 211313 Wet Pipe Sprinkler System in the base bid. It appears that there is no sprinkler work to be included in our proposal, but there is a possibility that it will be added to the project during wood deck replacement.
A: 21 12 13, 1.03A requires, "The scope for Wet Pipe Sprinkler Systems is limited to the work required to remove components where supporting parts of the building are being removed, and reinstalling components after the removed building items have been replaced." This includes the sprinkler piping supported by Beams #1 & #2 to be installed the full width of the building underneath existing beams. Contractor shall include this work in the base bid. The three photos on S001 are included as part of addendum #6 and they show the associated sprinkler piping.

Due to potential unforeseen conditions encountered during roof deck removal and replacement, there is the possibility that existing sprinkler piping/support will require temporary disconnection and reconnection. Necessary sprinkler work associated with removal and replacement of roof decking will be carried as a project allowance. Include an Allowance per the attached Section 01 20 00 Contact Considerations for work required on sprinkler systems that has not yet been determined.

All questions must be in writing (not phone or e-mail) and must be forwarded to the consulting Architect/Engineer (Gale Consultants Inc. Fax No. 860-430-9072) with copies sent to the DCS Project Manager (Steven Udeh Fax No. 860-713-7264) and Construction Manager (TBD)

End of Addendum No. 7


Mellanee Walton, Associate Fiscal Administrative Officer
Department of Administrative Services
On Behalf of the Division of Construction Services