



Joette Katz  
Commissioner

**DEPARTMENT of CHILDREN and FAMILIES**  
*Making a Difference for Children, Families and Communities*



M. Jodi Rell  
Governor

**JJ Girls Program Building Modifications**

**Albert J Solnit Children's Center  
915 River Road  
Middletown, CT**

Project No. BI-YS-174 (28-CJTS-154)

**BID OPENING**

**2:00P.M.**

**DECEMBER 16, 2013**

**ADDENDUM NUMBER 2**

**DATE OF ADDENDUM:**

**DEC. 13, 2013**

*The following clarifications are applicable to Drawings and Specifications for the project referenced above:*

Item 1: Add SLAM clarifications (attached)

**This Addendum page must be Signed & Returned with your Bid acknowledging receipt.**

\_\_\_\_\_  
Authorized Signature of Bidder

\_\_\_\_\_  
Company Name

**STATE OF CONNECTICUT**  
Phone (860) 550-6669 - Fax (860) 560-5019  
505 Hudson Street, Hartford, Connecticut 06106-7107  
E-Mail: [richard.grossman@po.state.ct.us](mailto:richard.grossman@po.state.ct.us)  
[www.state.ct.us/dcf](http://www.state.ct.us/dcf)  
An Equal Opportunity Employer

SECTION 00 9111 – ADDENDUM No. 2

**JJ Girls Program Building Modifications  
915 River Road, Middletown, CT  
BI-YS-174**

**Project No. 12035.05**

---

This Addendum dated **December 12, 2013** forms a part of the Contract Documents and modifies the original Bidding Documents dated **November 22, 2013**. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

This Addendum is comprised of Page Nos. 1 of 1, and the following attachments:

**GENERAL:**

1. RFI 2 – “Drawings show masonry wall type M6 extending to the deck. New door frame head details indicates gypsum board assembly within the masonry wall. Please confirm the masonry wall should extend to the deck and that gypsum board assembly should be installed only above the door. GI01 existing ratings does not show 2hr assemblies between the common area and individual rooms.”
  - a. RESPONSE: Clarification - The existing walls between the Bedrooms and to the Common Area are CMU to the top of the door frames and gyp board above that to the underside of the deck. The new wall infill shall match this condition with CMU up the sides of the new frames to the same height as the existing masonry, gyp board infill above the CMU and above the new doors to the deck (or existing gyp wall if in the same plane). These CMU walls are not rated.

**END OF ADDENDUM No. 2**